HealthFirst Medico

Location 2328 Medico Lane, Melbourne, FL 32940 **Building** owner Program user **RLF** Company Comments Ву **RLF** Dataset name H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC Calculation time 05:19 PM on 04/11/2022 TRACE® 700 version 6.3.4 Location Melbourne, Florida Latitude 28.0 deg Longitude 80.0 deg Time Zone 5 Elevation 16 ft Barometric pressure 29.9 in. Hg 0.0760 lb/cu ft Air density 0.2444 Btu/lb·°F Air specific heat Btu/h·cfm·°F Density-specific heat product 1.1147 Latent heat factor 4,906.9 Btu·min/h·cu ft Enthalpy factor 4.5604 lb·min/hr·cu ft Summer design dry bulb 88.0 °F Summer design wet bulb 78.0 °F Winter design dry bulb 38.0 °F Summer clearness number 0.95 Winter clearness number 0.95 Summer ground reflectance 0.20 Winter ground reflectance 0.20 Carbon Dioxide Level 400 ppm Design simulation period January - December Cooling load methodology TETD-TA1 Heating load methodology **UATD**





ENTERED VALUES

ROOM BY ROOM

By RLF

Room Description: 117 BREAK ROOM

GENERAL INFORMATION

Floor Area: 185 ft² Flr-Flr Height: 12.0 ft
Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None

Room Type:Conditioned

Zone Description: Zone - 1-1-1

People Type: General Office Space

of People: 8 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

PEOPLE

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

System Description: AHU

AIRFLOW INFORMATION

CoolingHeatingVent Type:NoneNoneVent Value:0.00 cfm0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

								(Glass			Adj Temp/	Pct Sen/	Pct Rm/		Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl		Heat	Perm	Loss Coef
Roof - 1	200 ft ²	0	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
NORTH	250 ft ²	0	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Opening - 2			Door			90.1-13 Min Swinging	21	0.00	0.70	Overhang - None	None	0.00				
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)			None							100	100	0	60.00
Floor - 1															21	0.50

Project Name: HealthFirst Medico

Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC

SYSTEM ENTERED VALUES

By RLF

AHU - Variable Volume Reheat (30% Min Flow Default)

Cooling supply: Leaving cooling coil:		Supply duct temperature diff: 0.0 °F Reheat Temperature diff: 0.0 °F	Design humidity ratio diff: Min room relative humidity:				
Heating su	pply:						
dvanced Options							
Cooling coil sizing m	nethod: Block	Supply fan motor location: Supply	Night purge schedule: Off (0%)				
Cooling coil lo	cation: System	Return fan motor location: Return	Optimum start schedule: Off (0%)				
Block cooling a	airflow:	Supply fan cofiguration: Draw Thru	Optimum stop schedule: Off (0%)				
	cation: Return/Outdoor Deck	Supply fan sizing: Block					
	cation: Return Air	Fan mechanical efficiency: 75%	CO2-based DCV: None				
Return ai	ir path: PLENUM	Apply Std62 People Avg: No					
		Std62 Max Vent (Z) Ratio:	System ventilation flag: Sum Room OA Reqs				
Reset per worst case	e room schedule: Off (0%)		Supply air path / duct location: Return Air				
	Max reset:		Space convective gains to occupied layer: 100 %				
Use system default	outside air reset: Yes		Underfloor plenum height:				
,			Conductive resistance of raised floor: 0.8 hr·ft²-°F/Btu				
			Upstream nominal leakage fraction: 0 %				
			Downstream constant leakage fraction: 0 %				
(Control Method	Control Type	Aux cooling coil losses to plenum: 0 %				
Auxiliary cooling coil	Activate After Primary System	None					
, ,	Activate After Primary System	None					
	No Fan						

Coils	Capacity	Schedule	Diversity	
Main cooling:	100.0 % of Design Capacity by adjusting a	Available (100%)	People 100%	
Aux cooling		Available (100%)	Lights 100%	
Main heating:	100.0 % of Design Capacity	Available (100%)	Misc loads 100%	
Aux heating		Available (100%)		
Preheat	100.0% of Design Capacity	Available (100%)		
Reheat	100.0 % of Design Capacity	Available (100%)		
Humidification	100.0 % of Design Capacity	Available (100%)		

Fans	Туре	Static Press.	90.1 SP Adj	Full Load Energy Rate	Schedule	Efficiency	Priority
	Primary None	0.0 in. wg	0.0 in. wg	0.00000 kW	Available (100%)	90	
	Secondary None	0.0 in. wg	NA	0.00000 kW	Available (100%)	85	
	Return None	0.0 in. wg	0.0 in. wg	0.00000 kW	Available (100%)	90	
Syste	m Exhaust None	0.0 in. wg	0.0 in. wg	0.00000 kW	Available (100%)	90	
Rooi	m Exhaust None	0.0 in. wg	0.0 in. wg	0.00000 kW	Available (100%)	85	
Optional	ventilation None	0.0 in. wg	NA	0.00000 kW	Available (100%)	90	
	Auxiliary None	0.0 in. wg	NA	0.00000 kW	Available (100%)	85	
F	an Cycling				Cycle with occupancy 0.0 ft		

Project Name: HealthFirst Medico

Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC

Entered Values

TRACE® 700 version 6.3.4

By RLF

Project Name: HealthFirst Medico

Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC

Location: 2328 Medico Lane, Melbourne, FL 32940

Building Owner:
Program User:
Company: RLF
Comments:

Cooling Design Period: January thru December Location: Melbourne, Florida

Peak Hour Override: 0 Summer Design Dry Bulb: 88.00 °F
Daylight Savings Period: Summer Design Wet Bulb: 78.00 °F
Summer Period: Winter Design Dry Bulb: 38.00 °F

Cooling Methodology: TETD-TA1 Summer Clearness Number: 0.95
Heating Methodology: UATD Winter Clearness Number: 0.95

Infiltration Methodology: Vary with wind speed
Outside Film Methodology: Vary with wind speed
Terrain Methodology: Center of a large city

Vary with wind speed
Vary with wind sp

Carbon Dioxide Level: 400 ppm

Room Circ Rate: Medium

Wall Load To Plenum: YES

Building Orientation: 0 degrees from north

Force VAV Min => Nominal Ventilation at Design: No
Allow Energy Recovery/Transfer at Design: No

Retest Design Peaks: Yes
Simulation Hours: Reduced year Calculate Building Block Loads: No

Calendar Code: Standard (1978)

Energy Simulation Period: January thru December Close ventilation dampers during unoccupied hours: Yes

Project Name: HealthFirst Medico
Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC

System Checksums By RLF

AHU

Variable Volume Reheat (30% Min Flow Default)

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/F OADB/WB/H	Hr: 8 / 16 R: 87 / 78 / 1	30	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	t contract to the contract of	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0		0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	11,566	11,566	9	0	0	,	0	-4,631	8.12
Glass Solar	7,738	0	7,738	6 ;	8,755	11		0	0	0.00
Glass/Door Cond	2,962	0	2,962	2:	2,595	3		-7,438	-7,438	13.03
Wall Cond	14,730	5,924	20,654	17 ;	16,248	20	-	-6,491	-9,035	15.83
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-3,889	-3,889	6.81
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	23,536		23,536	19	4,704	6	•	-14,337	-14,337	25.12
Sub Total ==>	48,966	17,490	66,456	53	32,303	39	Sub Total ==>	-32,155	-39,329	68.92
Internal Loads							Internal Loads			
Lights	9,665	2,416	12,081	10	9,665	12	Lights	0	0	0.00
People	27,900	0	27,900	22	15,500	19	People	0	0	0.00
Misc	20,000	0	20,000	16	20,000	24	Misc	0	0	0.00
Sub Total ==>	57,565	2,416	59,981	48	45,165	55	Sub Total ==>	0	0	0.00
Ceiling Load	5,267	-5,267	0	0	4,978	6	Ceiling Load	-3,346	0	0.00
Ventilation Load	0	0	0	0 :	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		Ô	0	0	0	Exhaust Heat		1,060	-1.86
Exhaust Heat	· ·	-1,668	-1,668	-1	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		1,000	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		-18,798	32.94
Duct Heat Pkup		0	0	0					-,	
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	111,798	12,972	124,770	100.00	82,446	100.00	Grand Total ==>	-35,501	-57,068	100.00

TEMPERATURES								
	Cooling Heating							
SADB	51.6	100.3						
Ra Plenum	78.7	67.6						
Return	78.7	67.6						
Ret/OA	78.7	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRF	AIRFLOWS								
	Cooling	Heating							
Diffuser	3,158	1,050							
Terminal Main Fan	3,158 3,158	1,050 1,050							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	402	402							
MinStop/Rh	1,050	1,050							
Return	3,560	1,452							
Exhaust	402	402							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
	Cooling	Heating					
% OA	0.0	0.0					
cfm/ft²	0.71	0.24					
cfm/ton	303.74						
ft²/ton	429.50						
Btu/hr·ft²	27.94	-12.78					
No. People	62						

COOLING COIL SELECTION										
		•					Leave DB/WB/HR °F °F gr/lb			
10.4	124.8	94.2	3,112	78.7	63.9	65.0	51.6	50.0	51.1 0.0	
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
10.4	124.8									
	ton 10.4 0.0 0.0	10.4 124.8 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. 10.4 124.8 94.2 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm 10.4 124.8 94.2 3,112 0.0 0.0 0.0 0 0.0 0.0 0 0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Ent °F 10.4 124.8 94.2 3,112 78.7 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Enter DB/W 10.4 124.8 94.2 3,112 78.7 63.9 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Enter DB/WB/HR 10.4 124.8 94.2 3,112 78.7 63.9 65.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Enter DB/WB/HR Lear PB/WB/HR PB/WB/HR Lear PB/WB/HR Lear	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Enter DB/WB/HR Leave DB/ °F 10.4 124.8 94.2 3,112 78.7 63.9 65.0 51.6 50.0 0.0 </td	

	AREA	S	
	Gross Total	Glas	-
		ft²	(%)
Floor	4,466		
Part	0		
Int Door	0		
ExFlr	243		
Roof	4,977	0	0
Wall	2,414	313	13
Ext Door	r 84	0	0

HEA	HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-57.1	1,050	51.6	100.3						
Aux Htg	0.0	0	0.0	0.0						
Preheat	0.0	,	0.0	0.0						
Reheat	-21.6		51.6	70.0						
Humidif Opt Vent	0.0 0.0	0	0.0	0.0						
Total	-57.1									

Room Checksums

By RLF

100 LOBBY

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HI	lr: 10 / 14 R: 82 / 72 / 1	02	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	I
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	1,209	1,209	6	0	0	Roof Cond	0	-423	5.50
Glass Solar	1,405	0	1,405	7 ;	1,830	13		0	0	0.00
Glass/Door Cond	121	0	121	1;	-10	0	Glass/Door Cond	-590	-590	7.66
Wall Cond	6,589	2,352	8,940	45 :	7,147	51		-1,479	-1,980	25.74
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0.00	0		-657	-657	8.53
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,262		1,262	6 ;	-4	0	Infiltration	-1,348	-1,348	17.52
Sub Total ==>	9,377	3,561	12,937	65	8,963	64	Sub Total ==>	-4,074	-4,998	64.96
Internal Loads							Internal Loads			
Lights	917	229	1,147	6	917	7	Lights	0	0	0.00
People	5,400	0	5,400	27	3,000	21		0	0	0.00
Misc	717	0	717	4	717	5	Misc	0	0	0.00
Sub Total ==>	7,034	229	7,263	36	4,634	33	Sub Total ==>	0	0	0.00
Ceiling Load	472	-472	0	0	415	3	Ceiling Load	-315	0	0.00
Ventilation Load	0	0	0	0	0	_	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	ŭ	0	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		100	-1.30
Exhaust Heat	ŭ	-149	-149	-1	ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-2,882	37.45
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		86	-1.12
Underfir Sup Ht Pkuj	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	16,883	3,168	20,051	100.00	14,012	100.00	Grand Total ==>	-4,388	-7,694	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	94.5					
Ra Plenum	78.6	67.6					
Return	78.6	67.6					
Ret/OA	78.6	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS									
Cooling Heating									
Diffuser	537	161							
Terminal Main Fan	537 537	161 161							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	38	38							
MinStop/Rh	161	161							
Return	575	199							
Exhaust	38	38							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.28	0.38					
cfm/ton	321.21						
ft²/ton	251.36						
Btu/hr·ft²	47.74	-18.32					
No. People	12.0	28.6/1000 ft ²					

COOLING COIL SELECTION										
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	1.7 0.0	20.1 0.0	16.7 0.0	517 0	78.6 0.0	63.8 0.0	65.0 0.0	51.6 0.0	50.4 0.0	52.6 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.7	20.1								

	AREAS			
G	Gross Total	Glas:	s (%)	
			(70)	
Floor	420			1
Part	0			1
Int Door	0			F
ExFlr	41			F
Roof	455	0	0	H
Wall	492	33	7	(
Ext Door	0	0	0	7

HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-7.7	161	51.6	94.5					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	0	0.0	0.0					
Reheat	-3.3	161	51.6	70.0					
Humidif Opt Vent <i>Total</i>	0.0 0.0 -7.7	0	0.0	0.0					

By RLF

Zone - 1-1-1

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 17 R: 87 / 78 / 1	32	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads						(/	Envelope Loads			(/
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	703	703	6	0	0	Roof Cond	0	-305	5.67
Glass Solar	341	0	341	3	373	5	Glass Solar	0	0	0.00
Glass/Door Cond	411	0	411	4	364	5	Glass/Door Cond	-1,049	-1,049	19.49
Wall Cond	2,445	911	3,356	31 ;	2,617	38	Wall Cond	-1,204	-1,649	30.65
Partition/Door	0		0	0:	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-583	-583	10.83
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,238		1,238	11	232	3	Infiltration	-735	-735	13.67
Sub Total ==>	4,434	1,614	6,049	56	3,586	52	Sub Total ==>	-3,570	-4,320	80.32
Internal Loads							Internal Loads			
Lights	500	125	625	6	500	7	Lights	0	0	0.00
People	3,600	0	3,600	33	2,000	29	People	0	0	0.00
Misc	631	0	631	6	631	9		0	0	0.00
Sub Total ==>	4,732	125	4,857	45	3,132	45	Sub Total ==>	0	0	0.00
Ceiling Load	252	-252	0	0	221	3	Ceiling Load	-172	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	O	· ·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	٥	Exhaust Heat	· ·	54	-1.01
Exhaust Heat	U	-80	-80	-1	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0;			Additional Reheat		-1,427	26.53
Duct Heat Pkup		0	0	0:			System Plenum Heat		314	-5.84
Underfir Sup Ht Pku	q	,	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	Ρ.	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	9,418	1,407	10,825	100.00	6,938	100.00	Grand Total ==>	-3,742	-5,379	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	112.1						
Ra Plenum	78.5	67.6						
Return	78.5	67.6						
Ret/OA	78.5	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS										
Cooling Heating										
Diffuser	266	80								
Terminal Main Fan	266 266	80 80								
Sec Fan	0	0								
Nom Vent	0	0								
AHU Vent	0	0								
Infil	21	21								
MinStop/Rh	80	80								
Return	286	100								
Exhaust	21	21								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.16	0.35					
cfm/ton	294.60						
ft²/ton	253.85						
Btu/hr·ft²	47.27	-23.49					
No. People	8						

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E nt °F	ter DB/W	/B/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	0.9 0.0	10.8 0.0	8.3 0.0	262 0	78.5 0.0	63.8 0.0	65.0 0.0	51.6 0.0	49.4 0.0	49.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.9	10.8								

	AREA	AS		Н
	Gross Total	Glas	-	
		ft²	(%)	
Floor	229			Main Htg
Part	0			Aux Htg
Int Door	. 0			Preheat
ExFlr	36			Reheat
Roof	328	0	0	Humidif
Wall	416	33	8	Opt Vent
Ext Doo	or 21	0	0	Total

HEA ⁻	TING COIL	SELECTIO	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-5.4	80	51.6	112.1
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-1.6	80	51.6	70.0
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0
Total	-5.4			

Load / Airflow Summary

By RLF

System	Zone Room **		Floor Area ft²	People #	Coil Cooling Sensible Btu/h	Coil Cooling Total Btu/h	Space Design Max SA cfm	Air Changes ach/hr	VAV Minimum SA cfm	VAV Minimum %	Main Coil Heating Sensible Btu/h	Heating Fan Max SA cfm	Pero O	
Alterna	tive 1													
	117 BREAK ROOM	Rm Peak	185	8.0	5,549	7,934	192	6.90	57	30	-3,881	0	0.0	0.0
	118 S TLT	Rm Peak	44	0.0	2,730	2,903	74	11.24	22	30	-1,498	0	0.0	0.0
	Zone - 1-1-1	Zn Peak	229	8.0	8,279	10,837	266			30	-5,379	0	0.0	0.0
	Zone - 1-1-1	Zn Block	229	8.0	8,254	10,825	266			30	-5,379	0	0.0	0.0
	119 CONF/CONSULT	Rm Peak	102	4.0	4,546	5,769	149	9.72	45	30	-2,042	0	0.0	0.0
	120 PROVIDER OFF	Rm Peak	113	2.0	4,184	5,054	132	7.77	40	30	-1,983	0	0.0	0.0
	Zone - 1-1-2	Zn Peak	215	6.0	8,730	10,823	280			30	-4,026	0	0.0	0.0
	Zone - 1-1-2	Zn Block	215	6.0	8,730	10,823	280			30	-4,026	0	0.0	0.0
	111 TEAM STATION	Rm Peak	150	4.0	2,427	3,870	85	3.79	26	30	-1,119	0	0.0	0.0
	125 TEAM STATION	Rm Peak	198	6.0	3,434	5,482	119	4.02	36	30	-1,519	0	0.0	0.0
	126 B TLT	Rm Peak	198	0.0	1,029	1,878	36	1.21	11	30	-1,006	0	0.0	0.0
	129 CORR CENTRAL	Rm Peak	125	0.0	760	1,294	23	1.21	7	30	-867	0	0.0	0.0
	130 CORR	Rm Peak	99	0.0	604	1,028	18	1.21	5	30	-503	0	0.0	0.0
	131 CORR	Rm Peak	224	0.0	1,366	2,326	41	1.21	12	30	-1,138	0	0.0	0.0
	132 CORR NORTH	Rm Peak	113	0.0	741	1,227	21	1.21	6	30	-664	0	0.0	0.0
	Zone - 1-1-3	Zn Peak	1,107	10.0	10,360	17,105	342			30	-6,815	0	0.0	0.0
	Zone - 1-1-3	Zn Block	1,107	10.0	10,360	17,105	342			30	-6,815	0	0.0	0.0
	121 EXAM ROOM 10	Rm Peak	116	2.0	5,897	6,779	192	11.03	58	30	-2,709	0	0.0	0.0
	122 EXAM ROOM 9	Rm Peak	116	2.0	5,649	6,531	185	10.62	55	30	-2,610	0	0.0	0.0
	123 EXAM ROOM 8	Rm Peak	116	2.0	4,882	5,764	156	8.94	47	30	-2,205	0	0.0	0.0
	124 MECH	Rm Peak	41	0.0	3,005	3,014	88	14.31	26	30	-1,426	0	0.0	0.0
	Zone - 1-1-4	Zn Peak	389	6.0	19,433	22,088	620			30	-8,950	0	0.0	0.0
	Zone - 1-1-4	Zn Block	389	6.0	17,964	20,643	575			32	-8,950	0	0.0	0.0
	100 LOBBY	Rm Peak	420	12.0	16,667	20,051	537	8.52	161	30	-7,694	0	0.0	0.0
	101 W TLT	Rm Peak	47	0.0	308	497	9	1.21	3	30	-239	0	0.0	0.0
	102 M TLT	Rm Peak	47	0.0	308	497	9	1.21	3	30	-239	0	0.0	0.0
	Zone - 1-2-1	Zn Peak	514	12.0	17,422	21,185	554			30	-8,172	0	0.0	0.0
	Zone - 1-2-1	Zn Block	514	12.0	17,364	20,968	548			30	-8,172	0	0.0	0.0
	113 ELEC	Rm Peak	55	0.0	1,095	1,316	35	4.28	11	30	-736	0	0.0	0.0
	114 EVS	Rm Peak	57	0.0	1,154	1,396	38	4.42	11	30	-1,269	0	0.0	0.0
	115 SOIL	Rm Peak	56	0.0	668	893	19	2.30	6	30	-595	0	0.0	0.0
	116 MANAGER OFF	Rm Peak	102	2.0	2,123	2,955	71	4.63	21	30	-1,822	0	0.0	0.0
	Zone - 1-2-2	Zn Peak	270	2.0	5,039	6,560	163			30	-4,423	0	0.0	0.0
	Zone - 1-2-2	Zn Block	270	2.0	4,972	6,518	163			30	-4,423	0	0.0	0.0
	109 PROVIDER OFF	Rm Peak	117	2.0	2,826	3,722	96	5.46	29	30	-2,212	0	0.0	0.0

^{*} This report does not display heating only systems.

Project Name: HealthFirst Medico

Dataset Name: 21184.TRC

PEAK COOLING LOADS

MAIN SYSTEM

By RLF

SPACE COIL

					C)A	Room	Supply	Space	Space	Space		0	A			Coil	Coil
			Floor	Peak	Con	dition	Dry	Dry	Air	Sensible	Latent	Peak	Conc	lition	Supply	Coil	Sensible	Latent
			Area	Time	DB	WB	Bulb	Bulb	Flow	Load	Load	Time	DB	WB	Dry Bulb	Airflow	Load	Load
System	Zone Room		ft²	Mo/Hr	°F	°F	°F	°F	cfm	Btu/h	Btu/h	Mo/Hr	°F	°F	°F	cfm	Btu/h	Btu/h
Alterna	ative 1																	
	117 BREAK ROOM	Peak	185	7/18	85	77	75.0	51.6	192	5,001	2,328	7 /17	87	78	51.6	191	5,549	2,385
	118 S TLT	Peak	44	7/18	85	77	75.0	51.6	74	1,937	173	7 /18	85	77	51.6	74	2,730	173
	Zone - 1-1-1	Peak	229		85	77	75.0	51.6	266	6,938	2,501		87	78	51.6	265	8,279	2,558
	Zone - 1-1-1	Block	229	7/18	85	77	75.0	51.6	266	6,938	2,501	7 /17	87	78	51.6	262	8,254	2,572
	119 CONF/CONSULT	Peak	102	8/17	86	78	75.0	51.6	149	3,883	1,224	8 /17	86	78	51.6	149	4,546	1,224
	120 PROVIDER OFF	Peak	113	8/17	86	78	75.0	51.6	132	3,438	869	8 /17	86	78	51.6	132	4,184	869
	Zone - 1-1-2	Peak	215		86	78	75.0	51.6	280	7,321	2,093		86	78	51.6	280	8,730	2,093
	Zone - 1-1-2	Block	215	8/17	86	78	75.0	51.6	280	7,321	2,093	8 /17	86	78	51.6	280	8,730	2,093
	111 TEAM STATION	Peak	150	7/15	88	78	75.0	51.6	85	2,224	1,403	7 /16	88	78	51.6	85	2,427	1,443
	125 TEAM STATION	Peak	198	7/15	88	78	75.0	51.6	119	3,115	1,996	7 /16	88	78	51.6	119	3,434	2,049
	126 B TLT	Peak	198	7/15	88	78	75.0	51.6	36	939	796	7 /16	88	78	51.6	35	1,029	849
	129 CORR CENTRAL	Peak	125	7/15	88	78	75.0	51.6	23	591	501	7 /16	88	78	51.6	22	760	534
	130 CORR	Peak	99	7/15	88	78	75.0	51.6	18	470	398	7 /16	88	78	51.6	18	604	424
	131 CORR	Peak	224	7/15	88	78	75.0	51.6	41	1,063	901	7 /16	88	78	51.6	40	1,366	960
	132 CORR NORTH	Peak	113	7/15	88	78	75.0	51.6	21	538	456	7 /16	88	78	51.6	20	741	486
	Zone - 1-1-3	Peak	1,107		88	78	75.0	51.6	342	8,939	6,452		88	78	51.6	338	10,360	6,745
	Zone - 1-1-3	Block	1,107	7/15	88	78	75.0	51.6	342	8,939	6,452	7 /16	88	78	51.6	338	10,360	6,745
	121 EXAM ROOM 10	Peak	116	8/17	86	78	75.0	51.6	192	5,011	882	8 /17	86	78	51.6	192	5,897	882
	122 EXAM ROOM 9	Peak	116	8/17	86	78	75.0	51.6	185	4,825	882	8 /17	86	78	51.6	185	5,649	882
	123 EXAM ROOM 8	Peak	116	8/17	86	78	75.0	51.6	156	4,060	882	8 /17	86	78	51.6	156	4,882	882
	124 MECH	Peak	41	12/14	69	60	75.0	51.6	88	2,298	-5	11 /14	75	63	51.6	87	3,005	9
	Zone - 1-1-4	Peak	389		84	76	75.0	51.6	620	16,194	2,640		84	76	51.6	620	19,433	2,655
	Zone - 1-1-4	Block	389	9/17	84	76	75.0	51.6	575	15,002	2,679	9 /17	84	76	51.6	575	17,964	2,679
	100 LOBBY	Peak	420	11/14	75	63	75.0	51.6	537	14,012	2,494	10 /14	82	72	51.6	517	16,667	3,385
	101 W TLT	Peak	47	7/15	88	78	75.0	51.6	9	223	189	7 /15	88	78	51.6	9	308	189
	102 M TLT	Peak	47	7/15	88	78	75.0	51.6	9	223	189	7 /15	88	78	51.6	9	308	189
	Zone - 1-2-1	Peak	514		75	63	75.0	51.6	554	14,458	2,872		82	72	51.6	534	17,422	3,763
	Zone - 1-2-1	Block	514	11/14	75	63	75.0	51.6	548	14,309	2,515	10 /14	82	72	51.6	537	17,364	3,605
	113 ELEC	Peak	55	6/18	81	73	75.0	51.6	35	921	156	7 /15	88	78	51.6	35	1,095	221
	114 EVS	Peak	57	6/18	81	73	75.0	51.6	38	986	161	7 /17	87	78	51.6	37	1,154	242
	115 SOIL	Peak	56	7/15	88	78	75.0	51.6	19	505	225	7 /15	88	78	51.6	19	668	225
	116 MANAGER OFF	Peak	102	7/18	85	77	75.0	51.6	71	1,850	801	7 /17	87	78	51.6	71	2,123	833
	Zone - 1-2-2	Peak	270		85	77	75.0	51.6	163	4,263	1,343		87	78	51.6	163	5,039	1,521
	Zone - 1-2-2	Block	270	7/18	85	77	75.0	51.6	163	4,253	1,462	7 /17	87	78	51.6	162	4,972	1,545

Project Name: HealthFirst Medico

Dataset Name: 21184.TRC

PEAK HEATING LOADS

MAIN SYSTEM

By RLF

OA Condition DB WB

Peak Time °F °F					SPAC	E		COIL	
Htg Design 38 27	Block	Floor	Room Dry	Supply Dry	Space Air	Space Sensible	Supply Dry	Coil Air	Coil Sensible
	or	Area	Bulb	Bulb	Flow	Load	Bulb	Flow	Load
System Zone Room	Peak	ft²	°F	°F	cfm	Btu/h	°F	cfm	Btu/h
Alternative 1									
117 BREAK ROOM	Peak	185	70.0	112.2	57	-2,701	112.2	57	-3,881
118 S TLT	Peak	44	70.0	112.0	22	-1,041	112.0	22	-1,498
Zone - 1-1-1	Peak	229	70.0	112.1	80	-3,742	112.1	80	-5,379
Zone - 1-1-1	Block	229	70.0	112.1	80	-3,742	112.1	80	-5,379
119 CONF/CONSULT	Peak	102	70.0	92.6	45	-1,126	92.6	45	-2,042
120 PROVIDER OFF	Peak	113	70.0	96.6	40	-1,172	96.6	40	-1,983
Zone - 1-1-2	Peak	215	70.0	94.5	84	-2,299	94.5	84	-4,026
Zone - 1-1-2	Block	215	70.0	94.5	84	-2,299	94.5	84	-4,026
111 TEAM STATION	Peak	150	70.0	90.9	26	-594	90.9	26	-1,119
125 TEAM STATION	Peak	198	70.0	89.6	36	-784	89.6	36	-1,519
126 B TLT	Peak	198	70.0	135.2	11	-784	135.2	11	-1,006
129 CORR CENTRAL	Peak	125	70.0	166.1	7	-728	166.1	7	-867
130 CORR	Peak	99	70.0	135.1	5	-392	135.1	5	-503
131 CORR	Peak	224	70.0	135.2	12	-887	135.2	12	-1,138
132 CORR NORTH	Peak	113	70.0	147.9	6	-537	147.9	6	-664
Zone - 1-1-3	Peak	1,107	70.0	111.1	103	-4,706	111.1	103	-6,815
Zone - 1-1-3	Block	1,107	70.0	111.1	103	-4,706	111.1	103	-6,815
121 EXAM ROOM 10	Peak	116	70.0	93.8	58	-1,527	93.8	58	-2,709
122 EXAM ROOM 9	Peak	116	70.0	93.8	55	-1,471	93.8	55	-2,610
123 EXAM ROOM 8	Peak	116	70.0	94.0	47	-1,247	94.0	47	-2,205
124 MECH	Peak	41	70.0	100.0	26	-884	100.0	26	-1,426
Zone - 1-1-4	Peak	389	70.0	94.7	186	-5,129	94.7	186	-8,950
Zone - 1-1-4	Block	389	70.0	94.7	186	-5,129	94.7	186	-8,950
100 LOBBY	Peak	420	70.0	94.4	161	-4,388	94.4	161	-7,694
101 W TLT	Peak	47	70.0	135.1	3	-186	135.1	3	-239
102 M TLT	Peak	47	70.0	135.1	3	-186	135.1	3	-239
Zone - 1-2-1	Peak	514	70.0	95.7	166	-4,761	95.7	166	-8,172
Zone - 1-2-1	Block	514	70.0	95.7	166	-4,761	95.7	166	-8,172
113 ELEC	Peak	55	70.0	114.0	11	-519	114.0	11	-736
114 EVS	Peak	57	70.0	152.0	11	-1,036	152.0	11	-1,269
115 SOIL	Peak	56	70.0	143.5	6	-476	143.5	6	-595
116 MANAGER OFF	Peak	102	70.0	128.5	21	-1,386	128.5	21	-1,822
Zone - 1-2-2	Peak	270	70.0	132.6	49	-3,417	132.6	49	-4,423

at Space Peak

By RLF

Alternative 1

			WA	LL		WINDOW						
		Plenum	Plenum	Space	Space	Space	Plenum		Space	Space	Plenum	Plenum
		Load	CLTD	Load	CLTD	Solar	Solar	Solar	Conduction	CLTD	Conduction	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	CLF	Btu/h	°F	Btu/h	°F
117 BREAK ROOM		378	44.0	863	47.1	373	0	0.932	364	10.9	0	0.0
118 S TLT		565	87.9	1,754	90.9	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-1	Zn Tot/Ave	943	62.8	2,617	69.6	373	0	0.932	364	10.9	0	0.0
Zone - 1-1-1	Zn Block	985	65.6	2,617	69.6	373	0	0.932	364	10.9	0	0.0
119 CONF/CONSULT		547	147.5	1,337	150.9	992	0	0.970	109	11.6	0	0.0
120 PROVIDER OFF		550	147.5	1,344	150.9	992	0	0.970	109	11.6	0	0.0
Zone - 1-1-2	Zn Tot/Ave	1,097	147.5	2,681	150.9	1,985	0	0.970	218	11.6	0	0.0
Zone - 1-1-2	Zn Block	1,097	147.5	2,681	150.9	1,985	0	0.970	218	11.6	0	0.0
111 TEAM STATION		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
125 TEAM STATION		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
126 B TLT		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
129 CORR CENTRAL		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
I30 CORR		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
131 CORR		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
132 CORR NORTH		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Tot/Ave	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Block	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
121 EXAM ROOM 10		682	147.5	1,407	150.9	1,985	0	0.970	218	11.6	0	0.0
122 EXAM ROOM 9		621	147.5	1,221	150.9	1,985	0	0.970	218	11.6	0	0.0
123 EXAM ROOM 8		619	147.5	1,557	150.9	992	0	0.970	109	11.6	0	0.0
124 MECH		558	150.8	1,358	153.6	994	0	0.920	-66	-7.0	0	0.0
Zone - 1-1-4	Zn Tot/Ave	2,479	148.2	5,543	151.5	5,956	0	0.962	480	8.5	0	0.0
Zone - 1-1-4	Zn Block	2,189	130.9	4,883	133.5	5,355	0	0.953	566	10.0	0	0.0
100 LOBBY		2,563	151.5	7,147	154.6	1,830	0	0.899	-10	-0.5	0	0.0
101 W TLT		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
102 M TLT		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-1	Zn Tot/Ave	2,563	151.5	7,147	154.6	1,830	0	0.899	-10	-0.5	0	0.0
Zone - 1-2-1	Zn Block	2,563	151.5	7,147	154.6	1,830	0	0.899	-10	-0.5	0	0.0
113 ELEC		106	47.6	339	50.5	0	0	0.000	0	0.0	0	0.0
114 EVS		129	47.6	182	50.5	461	0	0.925	128	6.8	0	0.0
115 SOIL		72	38.4	240	42.3	0	0	0.000	0	0.0	0	0.0
116 MANAGER OFF		176	44.0	350	47.1	373	0	0.932	204	10.8	0	0.0
Zone - 1-2-2	Zn Tot/Ave	483	44.7	1,110	47.5	834	0	0.928	332	8.8	0	0.0

Project Name: Dataset Name:

21184.TRC

at Space Peak

By RLF

Alternative 1

			WA	LL					WINDOW -			
		Plenum	Plenum	Space	Space	Space	Plenum		Space	Space	Plenum	Plenum
		Load	CLTD	Load	CLTD	Solar	Solar	Solar	Conduction	CLTD	Conduction	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	CLF	Btu/h	°F	Btu/h	°F
117 BREAK ROOM		-254	-29.6	-586	-32.0	0	0	0.000	-1,049	-30.7	0	0.0
118 S TLT		-191	-29.6	-617	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-1	Zn Tot/Ave	-445	-29.6	-1,204	-32.0	0	0	0.000	-1,049	-30.7	0	0.0
Zone - 1-1-1	Zn Block	-445	-29.6	-1,204	-32.0	0	0	0.000	-1,049	-30.7	0	0.0
119 CONF/CONSULT		-110	-29.6	-284	-32.0	0	0	0.000	-295	-30.7	0	0.0
120 PROVIDER OFF		-110	-29.6	-285	-32.0	0	0	0.000	-295	-30.7	0	0.0
Zone - 1-1-2	Zn Tot/Ave	-220	-29.6	-569	-32.0	0	0	0.000	-590	-30.7	0	0.0
Zone - 1-1-2	Zn Block	-220	-29.6	-569	-32.0	0	0	0.000	-590	-30.7	0	0.0
111 TEAM STATION		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
125 TEAM STATION		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
126 B TLT		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
129 CORR CENTRAL		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
130 CORR		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
131 CORR		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
132 CORR NORTH		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Tot/Ave	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Block	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
121 EXAM ROOM 10		-137	-29.6	-299	-32.0	0	0	0.000	-590	-30.7	0	0.0
122 EXAM ROOM 9		-125	-29.6	-259	-32.0	0	0	0.000	-590	-30.7	0	0.0
123 EXAM ROOM 8		-124	-29.6	-330	-32.0	0	0	0.000	-295	-30.7	0	0.0
124 MECH		-110	-29.6	-283	-32.0	0	0	0.000	-295	-30.7	0	0.0
Zone - 1-1-4	Zn Tot/Ave	-496	-29.6	-1,171	-32.0	0	0	0.000	-1,769	-30.7	0	0.0
Zone - 1-1-4	Zn Block	-496	-29.6	-1,171	-32.0	0	0	0.000	-1,769	-30.7	0	0.0
100 LOBBY		-501	-29.6	-1,479	-32.0	0	0	0.000	-590	-30.7	0	0.0
101 W TLT		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
102 M TLT		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-1	Zn Tot/Ave	-501	-29.6	-1,479	-32.0	0	0	0.000	-590	-30.7	0	0.0
Zone - 1-2-1	Zn Block	-501	-29.6	-1,479	-32.0	0	0	0.000	-590	-30.7	0	0.0
113 ELEC		-66	-29.6	-214	-32.0	0	0	0.000	0	0.0	0	0.0
114 EVS		-80	-29.6	-115	-32.0	0	0	0.000	-590	-30.7	0	0.0
115 SOIL		-56	-29.6	-181	-32.0	0	0	0.000	0	0.0	0	0.0
116 MANAGER OFF		-118	-29.6	-238	-32.0	0	0	0.000	-590	-30.7	0	0.0
Zone - 1-2-2	Zn Tot/Ave	-321	-29.6	-749	-32.0	0	0	0.000	-1,179	-30.7	0	0.0
Zone - 1-2-2	Zn Block	-321	-29.6	-749	-32.0	0	0	0.000	-1,179	-30.7	0	0.0
109 PROVIDER OFF		-157	-29.6	-363	-32.0	0	0	0.000	-590	-30.7	0	0.0
112 POC		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
129 CORR NORTH		-112	-29.6	-271	-32.0	0	0	0.000	-459	-31.2	0	0.0
Zone - 1-2-3	Zn Tot/Ave	-269	-29.6	-634	-32.0	0	0	0.000	-1,049	-30.9	0	0.0

at Space Peak

By RLF

	Ī	WALL							WINDOW -			
		Plenum	Plenum	Space	Space	Space	Plenum		Space	Space	Plenum	Plenum
		Load	CLTD	Load	CLTD	Solar	Solar	Solar	Conduction	CLTD	Conduction	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	CLF	Btu/h	°F	Btu/h	°F
Zone - 1-2-3	Zn Block	-269	-29.6	-634	-32.0	0	0	0.000	-1,049	-30.7	0	0.0
105 EXAM ROOM 2		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
106 EXAM ROOM 3		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
107 EXAMS ROOM 4		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
108 EXAM ROOM 5		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Tot/Ave	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Block	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
103 RECEPTION/SCHEDULING		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
110 EXAM ROOM 6		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
127 CLEAN STORAGE		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
128 COMM		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
132 CORR SOUTH		-67	-29.6	-145	-32.0	0	0	0.000	-295	-30.7	0	0.0
Zone - 1-2-5	Zn Tot/Ave	-67	-29.6	-145	-32.0	0	0	0.000	-295	-30.7	0	0.0
Zone - 1-2-5	Zn Block	-67	-29.6	-145	-32.0	0	0	0.000	-295	-30.7	0	0.0
104 EXAM ROOM 1		-157	-29.6	-324	-32.0	0	0	0.000	-918	-31.2	0	0.0
129 CORR SOUTH		-67	-29.6	-218	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-6	Zn Tot/Ave	-224	-29.6	-541	-32.0	0	0	0.000	-918	-31.2	0	0.0
Zone - 1-2-6	Zn Block	-224	-29.6	-541	-32.0	0	0	0.000	-918	-31.2	0	0.0
AHU	Sys Tot/Ave	-2,543	-29.6	-6,491	-32.0	0	0	0.000	-7,438	-30.8	0	0.0
AHU	Sys Block	-2,543	-29.6	-6,491	-32.0	0	0	0.000	-7,438	-30.7	0	0.0

at Space Peak

By RLF

			— ROC)F		SKYLIGHT						
		Plenum		Space					Plenum		Space	
		Sensible	Plenum	Sensible	Space	Plenum	Space		Conduction	Plenum	Conduction	Space
		Load	CLTD	Load	CLTD	Solar	Solar		Load	CLTD	Load	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	Solar CLF	Btu/h	°F	Btu/h	°F
117 BREAK ROOM		-186	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
118 S TLT	7 T //A	-119	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-1	Zn Tot/Ave	-305	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-1	Zn Block	-305	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
119 CONF/CONSULT		-102	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
120 PROVIDER OFF		-114	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-2	Zn Tot/Ave	-216	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-2	Zn Block	-216	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
111 TEAM STATION		-152	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
125 TEAM STATION		-200	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
126 B TLT		-127	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
129 CORR CENTRAL		-126	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
130 CORR		-100	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
131 CORR		-226	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
132 CORR NORTH		-114	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Tot/Ave	-1,045	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Block	-1,045	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
121 EXAM ROOM 10		-117	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
122 EXAM ROOM 9		-117	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
123 EXAM ROOM 8		-117	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
124 MECH		-125	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-4	Zn Tot/Ave	-476	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-4	Zn Block	-476	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
100 LOBBY	2 2.33.	-423	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
101 W TLT		-47	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
102 M TLT		-47	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-1	Zn Tot/Ave	-518	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-1	Zn Block	-518	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
113 ELEC	ZITBIOCK	-56	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
114 EVS		-58	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
115 SOIL		-57	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
116 MANAGER OFF		-103	-29.6 -29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-2	Zn Tot/Ave	-103 -274	-29.6 -29.6	0	-32.0 -32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-2	Zn Block	-274	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
109 PROVIDER OFF		-118	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
112 POC		-20	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
129 CORR NORTH		-77	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-3	Zn Tot/Ave	-216	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-3	Zn Block	-216	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0

at Space Peak

By RLF

			- ROC)F		<u> </u>			SKYLIGHT			
		Plenum		Space					Plenum		Space	
		Sensible	Plenum	Sensible	Space	Plenum	Space		Conduction	Plenum	Conduction	Space
		Load	CLTD	Load	CLTD	Solar	Solar		Load	CLTD	Load	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	Solar CLF	Btu/h	°F	Btu/h	°F
105 EXAM ROOM 2		-118	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
106 EXAM ROOM 3		-118	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
107 EXAMS ROOM 4		-118	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
108 EXAM ROOM 5		-118	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Tot/Ave	-473	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Block	-473	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
103 RECEPTION/SCHEDULING		-328	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
110 EXAM ROOM 6		-117	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
127 CLEAN STORAGE		-93	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
128 COMM		-129	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
132 CORR SOUTH		-167	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-5	Zn Tot/Ave	-834	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-5	Zn Block	-834	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
104 EXAM ROOM 1		-118	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
129 CORR SOUTH		-156	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-6	Zn Tot/Ave	-275	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-6	Zn Block	-275	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
AHU	Sys Tot/Ave	-4,631	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0
AHU	Sys Block	-4,631	-29.6	0	-32.0	0	0	0.000	0	0.0	0	0.0

at Space Peak

By RLF

		—— FLO	OR	PART	ITION —	INFILT	RATION —	Plenum	IG ——	Envelope
		Load	CLTD	Load	CLTD	Airflow	Sensible	Dry Bulb Temp	Load	Total
System Zone Room		Btu/h	°F	Btu/h	°F	cfm	Btu/h	°F	Btu/h	Btu/h
117 BREAK ROOM		-333	-32.0	0	0.0	17	-594	67.6	-139	-3,141
118 S TLT		-250	-32.0	0	0.0	4	-141	67.6	-33	-1,351
Zone - 1-1-1	Zn Tot/Ave	-583	-32.0	0	0.0	21	-735	67.6	-172	-4,492
Zone - 1-1-1	Zn Block	-583	-32.0	0	0.0	21	-735	67.6	-172	-4,492
119 CONF/CONSULT		-144	-32.0	0	0.0	9	-327	67.6	-76	-1,339
120 PROVIDER OFF		-145	-32.0	0	0.0	10	-363	67.6	-85	-1,396
Zone - 1-1-2	Zn Tot/Ave	-289	-32.0	0	0.0	19	-690	67.6	-161	-2,735
Zone - 1-1-2	Zn Block	-289	-32.0	0	0.0	19	-690	67.6	-161	-2,735
111 TEAM STATION		0	0.0	0	0.0	14	-482	67.6	-112	-746
125 TEAM STATION		0	0.0	0	0.0	18	-636	67.6	-148	-984
126 B TLT		0	0.0	0	0.0	18	-636	67.6	-148	-912
129 CORR CENTRAL		-235	-32.0	0	0.0	11	-400	67.6	-93	-854
130 CORR		0	0.0	0	0.0	9	-318	67.6	-74	-492
131 CORR		0	0.0	0	0.0	20	-719	67.6	-168	-1,113
132 CORR NORTH		-88	-32.0	0	0.0	10	-364	67.6	-85	-651
Zone - 1-1-3	Zn Tot/Ave	-323	-32.0	0	0.0	100	-3,554	67.6	-829	-5,751
Zone - 1-1-3	Zn Block	-323	-32.0	0	0.0	100	-3,554	67.6	-829	-5,751
121 EXAM ROOM 10		-179	-32.0	0	0.0	10	-372	67.6	-87	-1,781
122 EXAM ROOM 9		-163	-32.0	0	0.0	10	-372	67.6	-87	-1,713
123 EXAM ROOM 8		-163	-32.0	0	0.0	10	-372	67.6	-87	-1,489
124 MECH		-144	-32.0	0	0.0	4	-132	67.6	-31	-1,118
Zone - 1-1-4	Zn Tot/Ave	-649	-32.0	0	0.0	35	-1,249	67.6	-291	-6,102
Zone - 1-1-4	Zn Block	-649	-32.0	0	0.0	35	-1,249	67.6	-291	-6,102
100 LOBBY		-657	-32.0	0	0.0	38	-1,348	67.6	-315	-5,313
101 W TLT		0	0.0	0	0.0	4	-151	67.6	-35	-234
102 M TLT		0	0.0	0	0.0	4	-151	67.6	-35	-234
Zone - 1-2-1	Zn Tot/Ave	-657	-32.0	0	0.0	46	-1,650	67.6	-385	-5,780
Zone - 1-2-1	Zn Block	-657	-32.0	0	0.0	46	-1,650	67.6	-385	-5,780
113 ELEC	2.1 2.001	-87	-32.0	0	0.0	5	-177	67.6	-41	-641
114 EVS		-105	-32.0	0	0.0	5	-183	67.6	-43	-1,174
115 SOIL		-73	-32.0	0	0.0	5	-180	67.6	-42	-589
116 MANAGER OFF		-155	-32.0	0	0.0	9	-327	67.6	-76	-1,607
Zone - 1-2-2	Zn Tot/Ave	-420	-32.0	0	0.0	24	-867	67.6	-202	-4,011
Zone - 1-2-2	Zn Block	-420	-32.0	0	0.0	24	-867	67.6	-202	-4,011
109 PROVIDER OFF	Zii blook	-206	-32.0	0	0.0	11	-376	67.6	-88	-1,897
112 POC		-200	0.0	0	0.0	2	-64	67.6	-00 -15	-1,097
129 CORR NORTH		-235	-32.0	0	0.0	7	-246	67.6	-13 -57	-1,457
Zone - 1-2-3	Zn Tot/Ave	-440	-32.0	0	0.0	19	-686	67.6	-160	-3,453
Zone - 1-2-3 Zone - 1-2-3	Zn Block	-440 -440	-32.0	0	0.0	19	-686	67.6	-160	-3,453
ZUIIE - 1-Z-3	ZII DIUCK	-440	-32.0	U	0.0	19	-000	0.10	-100	-3,433

at Space Peak

By RLF

	ĺ	FLOOR		PARTI	TION —	INFILT	RATION —	CEILIN	IG	
								Plenum		Envelope
		Load	CLTD	Load	CLTD	Airflow	Sensible	Dry Bulb Temp	Load	Total
System Zone Room		Btu/h	°F	Btu/h	°F	cfm	Btu/h	°F	Btu/h	Btu/h
105 EXAM ROOM 2		0	0.0	0	0.0	11	-376	67.6	-88	-581
106 EXAM ROOM 3		0	0.0	0	0.0	11	-376	67.6	-88	-581
107 EXAMS ROOM 4		0	0.0	0	0.0	11	-376	67.6	-88	-581
108 EXAM ROOM 5		0	0.0	0	0.0	11	-376	67.6	-88	-581
Zone - 1-2-4	Zn Tot/Ave	0	0.0	0	0.0	42	-1,502	67.6	-351	-2,326
Zone - 1-2-4	Zn Block	0	0.0	0	0.0	42	-1,502	67.6	-351	-2,326
103 RECEPTION/SCHEDULING		0	0.0	0	0.0	29	-1,043	67.6	-244	-1,614
110 EXAM ROOM 6		0	0.0	0	0.0	10	-372	67.6	-87	-577
127 CLEAN STORAGE		0	0.0	0	0.0	8	-295	67.6	-69	-457
128 COMM		0	0.0	0	0.0	8	-289	67.6	-67	-486
132 CORR SOUTH		-88	-32.0	0	0.0	15	-531	67.6	-124	-1,417
Zone - 1-2-5	Zn Tot/Ave	-88	-32.0	0	0.0	71	-2,532	67.6	-591	-4,551
Zone - 1-2-5	Zn Block	-88	-32.0	0	0.0	71	-2,532	67.6	-591	-4,551
104 EXAM ROOM 1		-206	-32.0	0	0.0	11	-376	67.6	-88	-2,186
129 CORR SOUTH		-235	-32.0	0	0.0	14	-496	67.6	-116	-1,288
Zone - 1-2-6	Zn Tot/Ave	-440	-32.0	0	0.0	24	-872	67.6	-204	-3,474
Zone - 1-2-6	Zn Block	-440	-32.0	0	0.0	24	-872	67.6	-204	-3,474
AHU	Sys Tot/Ave	-3,889	-32.0	0	0.0	402	-14,337	67.6	-3,346	-42,675
AHU	Sys Block	-3,889	-32.0	0	0.0	402	-14,337	67.6	-3,346	-42,675

at Space Peak

By RLF

		su	PPLY AIR TE	MPERATURE	S AIRFLOW	/s ——		CONDUCTIO	N HEAT GAIN	I / LOSSES	
UNDER FLOOR System Zone Room		Supply Airflow into Uflr Plen cfm	Uflr Plen Air Leakage To Space cfm	Supply Tem Entering Uflr Plen °F		Uflr Plenum Air Heat Pickup °F	Conduction From Adj Ceiling Plen Btu/h	Conduction From Adj Ceiling No Plen Btu/h	Conduction From Exp Floor Slab Btu/h	Conduction From Ext Wall Btu/h	Conduction Into Space Btu/h
117 BREAK ROOM		0	0	0.0	0.0	0.0	0	0	0	0	0
118 S TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-1	Zn Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-1	Zn Block	0	0	0.0	0.0	0.0	0	0	0	0	0
119 CONF/CONSULT		0	0	0.0	0.0	0.0	0	0	0	0	0
120 PROVIDER OFF		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-2	Zn Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-2	Zn Block	0	0	0.0	0.0	0.0	0	0	0	0	0
111 TEAM STATION		0	0	0.0	0.0	0.0	0	0	0	0	0
125 TEAM STATION		0	0	0.0	0.0	0.0	0	0	0	0	0
126 B TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
129 CORR CENTRAL		0	0	0.0	0.0	0.0	0	0	0	0	0
130 CORR		0	0	0.0	0.0	0.0	0	0	0	0	0
131 CORR		0	0	0.0	0.0	0.0	0	0	0	0	0
132 CORR NORTH		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-3	Zn Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-3	Zn Block	0	0	0.0	0.0	0.0	0	0	0	0	0
121 EXAM ROOM 10		0	0	0.0	0.0	0.0	0	0	0	0	0
122 EXAM ROOM 9		0	0	0.0	0.0	0.0	0	0	0	0	0
123 EXAM ROOM 8		0	0	0.0	0.0	0.0	0	0	0	0	0
124 MECH		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-4	Zn Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-4	Zn Block	0	0	0.0	0.0	0.0	0	0	0	0	0
100 LOBBY		0	0	0.0	0.0	0.0	0	0	0	0	0
101 W TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
102 M TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-2-1	Zn Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-2-1	Zn Block	0	0	0.0	0.0	0.0	0	0	0	0	0
113 ELEC		0	0	0.0	0.0	0.0	0	0	0	0	0
114 EVS		0	0	0.0	0.0	0.0	0	0	0	0	0
115 SOIL		0	0	0.0	0.0	0.0	0	0	0	0	0
116 MANAGER OFF		0	0	0.0	0.0	0.0	0	0	0	0	0

at Space Peak

By RLF

		SU	IPPLY AIR TE	MPERATURE	S AIRFLOW		CONDUCTIO	N HEAT GAIN	I / LOSSES		
UNDER FLOOR		Supply Airflow into Uflr Plen	Uflr Plen Air Leakage To Space	Supply Tem Entering Uflr Plen	Leaving Uflr Plen	Uflr Plenum Air Heat Pickup	Conduction From Adj Ceiling Plen	Conduction From Adj Ceiling No Plen	Conduction From Exp Floor Slab	Conduction From Ext Wall	Conduction Into Space
System Zone Room		cfm	cfm	°F	°F	°F	Btu/h	Btu/h	Btu/h	Btu/h	Btu/h
Zone - 1-2-2	Zn Tot/Ave	0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-2	Zn Block	0	0	0.0	0.0	0.0	C	0	0	0	0
109 PROVIDER OFF		0	0	0.0	0.0	0.0	C	0	0	0	0
112 POC		0	0	0.0	0.0	0.0	C	0	0	0	0
129 CORR NORTH		0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-3	Zn Tot/Ave	0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-3	Zn Block	0	0	0.0	0.0	0.0	C	0	0	0	0
105 EXAM ROOM 2		0	0	0.0	0.0	0.0	C	0	0	0	0
106 EXAM ROOM 3		0	0	0.0	0.0	0.0	C	0	0	0	0
107 EXAMS ROOM 4		0	0	0.0	0.0	0.0	C	0	0	0	0
108 EXAM ROOM 5		0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-4	Zn Tot/Ave	0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-4	Zn Block	0	0	0.0	0.0	0.0	C	0	0	0	0
103 RECEPTION/SCHEDU	JLIN	0	0	0.0	0.0	0.0	C	0	0	0	0
110 EXAM ROOM 6		0	0	0.0	0.0	0.0	C	0	0	0	0
127 CLEAN STORAGE		0	0	0.0	0.0	0.0	C	0	0	0	0
128 COMM		0	0	0.0	0.0	0.0	C	0	0	0	0
132 CORR SOUTH		0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-5	Zn Tot/Ave	0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-5	Zn Block	0	0	0.0	0.0	0.0	C	0	0	0	0
104 EXAM ROOM 1		0	0	0.0	0.0	0.0	C	0	0	0	0
129 CORR SOUTH		0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-6	Zn Tot/Ave	0	0	0.0	0.0	0.0	C	0	0	0	0
Zone - 1-2-6	Zn Block	0	0	0.0	0.0	0.0	C	0	0	0	0
AHU	Sys Tot/Ave	0	0	0.0	0.0	0.0	C	0	0	0	0
AHU	Sys Block	0	0	0.0	0.0	0.0	C	0	0	0	0

at Space Peak

By RLF

		WALL				WINDOW						
		Plenum	Plenum	Space	Space	Space	Plenum		Space	Space	Plenum	Plenum
		Load	CLTD	Load	CLTD	Solar	Solar	Solar	Conduction	CLTD	Conduction	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	CLF	Btu/h	°F	Btu/h	°F
Zone - 1-2-2	Zn Block	477	44.0	1,102	47.1	745	0	0.932	407	10.8	0	0.0
109 PROVIDER OFF		252	47.6	574	50.5	461	0	0.925	128	6.8	0	0.0
112 POC		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
129 CORR NORTH		145	38.4	358	42.3	0	0	0.000	196	13.3	0	0.0
Zone - 1-2-3	Zn Tot/Ave	397	43.7	932	47.0	461	0	0.925	324	9.7	0	0.0
Zone - 1-2-3	Zn Block	400	44.0	933	47.1	373	0	0.932	364	10.9	0	0.0
105 EXAM ROOM 2		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
106 EXAM ROOM 3		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
107 EXAMS ROOM 4		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
108 EXAM ROOM 5		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Tot/Ave	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Block	0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
103 RECEPTION/SCHEDULING		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
110 EXAM ROOM 6		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
127 CLEAN STORAGE		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
128 COMM		0	0.0	0	0.0	0	0	0.000	0	0.0	0	0.0
132 CORR SOUTH		323	142.5	660	145.6	952	0	0.936	2	0.3	0	0.0
Zone - 1-2-5	Zn Tot/Ave	323	142.5	660	145.6	952	0	0.936	2	0.3	0	0.0
Zone - 1-2-5	Zn Block	247	109.1	512	112.8	598	0	0.929	104	11.1	0	0.0
104 EXAM ROOM 1		203	38.4	428	42.3	0	0	0.000	392	13.3	0	0.0
129 CORR SOUTH		315	139.0	970	142.6	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-6	Zn Tot/Ave	518	68.5	1,398	82.6	0	0	0.000	392	13.3	0	0.0
Zone - 1-2-6	Zn Block	473	62.5	1,157	68.4	0	0	0.000	308	10.5	0	0.0
AHU	Sys Tot/Ave	8,804	102.6	22,088	108.9	12,390	0	0.947	2,102	8.9	0	0.0
AHU	Sys Block	6,572	76.6	16,248	80.1	8,755	0	0.859	2,595	10.9	0	0.0

at Space Peak

By RLF

		ROOF -						s	KYLIGHT —			
		Plenum Sensible Load	Plenum CLTD	Space Sensible Load	Space CLTD	Plenum Solar	Space Solar		Plenum Conduction Load	Plenum CLTD	Space Conduction Load	Space CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	Solar CLF	Btu/h	°F	Btu/h	°F
117 BREAK ROOM		296	47.1	0	50.2	0	0	0.000	0	0.0	0	0.0
118 S TLT		260	64.6	0	67.7	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-1	Zn Tot/Ave	556	54.0	0	57.6	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-1	Zn Block	556	54.0	0	57.0	0	0	0.000	0	0.0	0	0.0
119 CONF/CONSULT		203	58.9	0	62.3	0	0	0.000	0	0.0	0	0.0
120 PROVIDER OFF		294	76.7	0	80.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-2	Zn Tot/Ave	497	68.2	0	70.0	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-2	Zn Block	497	68.2	0	71.6	0	0	0.000	0	0.0	0	0.0
111 TEAM STATION		407	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
125 TEAM STATION		573	84.8	0	88.8	0	0	0.000	0	0.0	0	0.0
126 B TLT		342	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
129 CORR CENTRAL		338	79.7	0	83.7	0	0	0.000	0	0.0	0	0.0
130 CORR		270	80.3	0	84.3	0	0	0.000	0	0.0	0	0.0
131 CORR		606	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
132 CORR NORTH		343	88.7	0	92.7	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Tot/Ave	2,878	81.6	0	85.6	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-3	Zn Block	2,878	81.6	0	85.6	0	0	0.000	0	0.0	0	0.0
121 EXAM ROOM 10		303	76.7	0	80.0	0	0	0.000	0	0.0	0	0.0
122 EXAM ROOM 9		303	76.7	0	80.0	0	0	0.000	0	0.0	0	0.0
123 EXAM ROOM 8		303	76.7	0	80.0	0	0	0.000	0	0.0	0	0.0
124 MECH		174	41.2	0	44.1	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-4	Zn Tot/Ave	1,084	67.4	0	66.5	0	0	0.000	0	0.0	0	0.0
Zone - 1-1-4	Zn Block	1,088	67.7	0	70.8	0	0	0.000	0	0.0	0	0.0
100 LOBBY		1,037	72.6	0	75.7	0	0	0.000	0	0.0	0	0.0
101 W TLT		137	85.3	0	89.2	0	0	0.000	0	0.0	0	0.0
102 M TLT		137	85.3	0	89.2	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-1	Zn Tot/Ave	1,310	74.9	0	84.2	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-1	Zn Block	1,270	72.6	0	75.7	0	0	0.000	0	0.0	0	0.0
113 ELEC		84	44.6	0	47.6	0	0	0.000	0	0.0	0	0.0
114 EVS		87	44.6	0	47.6	0	0	0.000	0	0.0	0	0.0
115 SOIL		152	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
116 MANAGER OFF		164	47.1	0	50.2	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-2	Zn Tot/Ave	488	52.8	0	54.1	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-2	Zn Block	435	47.1	0	50.2	0	0	0.000	0	0.0	0	0.0
109 PROVIDER OFF		178	44.6	0	47.6	0	0	0.000	0	0.0	0	0.0
112 POC		55	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
129 CORR NORTH		207	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-3	Zn Tot/Ave	440	60.4	0	66.7	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-3	Zn Block	343	47.1	0	50.2	0	0	0.000	0	0.0	0	0.0
105 EXAM ROOM 2		340	85.3	0	89.2	0	0	0.000	0	0.0	0	0.0

Project Name: Dataset Name:

Dataset Name: 21184.TRC

at Space Peak

By RLF

			ROC)F				s	KYLIGHT —			
		Plenum Sensible	Plenum	Space Sensible	Space	Plenum	Space		Plenum Conduction	Plenum	Space Conduction	Space
		Load	CLTD	Load	CLTD	Solar	Solar		Load	CLTD	Load	CLTD
System Zone Room		Btu/h	°F	Btu/h	°F	Btu/h	Btu/h	Solar CLF	Btu/h	°F	Btu/h	°F
106 EXAM ROOM 3		333	83.5	0	87.5	0	0	0.000	0	0.0	0	0.0
107 EXAMS ROOM 4		317	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
108 EXAM ROOM 5		317	79.5	0	83.4	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Tot/Ave	1,307	81.9	0	85.8	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-4	Zn Block	1,307	81.9	0	85.9	0	0	0.000	0	0.0	0	0.0
103 RECEPTION/SCHEDULING		952	86.2	0	90.1	0	0	0.000	0	0.0	0	0.0
110 EXAM ROOM 6		328	83.0	0	86.9	0	0	0.000	0	0.0	0	0.0
127 CLEAN STORAGE		286	91.1	0	95.0	0	0	0.000	0	0.0	0	0.0
128 COMM		363	83.1	0	87.0	0	0	0.000	0	0.0	0	0.0
132 CORR SOUTH		335	59.6	0	62.7	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-5	Zn Tot/Ave	2,264	80.5	0	82.6	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-5	Zn Block	2,283	81.1	0	84.9	0	0	0.000	0	0.0	0	0.0
104 EXAM ROOM 1		340	85.3	0	89.2	0	0	0.000	0	0.0	0	0.0
129 CORR SOUTH		446	84.6	0	88.2	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-6	Zn Tot/Ave	786	84.9	0	88.7	0	0	0.000	0	0.0	0	0.0
Zone - 1-2-6	Zn Block	840	90.7	0	94.5	0	0	0.000	0	0.0	0	0.0
AHU	Sys Tot/Ave	11,611	74.3	0	73.5	0	0	0.000	0	0.0	0	0.0
AHU	Sys Block	10,091	64.6	0	68.1	0	0	0.000	0	0.0	0	0.0

at Space Peak

By RLF

	1	FLOOR -		— PARTI	ITION —	<u> </u>	INFILTRATION		CEIL	ING —	1
									Plenum		Envelope
		Load	CLTD	Load	CLTD	Airflow	Sensible	Latent	Dry Bulb	Load	Total
System Zone Room		Btu/h	°F	Btu/h	°F	cfm	Btu/h	Btu/h	°F	Btu/h	Btu/h
117 BREAK ROOM		0	0.0	0	0.0	17	187	728	78.0	178	3,367
118 S TLT		0	0.0	0	0.0 0.0	4	45	173	78.0	42	2,839
	Zn Tot/Ave	0	0.0	0	0.0	21	232	901	78.0	221	6,206
	Zn Block	0	0.0	0	0.0	21	232	901	78.0	221	6,248
119 CONF/CONSULT	ZII DIOCK	0	0.0	0	0.0	9	113	424	78.4	109	3,834
120 PROVIDER OFF		0	0.0	0	0.0	10	125	469	78.4	121	4,004
	Zn Tot/Ave	0	0.0	0	0.0	19	237	893	78.4	229	7,838
	Zn Block	0	0.0	0	0.0	19	237	893	78.4	229	7,838
111 TEAM STATION	ZII DIOCK	0	0.0	0	0.0	14	196	603	79.0	188	1,394
125 TEAM STATION		0	0.0	0	0.0	18	258	796	79.0	249	1,876
126 B TLT		0	0.0	0	0.0	18	258	796	79.0	249	1,645
129 CORR CENTRAL		0	0.0	0	0.0	11	162	501	79.0	156	1,158
130 CORR		0	0.0	0	0.0	9	129	398	79.0	124	921
131 CORR		0	0.0	0	0.0	20	292	901	79.0	281	2,081
132 CORR NORTH		0	0.0	0	0.0	10	148	456	79.0	142	1,089
	Zn Tot/Ave	0	0.0	0	0.0	100	1,444	4,452	79.0	1,390	10,164
	Zn Block	0	0.0	0	0.0	100	1,444	4,452	79.0	1,390	10,164
121 EXAM ROOM 10	22.00.	0	0.0	0	0.0	10	128	482	78.4	124	5,329
122 EXAM ROOM 9		0	0.0	0	0.0	10	128	482	78.4	124	5,082
123 EXAM ROOM 8		0	0.0	0	0.0	10	128	482	78.4	124	4,315
124 MECH		0	0.0	0	0.0	4	-24	-5	77.8	37	3,025
	Zn Tot/Ave	0	0.0	0	0.0	35	360	1,440	78.3	408	17,750
	Zn Block	0	0.0	0	0.0	35	367	1,479	78.1	383	16,310
100 LOBBY		0	0.0	0	0.0	38	-4	94	78.1	415	13,072
101 W TLT		0	0.0	0	0.0	4	61	189	79.0	59	446
102 M TLT		0	0.0	0	0.0	4	61	189	79.0	59	446
Zone - 1-2-1	Zn Tot/Ave	0	0.0	0	0.0	46	118	472	78.3	533	13,964
Zone - 1-2-1	Zn Block	0	0.0	0	0.0	46	-5	115	78.1	508	13,418
113 ELEC		0	0.0	0	0.0	5	35	156	78.0	52	771
114 EVS		0	0.0	0	0.0	5	36	161	78.0	54	1,239
115 SOIL		0	0.0	0	0.0	5	73	225	79.0	70	833
116 MANAGER OFF		0	0.0	0	0.0	9	103	401	78.0	98	1,869
Zone - 1-2-2	Zn Tot/Ave	0	0.0	0	0.0	24	247	943	78.2	274	4,712
Zone - 1-2-2	Zn Block	0	0.0	0	0.0	24	273	1,062	78.0	260	4,762
109 PROVIDER OFF		0	0.0	0	0.0	11	74	331	78.0	110	2,109
112 POC		0	0.0	0	0.0	2	26	80	79.0	25	187
129 CORR NORTH		0	0.0	0	0.0	7	100	308	79.0	96	1,410
Zone - 1-2-3	Zn Tot/Ave	0	0.0	0	0.0	19	200	720	78.4	232	3,705
Zone - 1-2-3	Zn Block	0	0.0	0	0.0	19	216	840	78.0	206	3,675

Project Name: Dataset Name:

21184.TRC

at Space Peak

By RLF

	ſ	FLC	OR	PARTI	TION —		INFILTRATION	ı ——	CEIL	LING	1
									Plenum		Envelope
		Load	CLTD	Load	CLTD	Airflow	Sensible	Latent	Dry Bulb	Load	Total
System Zone Room		Btu/h	°F	Btu/h	°F	cfm	Btu/h	Btu/h	°F	Btu/h	Btu/h
105 EXAM ROOM 2		0	0.0	0	0.0	11	153	471	79.0	147	1,110
106 EXAM ROOM 3		0	0.0	0	0.0	11	153	471	79.0	147	1,103
107 EXAMS ROOM 4		0	0.0	0	0.0	11	153	471	79.0	147	1,087
108 EXAM ROOM 5		0	0.0	0	0.0	11	153	471	79.0	147	1,087
Zone - 1-2-4	Zn Tot/Ave	0	0.0	0	0.0	42	610	1,882	79.0	588	4,388
Zone - 1-2-4	Zn Block	0	0.0	0	0.0	42	610	1,882	79.0	588	4,388
103 RECEPTION/SCHEDULING		0	0.0	0	0.0	29	424	1,307	79.0	408	3,091
110 EXAM ROOM 6		0	0.0	0	0.0	10	151	467	79.0	146	1,092
127 CLEAN STORAGE		0	0.0	0	0.0	8	120	370	79.0	116	892
128 COMM		0	0.0	0	0.0	8	117	362	79.0	113	955
132 CORR SOUTH		0	0.0	0	0.0	15	7	52	78.1	160	2,491
Zone - 1-2-5	Zn Tot/Ave	0	0.0	0	0.0	71	819	2,558	78.8	942	8,521
Zone - 1-2-5	Zn Block	0	0.0	0	0.0	71	862	2,928	78.7	935	8,469
104 EXAM ROOM 1		0	0.0	0	0.0	11	153	471	79.0	147	2,133
129 CORR SOUTH		0	0.0	0	0.0	14	102	363	78.5	174	2,370
Zone - 1-2-6	Zn Tot/Ave	0	0.0	0	0.0	24	255	833	78.7	321	4,503
Zone - 1-2-6	Zn Block	0	0.0	0	0.0	24	286	937	78.8	328	4,329
AHU	Sys Tot/Ave	0	0.0	0	0.0	402	4,523	15,095	78.6	5,137	81,751
AHU	Sys Block	0	0.0	0	0.0	402	4,704	17,171	78.5	4,978	71,115

at Space Peak

By RLF

		SUI	PPLY AIR TEI	MPERATURE	S AIRFLOW	s —		CONDUCTION	N HEAT GAIN	/ LOSSES	
UNDER FLOOR		Supply Airflow into Uflr Plen	Uflr Plen Air Leakage To Space	Supply Tem Entering Uflr Plen	perature Leaving Uflr Plen	Uflr Plenum Air Heat Pickup	Conduction From Adj Ceiling Plen	Conduction From Adj Ceiling No Plen	Conduction From Exp Floor Slab	Conduction From Ext Wall	Conduction Into Space
System Zone Room		cfm	cfm	°F	°F	°F	Btu/h	Btu/h	Btu/h	Btu/h	Btu/h
117 BREAK ROOM		0	0	0.0	0.0	0.0	0	0	0	0	0
118 S TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-1 Zn	Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-1 Zn l	Block	0	0	0.0	0.0	0.0	0	0	0	0	0
119 CONF/CONSULT		0	0	0.0	0.0	0.0	0	0	0	0	0
120 PROVIDER OFF		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-2 Zn	Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-2 Zn l	Block	0	0	0.0	0.0	0.0	0	0	0	0	0
111 TEAM STATION		0	0	0.0	0.0	0.0	0	0	0	0	0
125 TEAM STATION		0	0	0.0	0.0	0.0	0	0	0	0	0
126 B TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
129 CORR CENTRAL		0	0	0.0	0.0	0.0	0	0	0	0	0
130 CORR		0	0	0.0	0.0	0.0	0	0	0	0	0
131 CORR		0	0	0.0	0.0	0.0	0	0	0	0	0
132 CORR NORTH		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-3 Zn	Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-3 Zn I	Block	0	0	0.0	0.0	0.0	0	0	0	0	0
121 EXAM ROOM 10		0	0	0.0	0.0	0.0	0	0	0	0	0
122 EXAM ROOM 9		0	0	0.0	0.0	0.0	0	0	0	0	0
123 EXAM ROOM 8		0	0	0.0	0.0	0.0	0	0	0	0	0
124 MECH		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-4 Zn	Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-1-4 Zn l	Block	0	0	0.0	0.0	0.0	0	0	0	0	0
100 LOBBY		0	0	0.0	0.0	0.0	0	0	0	0	0
101 W TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
102 M TLT		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-2-1 Zn	Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-2-1 Zn l	Block	0	0	0.0	0.0	0.0	0	0	0	0	0
113 ELEC		0	0	0.0	0.0	0.0	0	0	0	0	0
114 EVS		0	0	0.0	0.0	0.0	0	0	0	0	0
115 SOIL		0	0	0.0	0.0	0.0	0	0	0	0	0
116 MANAGER OFF		0	0	0.0	0.0	0.0	0	0	0	0	0
Zone - 1-2-2 Zn	Tot/Ave	0	0	0.0	0.0	0.0	0	0	0	0	0

Project Name:

Dataset Name: 21184.TRC

at Space Peak

By RLF

UNDER FLOOR Supply Airflow into Uflr Plen CFM Uflr Plen Air Leakage To Space CFM Uflr Plen U	0 0
Zone - 1-2-2 Zn Block 0 0 0.0 0.0 0.0 0 0 0 0 109 PROVIDER OFF 0 0 0.0 0.0 0.0 0<	0 0 0 0
109 PROVIDER OFF 0 0 0.0 0.0 0.0 0 0 0 0 112 POC 0 0 0.0 0.0 0.0 0 0 0 0 0	0 0
112 POC 0 0 0.0 0.0 0.0 0 0 0 0 0	0
	0
129 CORR NORTH 0 0 0.0 0.0 0.0 0 0 0 0 0	
	0
Zone - 1-2-3 Zn Tot/Ave 0 0 0.0 0.0 0.0 0.0 0 0 0 0	
Zone - 1-2-3 Zn Block 0 0 0.0 0.0 0.0 0 0 0 0	0
105 EXAM ROOM 2 0 0 0.0 0.0 0.0 0 0 0 0 0	0
106 EXAM ROOM 3 0 0 0.0 0.0 0.0 0 0 0 0 0	0
107 EXAMS ROOM 4 0 0 0.0 0.0 0.0 0 0 0 0 0	0
108 EXAM ROOM 5 0 0 0.0 0.0 0.0 0 0 0 0 0	0
Zone - 1-2-4 Zn Tot/Ave 0 0 0.0 0.0 0.0 0.0 0 0 0 0	0
Zone - 1-2-4 Zn Block 0 0 0.0 0.0 0.0 0.0 0 0 0 0	0
103 RECEPTION/SCHEDULIN 0 0 0.0 0.0 0.0 0 0 0 0 0	0
110 EXAM ROOM 6 0 0 0.0 0.0 0.0 0 0 0 0 0	0
127 CLEAN STORAGE 0 0 0.0 0.0 0.0 0 0 0 0 0	0
128 COMM 0 0.0 0.0 0.0 0 0 0 0 0	0
132 CORR SOUTH 0 0 0.0 0.0 0.0 0 0 0 0 0	0
Zone - 1-2-5 Zn Tot/Ave 0 0 0.0 0.0 0.0 0 0 0 0	0
Zone - 1-2-5 Zn Block 0 0 0.0 0.0 0.0 0.0 0 0 0 0	0
104 EXAM ROOM 1 0 0.0 0.0 0.0 0.0 0 0 0 0	0
129 CORR SOUTH 0 0 0.0 0.0 0.0 0 0 0 0	0
Zone - 1-2-6 Zn Tot/Ave 0 0 0.0 0.0 0.0 0.0 0 0 0 0	0
Zone - 1-2-6 Zn Block 0 0 0.0 0.0 0.0 0 0 0 0	0
AHU Sys Tot/Ave 0 0 0.0 0.0 0.0 0 0 0 0	0
AHU Sys Block 0 0 0.0 0.0 0.0 0 0 0 0	0

	OA Condition									
	DB WB Peak Time °F °F					SPAC	CE		COIL	
System	Htg Design 38 27	Block or Peak	Floor Area ft²	Room Dry Bulb °F	Supply Dry Bulb °F	Space Air Flow cfm	Space Sensible Load Btu/h	Supply Dry Bulb °F	Coil Air Flow cfm	Coil Sensible Load Btu/h
	Zone - 1-2-2	Block	270	70.0	132.6	49	-3,417	132.6	49	-4,423
	109 PROVIDER OFF	Peak	117	70.0	120.6	29	-1,622	120.6	29	-2,212
	112 POC	Peak	20	70.0	135.1	1	-79	135.1	1	-102
	129 CORR NORTH	Peak	77	70.0	177.9	11	-1,267	177.9	11	-1,484
	Zone - 1-2-3	Peak	214	70.0	135.9	40	-2,969	135.9	40	-3,798
	Zone - 1-2-3	Block	214	70.0	135.9	40	-2,969	135.9	40	-3,798
	105 EXAM ROOM 2	Peak	117	70.0	94.9	17	-463	94.9	17	-806
	106 EXAM ROOM 3	Peak	117	70.0	94.9	17	-463	94.9	17	-806
	107 EXAMS ROOM 4	Peak	117	70.0	94.9	17	-463	94.9	17	-806
	108 EXAM ROOM 5	Peak	117	70.0	94.9	17	-463	94.9	17	-806
	Zone - 1-2-4	Peak	468	70.0	94.9	67	-1,853	94.9	67	-3,226
	Zone - 1-2-4	Block	468	70.0	94.9	67	-1,853	94.9	67	-3,226
	103 RECEPTION/SCHEDULING	Peak	325	70.0	97.5	42	-1,287	97.5	42	-2,148
	110 EXAM ROOM 6	Peak	116	70.0	94.8	17	-459	94.8	17	-801
	127 CLEAN STORAGE	Peak	92	70.0	135.1	5	-364	135.1	5	-467
	128 COMM	Peak	90	70.0	72.2	143	-356	72.2	143	-3,289
	132 CORR SOUTH	Peak	166	70.0	113.1	25	-1,184	113.1	25	-1,689
	Zone - 1-2-5	Peak	789	70.0	84.2	231	-3,651	84.2	231	-8,394
	Zone - 1-2-5	Block	789	70.0	84.2	231	-3,650	84.2	231	-8,394
	104 EXAM ROOM 1	Peak	117	70.0	135.6	26	-1,910	135.6	26	-2,447
	129 CORR SOUTH	Peak	155	70.0	122.5	18	-1,065	122.5	18	-1,438
	Zone - 1-2-6	Peak	272	70.0	130.2	44	-2,975	130.2	44	-3,885
	Zone - 1-2-6	Block	272	70.0	130.2	44	-2,975	130.2	44	-3,885
AHU		Peak	4,466	70.0	100.3	1,050	-35,501	100.3	1,050	-57,066
AHU		Block	4,466	70.0	100.3	1,050	-35,501	100.3	1,050	-57,066

SPACE COIL

				517(52															
						С	PΑ	Room	Supply	Space	Space	Space		О	A			Coil	Coil
				Floor	Peak	Cond	dition	Dry	Dry	Air	Sensible	Latent	Peak	Cond	dition_	Supply	Coil	Sensible	Latent
				Area	Time	DB	WB	Bulb	Bulb	Flow	Load	Load	Time	DB	WB	Dry Bulb	Airflow	Load	Load
System	Zone Ro	om		ft²	Mo/Hr	°F	°F	°F	°F	cfm	Btu/h	Btu/h	Mo/Hr	°F	°F	°F	cfm	Btu/h	Btu/h
	109	PROVIDER OFF	Peak	117	6/18	81	73	75.0	51.6	96	2,503	731	7 /17	87	78	51.6	95	2,826	896
	112	POC	Peak	20	7/15	88	78	75.0	51.6	4	95	80	7 /16	88	78	51.6	4	123	86
	129	CORR NORTH	Peak	77	7/15	88	78	75.0	51.6	35	917	308	7 /15	88	78	51.6	35	1,184	308
	Zone - 1-2-	-3	Peak	214		85	77	75.0	51.6	135	3,515	1,120		87	78	51.6	134	4,133	1,290
	Zone - 1-2-	-3	Block	214	7/18	85	77	75.0	51.6	132	3,458	1,240	7 /17	87	78	51.6	132	4,064	1,306
	105	EXAM ROOM 2	Peak	117	7/15	88	78	75.0	51.6	56	1,454	871	7 /15	88	78	51.6	56	1,665	871
	106	EXAM ROOM 3	Peak	117	7/15	88	78	75.0	51.6	56	1,454	871	7 /15	88	78	51.6	56	1,658	871
	107	EXAMS ROOM 4	Peak	117	7/15	88	78	75.0	51.6	56	1,454	871	7 /16	88	78	51.6	55	1,613	902
	108	EXAM ROOM 5	Peak	117	7/15	88	78	75.0	51.6	56	1,454	871	7 /16	88	78	51.6	55	1,613	902
	Zone - 1-2-	-4	Peak	468		88	78	75.0	51.6	223	5,818	3,482		88	78	51.6	222	6,549	3,544
	Zone - 1-2-	-4	Block	468	7/15	88	78	75.0	51.6	223	5,818	3,482	7 /15	88	78	51.6	223	6,607	3,482
	103	RECEPTION/SCHEDULING	Peak	325	7/15	88	78	75.0	51.6	140	3,651	2,107	7 /15	88	78	51.6	140	4,244	2,107
	110	EXAM ROOM 6	Peak	116	7/15	88	78	75.0	51.6	55	1,446	867	7 /15	88	78	51.6	55	1,646	867
	127	CLEAN STORAGE	Peak	92	7/15	88	78	75.0	51.6	17	436	370	7 /16	88	78	51.6	16	612	394
	128	COMM	Peak	90	7/15	88	78	75.0	51.6	476	12,427	362	7 /15	88	78	51.6	476	12,690	362
	132	CORR SOUTH	Peak	166	11/15	75	64	75.0	51.6	82	2,143	52	9 /15	86	77	51.6	75	2,504	615
	Zone - 1-2-	-5	Peak	789		86	77	75.0	51.6	770	20,103	3,758		87	78	51.6	762	21,695	4,345
	Zone - 1-2-	-5	Block	789	9/15	86	77	75.0	51.6	756	19,739	4,128	8 /15	87	78	51.6	748	21,250	4,372
	104	EXAM ROOM 1	Peak	117	7/15	88	78	75.0	51.6	87	2,274	871	7 /15	88	78	51.6	87	2,688	871
	129	CORR SOUTH	Peak	155	10/14	82	72	75.0	51.6	61	1,583	363	9 /14	86	76	51.6	57	2,080	533
	Zone - 1-2-	-6	Peak	272		86	76	75.0	51.6	148	3,858	1,233		86	76	51.6	145	4,768	1,404
	Zone - 1-2-	-6	Block	272	9/14	86	76	75.0	51.6	137	3,572	1,337	9 /14	86	76	51.6	137	4,601	1,337
AHU			Peak	4,466		86	77	75.0	51.6	3,501	91,406	27,495		87	78	51.6	3,463	106,269	29,918
AHU			Block	4,466	9/16	86	77	75.0	51.6	3,158	82,446	29,571	8 /16	87	78	51.6	3,112	94,210	30,560

Project Name: HealthFirst Medico

Dataset Name: 21184.TRC

					Coil	Coil	Space		VAV		Main Coil	Heating		
			Floor		Cooling	Cooling	Design	Air	Minimum	VAV	Heating	Fan	Perc	
System	Zone Room **		Area ft²	People #	Sensible Btu/h	Total Btu/h	Max SA cfm	Changes ach/hr	SA cfm	Minimum %	Sensible Btu/h	Max SA cfm	Clg	Htg
Oystelli	112 POC	Rm Peak	20	0.0	123	208	4		1	30	-102	0	0.0	0.0
	129 CORR NORTH	Rm Peak	77	0.0	1,184	1,492	35		11	30	-1,484	0	0.0	0.0
	Zone - 1-2-3	Zn Peak	214	2.0	4,133	5,423	135			30	-3,798	0	0.0	0.0
	Zone - 1-2-3	Zn Block	214	2.0	4,064	5,370	132			30	-3,798	0	0.0	0.0
	105 EXAM ROOM 2	Rm Peak	117	2.0	1,665	2,536	56	3.17	17	30	-806	0	0.0	0.0
	106 EXAM ROOM 3	Rm Peak	117	2.0	1,658	2,529	56	3.17	17	30	-806	0	0.0	0.0
	107 EXAMS ROOM 4	Rm Peak	117	2.0	1,613	2,514	56	3.17	17	30	-806	0	0.0	0.0
	108 EXAM ROOM 5	Rm Peak	117	2.0	1,613	2,514	56	3.17	17	30	-806	0	0.0	0.0
	Zone - 1-2-4	Zn Peak	468	8.0	6,549	10,093	223			30	-3,226	0	0.0	0.0
	Zone - 1-2-4	Zn Block	468	8.0	6,607	10,089	223			30	-3,226	0	0.0	0.0
	103 RECEPTION/SCHEDULING	Rm Peak	325	4.0	4,244	6,351	140	2.87	42	30	-2,148	0	0.0	0.0
	110 EXAM ROOM 6	Rm Peak	116	2.0	1,646	2,513	55	3.18	17	30	-801	0	0.0	0.0
	127 CLEAN STORAGE	Rm Peak	92	0.0	612	1,007	17	1.21	5	30	-467	0	0.0	0.0
	128 COMM	Rm Peak	90	0.0	12,690	13,052	476	35.26	143	30	-3,289	0	0.0	0.0
	132 CORR SOUTH	Rm Peak	166	0.0	2,504	3,118	82	3.31	25	30	-1,689	0	0.0	0.0
	Zone - 1-2-5	Zn Peak	789	6.0	21,695	26,040	770			30	-8,394	0	0.0	0.0
	Zone - 1-2-5	Zn Block	789	6.0	21,250	25,622	756			31	-8,394	0	0.0	0.0
	104 EXAM ROOM 1	Rm Peak	117	2.0	2,688	3,559	87	4.96	26	30	-2,447	0	0.0	0.0
	129 CORR SOUTH	Rm Peak	155	0.0	2,080	2,613	61	2.61	18	30	-1,438	0	0.0	0.0
	Zone - 1-2-6	Zn Peak	272	2.0	4,768	6,172	148			30	-3,885	0	0.0	0.0
	Zone - 1-2-6	Zn Block	272	2.0	4,601	5,938	137			32	-3,885	0	0.0	0.0
AHU		Sys Peak	4,466	62.0	106,269	136,188	3,501				-57,066	0	0.0	0.0
AHU		Sys Block	4,466	62.0	94,210	124,770	3,158				-57,066	0	0.0	0.0

^{*} This report does not display heating only systems.

By RLF

Zone - 1-1-2

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 8 / 17 R: 86 / 78 / 1	31	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	497	497	5	0	0	Roof Cond	0	-216	5.36
Glass Solar	1,985	0	1,985	18 ;	1,985	27	Glass Solar	0	0	0.00
Glass/Door Cond	218	0	218	2:	218	3	Glass/Door Cond	-590	-590	14.65
Wall Cond	2,681	1,097	3,778	35	2,681	37		-569	-789	19.60
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0.00	0	Floor	-289	-289	7.17
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,130		1,130	10 :	237	3	!	-690	-690	17.15
Sub Total ==>	6,015	1,594	7,609	70 :	5,122	70	Sub Total ==>	-2,137	-2,574	63.93
Internal Loads							Internal Loads			
Lights	470	117	587	5 :	470	6	Lights	0	0	0.00
People	2,700	0	2,700	25	1,500	20	People	0	0	0.00
Misc	0	0	0	0 :	0	0	Misc	0	0	0.00
Sub Total ==>	3,170	117	3,287	30	1,970	27	Sub Total ==>	0	0	0.00
Ceiling Load	229	-229	0	0:	229	3	Ceiling Load	-161	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0:			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		51	-1.27
Exhaust Heat	_	-73	-73	-1	-		OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-1,506	37.40
Duct Heat Pkup		0	0	0 :			System Plenum Heat		2	-0.06
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	9,414	1,409	10,823	100.00	7,321	100.00	Grand Total ==>	-2,299	-4,026	100.00

TEMPERATURES							
	Cooling	Heating					
SADB	51.6	94.5					
Ra Plenum	78.4	67.6					
Return	78.4	67.6					
Ret/OA	78.4	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
AIRFLUW5								
	Cooling	Heating						
Diffuser	280	84						
Terminal	280	84						
Main Fan	280	84						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	19	19						
MinStop/Rh	84	84						
Return	300	103						
Exhaust	19	19						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.30	0.39					
cfm/ton	310.91						
ft²/ton	238.38						
Btu/hr·ft²	50.34	-18.72					
No. People	6						

COOLING COIL SELECTION										
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E nt °F	ter DB/W	/B/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	0.9 0.0	10.8 0.0	8.7 0.0	280 0	78.4 0.0	63.7 0.0	65.0 0.0	51.6 0.0	50.4 0.0	52.6 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.9	10.8								

	AREAS	;		
Gi	ross Total	Glas:	s (%)	
		п	(%)	
Floor	215			I
Part	0			1
Int Door	0			F
ExFlr	18			F
Roof	232	0	0	
Wall	216	33	15	
Ext Door	0	0	0	7

HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-4.0	84	51.6	94.5					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	0	0.0	0.0					
Reheat	-1.7	84	51.6	70.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-4.0								

By RLF

Zone - 1-1-3

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 16 R: 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0 }	0	0	,	0	0	0.00
Roof Cond	0	2,672	2,672	16	0	0		0	-1,045	15.33
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	,	0	0	0.00
Wall Cond	0	0	0	0 :	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-323	-323	4.74
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	, ,	0.00	0.00	0.00
Infiltration	6,143		6,143	36 ;	1,444	16		-3,554	-3,554	52.14
Sub Total ==>	6,143	2,672	8,815	52	1,444	16	Sub Total ==>	-3,876	-4,921	72.21
Internal Loads							Internal Loads			
Lights	2,418	604	3,022	18	2,418	27	Lights	0	0	0.00
People	4,500	0	4,500	26	2,500	28	People	0	0	0.00
Misc	1,188	0	1,188	7	1,188	13	Misc	0	0	0.00
Sub Total ==>	8,106	604	8,710	51	6,106	68	Sub Total ==>	0	0	0.00
Ceiling Load	1,325	-1,325	0	0	1,390	16	Ceiling Load	-829	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0 :	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		263	-3.85
Exhaust Heat	ŭ	-420	-420	-2	ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-1,838	26.98
Duct Heat Pkup		0	0	0			System Plenum Heat		-318	4.66
Underfir Sup Ht Pku	D		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	15,574	1,531	17,105	100.00	8,939	100.00	Grand Total ==>	-4,706	-6,815	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	111.1					
Ra Plenum	78.8	67.6					
Return	78.8	67.6					
Ret/OA	78.8	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS									
Cooling Heating									
342	103								
342 342	103 103								
0	0								
0	0								
0	0								
100	100								
103	103								
442	202								
100	100								
0	0								
0	0								
0	0								
0	0								
	Cooling 342 342 0 0 0 100 100 103 442 100 0 0 0								

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft ²	0.31	0.09					
cfm/ton	240.21						
ft²/ton	776.54						
Btu/hr·ft²	15.45	-6.16					
No. People	10						

COOLING COIL SELECTION														
	Total C	Total Capacity						Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb			Leave DB/WB/HR °F °F gr/lb		
Main Clg	1.4	17.1	10.4	338	78.8	63.9	65.0	51.6		36.3				
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0				
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0				
Total	1.4	17.1												

	AREA	\S		
	Gross Total	Glass		
		ft²	(%)	
Floor	1,107			Mai
Part	0			Aux
Int Door	. 0			Prel
ExFlr	20			Reh
Roof	1,123	0	0	Hun
Wall	0	0	0	Opt
Ext Doo	or 0	0	0	Tota

HEATING COIL SELECTION						
	Capacity	Coil Airflow	Ent	Lvg		
	MBh	cfm	°F	°F		
Main Htg	-6.8	103	51.6	111.1		
Aux Htg	0.0	0	0.0	0.0		
Preheat	0.0	0	0.0	0.0		
Reheat	-2.1	103	51.6	70.0		
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0		
Total	-6.8					

By RLF

Zone - 1-1-4

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 9 / 17 R: 84 / 76 / 1	25	Mo/Hr: OADB:		· · ·	Mo/Hr: He OADB: 38	eating Design B	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads			_		_		Envelope Loads	_	_	
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	1,088	1,088	5 :	0	0		0	-476	5.32
Glass Solar	5,355	0	5,355	26 ;	5,355	36	Glass Solar	0	0	0.00
Glass/Door Cond	566	0	566	3 :	566	4		-1,769	-1,769	19.77
Wall Cond	4,883	2,189	7,073	34	4,883	33		-1,171	-1,666	18.62
Partition/Door	0		0	0	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		-649	-649	7.25
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	1,845		1,845	9 :	367	2		-1,249	-1,249	13.95
Sub Total ==>	12,649	3,277	15,926	77	11,171	74	Sub Total ==>	-4,838	-5,810	64.91
Internal Loads							Internal Loads			
Lights	760	190	950	5 :	760	5	Lights	0	0	0.00
People	2,700	0	2,700	13	1,500	10		0	0	0.00
Misc	1,188	0	1,188	6	1,188	8		0	0	0.00
Sub Total ==>	4,648	190	4,838	23	3,448	23	Sub Total ==>	0	0	0.00
Ceiling Load	383	-383	0	0	383	3	Ceiling Load	-291	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	ŭ	· ·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	o:	0	0	Exhaust Heat		92	-1.03
Exhaust Heat	· ·	-121	-121	-1	ŭ	Ū	OA Preheat Diff.		0	0.00
Sup. Fan Heat		·	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-3,330	37.21
Duct Heat Pkup		0	0	0:			System Plenum Heat		98	-1.09
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	=	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	17,681	2,962	20,643	100.00	15,002	100.00	Grand Total ==>	-5,129	-8,950	100.00

TEMPERATURES						
Cooling Heating						
SADB	51.6	94.7				
Ra Plenum	78.1	67.6				
Return	78.1	67.6				
Ret/OA	78.1	67.6				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS						
	Cooling	Heating				
Diffuser	575	186				
Terminal Main Fan	575 575	186 186				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	35	35				
MinStop/Rh	186	186				
Return	610	221				
Exhaust	35	35				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft ²	1.48	0.48				
cfm/ton	334.05					
ft²/ton	226.13					
Btu/hr·ft ²	53.07	-23.01				
No. People	6					

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E nt °F	ter DB/W	/B/HR gr/lb	Lea °F	ve DB	/ WB/HR gr/lb
Main Clg Aux Clg	1.7 0.0	20.6 0.0	18.0 0.0	575 0	78.1 0.0	63.6 0.0	65.0 0.0	51.6 0.0	51.3 0.0	56.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.7	20.6								

Gro	AREAS	Glass	s (%)	
Floor Part	389 0			N
Int Door ExFIr	0 41			F
Roof Wall	512 487	0 99	0 20	H
Ext Door	0	0	0	7

HEA	TING COIL	SELECTIO	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-9.0	186	51.6	94.7
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-3.8	186	51.6	70.0
Humidif Opt Vent	0.0 0.0	0	0.0 0.0	0.0
Total	-9.0			

By RLF

Zone - 1-2-1

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/Hi	lr: 10 / 14 R: 82 / 72 / 1	02	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads						;	Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	. ,	0	0	0.00
Roof Cond	0	1,480	1,480	7	0	0		0	-518	6.34
Glass Solar	1,405	0	1,405	7	1,830	13		0	0	0.00
Glass/Door Cond	121	0	121	1;	-10	0		-590	-590	7.22
Wall Cond	6,589	2,352	8,940	43 ;	7,147	50		-1,479	-1,980	24.23
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-657	-657	8.04
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,545		1,545	7	-5	0	Infiltration	-1,650	-1,650	20.19
Sub Total ==>	9,659	3,832	13,491	64	8,962	63	Sub Total ==>	-4,375	-5,395	66.02
Internal Loads							Internal Loads			
Lights	1,123	281	1,403	7	1,123	8	Lights	0	0	0.00
People	5,400	0	5,400	26	3,000	21	People	0	0	0.00
Misc	717	0	717	3	717	5	Misc	0	0	0.00
Sub Total ==>	7,239	281	7,520	36	4,839	34	Sub Total ==>	0	0	0.00
Ceiling Load	578	-578	0	0	508	4	Ceiling Load	-385	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	140		140	1	0	0	Exhaust Heat	•	122	-1.49
Exhaust Heat	110	-183	-183	-1	Ŭ		OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-2,973	36.39
Duct Heat Pkup		0	0	0			System Plenum Heat		75	-0.91
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0		:	Supply Air Leakage		0	0.00
Grand Total ==>	17,617	3,352	20,968	100.00	14,309	100.00	Grand Total ==>	-4,761	-8,172	100.00

TEMPERATURES						
Cooling Heating						
SADB	51.6	95.7				
Ra Plenum	78.6	67.6				
Return	78.6	67.6				
Ret/OA	78.6	67.6				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS					
	Cooling	Heating			
Diffuser	548	166			
Terminal Main Fan	548 548	166 166			
Sec Fan	0	0			
Nom Vent	0	0			
AHU Vent	0	0			
Infil	46	46			
MinStop/Rh	166	166			
Return	594	212			
Exhaust	46	46			
Rm Exh	0	0			
Auxiliary	0	0			
Leakage Dwn	0	0			
Leakage Ups	0	0			

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	1.07	0.32				
cfm/ton	313.68					
ft²/ton	294.16					
Btu/hr·ft²	40.79	-15.90				
No. People	12					

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E nt °F	ter DB/W	/B/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	1.8	21.0	17.4	537	78.6	63.8	65.0	51.6	50.3	52.2
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	1.8	21.0								

	ARE			
	Gross Total	Glas ft²	s (%)	
Floor	514			Ma
Part	0			Αu
Int Door	0			Pr
ExFlr	41			Re
Roof	557	0	0	Hu
Wall	492	33	7	Op
Ext Doo	r 0	0	0	То

HEA	TING COIL	SELECTIO	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-8.2	166	51.6	95.7
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-3.4	166	51.6	70.0
Humidif Opt Vent	0.0	0	0.0	0.0
Total	-8.2			

By RLF

Zone - 1-2-2

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time:		r: 7 / 17	:	Mo/Hr:		, ,		eating Design	
0	utside Air:	OADB/WB/HF	R: 87 / 78 / 1	32	OADB:	85	1 1 1	OADB: 38	3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	572	572	9	0	0		0	-274	6.19
Glass Solar	682	0	682	10	745	18	Glass Solar	0	0	0.00
Glass/Door Cond	460	0	460	7 :	407	10		-1,179	-1,179	26.67
Wall Cond	1,001	425	1,427	22 :	1,102	26		-749	-1,069	24.18
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-420	-420	9.50
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,459		1,459	22 ;	273	6	Infiltration	-867	-867	19.60
Sub Total ==>	3,602	997	4,599	71	2,528	59	Sub Total ==>	-3,215	-3,809	86.12
Internal Loads				:			Internal Loads			
Lights	590	147	737	11	590	14	Lights	0	0	0.00
People	900	0	900	14	500	12	People	0	0	0.00
Misc	375	0	375	6	375	9	Misc	0	0	0.00
Sub Total ==>	1,865	147	2,013	31	1,465	34	Sub Total ==>	0	0	0.00
Ceiling Load	298	-298	0	0	260	6	Ceiling Load	-202	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0:	_		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		64	-1.45
Exhaust Heat	· ·	-94	-94	-1	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0 :			Additional Reheat		-877	19.82
Duct Heat Pkup		0	0	0 :			System Plenum Heat		199	-4.49
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	5,765	753	6,518	100.00	4,253	100.00	Grand Total ==>	-3,417	-4,423	100.00

TEMPERATURES								
	Cooling	Heating						
SADB	51.6	132.6						
Ra Plenum	78.5	67.6						
Return	78.5	67.6						
Ret/OA	78.5	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS							
	Cooling	Heating					
Diffuser	163	49					
Terminal Main Fan	163 163	49 49					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	24	24					
MinStop/Rh	49	49					
Return	187	73					
Exhaust	24	24					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS								
Cooling Heating								
% OA	0.0	0.0						
cfm/ft ²	0.60	0.18						
cfm/ton	299.97							
ft²/ton	497.12							
Btu/hr·ft ²	24.14	-16.38						
No. People	2							

COOLING COIL SELECTION										
	Total C ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E nt °F	er DB/W	/B/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.5	6.5	5.0	162	78.5	63.8	65.0	51.6		50.3
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	6.5								

Gro	AREAS	Glass	s (%)	
Floor	270			
Part	0			
Int Door	0			Ш
ExFlr	26			Ш
Roof	294	0	0	
Wall	315	66	21	Н
Ext Door	0	0	0	

HEAT	TING COIL	SELECTIO	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-4.4	49	51.6	132.6
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-1.0	49	51.6	70.0
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0
Total	-4.4			

By RLF

Zone - 1-2-3

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	r: 7 / 17 R: 87 / 78 / 1	32	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	451	451	8	0	0	Roof Cond	0	-216	5.68
Glass Solar	341	0	341	6	373	11	Glass Solar	0	0	0.00
Glass/Door Cond	411	0	411	8 :	364	11	Glass/Door Cond	-1,049	-1,049	27.61
Wall Cond	848	357	1,205	22 ;	933	27	; Wall Cond	-634	-903	23.78
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-440	-440	11.59
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,155		1,155	22	216	6	Infiltration	-686	-686	18.06
Sub Total ==>	2,754	808	3,562	66	1,886	55	Sub Total ==>	-2,809	-3,293	86.72
Internal Loads							Internal Loads			
Lights	467	117	583	11	467	13	Lights	0	0	0.00
People	900	0	900	17	500	14	People	0	0	0.00
Misc	399	0	399	7	399	12		0	0	0.00
Sub Total ==>	1,766	117	1,883	35	1,366	40	'	0	0	0.00
Ceiling Load	235	-235	0	0	206	6	Ceiling Load	-160	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	-	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	ŭ	ŭ	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		51	-1.33
Exhaust Heat	· ·	-75	-75	-1	Ŭ	Ū	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-723	19.03
Duct Heat Pkup		Ö	Ö	0:			System Plenum Heat		168	-4.42
Underfir Sup Ht Pku	ıp		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	4,755	615	5,370	100.00	3,458	100.00	Grand Total ==>	-2,969	-3,798	100.00

TEMPERATURES								
	Cooling	Heating						
SADB	51.6	135.9						
Ra Plenum	78.5	67.6						
Return	78.5	67.6						
Ret/OA	78.5	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS						
Cooling	Heating					
132	40					
132 132	40 40					
0	0					
0	0					
0	0					
19	19					
40	40					
152	60					
19	19					
0	0					
0	0					
0	0					
0	0					
	Cooling 132 132 132 0 0 0 19 40 152 19 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0					

ENGINEERING CKS							
	Cooling Heating						
% OA	0.0	0.0					
cfm/ft²	0.62	0.19					
cfm/ton	295.97						
ft²/ton	477.31						
Btu/hr·ft²	25.14	-17.78					
No. People	2						

COOLING COIL SELECTION										
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	Ent °F	ter DB/W	/B/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.5	5.4	4.1	132	78.5	63.8	65.0	51.6		49.9
Aux Clg Opt Vent	0.0 0.0	0.0 0.0	0.0 0.0	0	0.0	0.0 0.0	0.0 0.0	0.0	0.0	0.0
Total	0.5	5.4								

	AREAS	;][
G	ross Total	Glas		
		ft²	(%)	
Floor	214			I
Part	0			1
Int Door	0			F
ExFlr	28			F
Roof	232	0	0	+
Wall	243	33	14	
Ext Door	21	0	0	7

HEATING COIL SELECTION							
	Capacity	Coil Airflow	Ent	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-3.8	40	51.6	135.9			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Reheat	-0.8	40	51.6	70.0			
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0			
Total	-3.8						

By RLF

Zone - 1-2-4

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	1,307	1,307	13	0	0		0	-473	14.65
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	2,493		2,493	25	610	10	Infiltration	-1,502	-1,502	46.58
Sub Total ==>	2,493	1,307	3,800	38	610	10	Sub Total ==>	-1,502	-1,975	61.23
Internal Loads							Internal Loads			
Lights	1,022	256	1,278	13	1,022	18	Lights	0	0	0.00
People	3,600	0	3,600	36	2,000	34	People	0	0	0.00
Misc	1,597	0	1,597	16	1,597	27	Misc	0	0	0.00
Sub Total ==>	6,220	256	6,475	64	4,620	79	Sub Total ==>	0	0	0.00
Ceiling Load	588	-588	0	0	588	10	Ceiling Load	-351	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		111	-3.44
Exhaust Heat	Ü	-186	-186	-2	Ŭ	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-1,196	37.09
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		-165	5.12
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	9,300	789	10,089	100.00	5,818	100.00	Grand Total ==>	-1,853	-3,226	100.00

TEMPERATURES						
Cooling Heating						
SADB	51.6	94.9				
Ra Plenum	79.0	67.6				
Return	79.0	67.6				
Ret/OA	79.0	67.6				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS							
Cooling Heating							
Diffuser	223	67					
Terminal Main Fan	223 223	67 67					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	42	42					
MinStop/Rh	67	67					
Return	265	109					
Exhaust	42	42					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.48	0.14				
cfm/ton	265.05					
ft²/ton	556.64					
Btu/hr·ft ²	21.56	-6.89				
No. People	8					

COOLING COIL SELECTION												
	Total (Total Capacity		Total Capacity Sens Cap. Coil Air		Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb		
Main Clg	0.8	10.1	6.6	223	79.0	63.9	65.0	51.6	48.0	44.1		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.8	10.1										

	AREAS			
•	Gross Total	Glass ft ²	s (%)	
Floor	468		(70)	Ma
Part	0			Au
Int Door	0			Pre
ExFlr	0			Rel
Roof	508	0	0	Hu
Wall	0	0	0	Op
Ext Door	. 0	0	0	Tot

HEATING COIL SELECTION							
	Capacity	Coil Airflow	Ent	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-3.2	67	51.6	94.9			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Reheat	-1.4	67	51.6	70.0			
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0			
Total	-3.2						

Zone Checksums

By RLF

Zone - 1-2-5

	COOLING COIL PEAK				CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 8 / 15 R: 87 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	2,411	2,411	9	0	0		0	-834	9.93
Glass Solar	340	0	340	1;	598	3	,	0	0	0.00
Glass/Door Cond	119	0	119	0 ;	104	1		-295	-295	3.51
Wall Cond	374	178	552	2 ;	512	3	-	-145	-212	2.53
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-88	-88	1.05
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	,	0.00	0.00	0.00
Infiltration	4,153		4,153	16 ;	862	4	1	-2,532	-2,532	30.16
Sub Total ==>	4,985	2,589	7,574	30	2,076	11	Sub Total ==>	-3,060	-3,961	47.18
Internal Loads				:			Internal Loads			
Lights	1,722	431	2,153	8 :	1,722	9	Lights	0	0	0.00
People	2,700	0	2,700	11	1,500	8	People	0	0	0.00
Misc	13,505	0	13,505	53	13,505	68		0	0	0.00
Sub Total ==>	17,928	431	18,358	72	16,728	85	Sub Total ==>	0	0	0.00
Ceiling Load	978	-978	0	0 :	935	5	Ceiling Load	-591	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	•	187	-2.23
Exhaust Heat	· ·	-310	-310	-1	Ŭ	Ū	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-4,134	49.26
Duct Heat Pkup		0	0	0			System Plenum Heat		-486	5.79
Underfir Sup Ht Pku	p		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	23,891	1,731	25,622	100.00	19,739	100.00	Grand Total ==>	-3,650	-8,394	100.00

TEMPERATURES									
Cooling Heating									
SADB	51.6	84.2							
Ra Plenum	78.9	67.6							
Return	78.9	67.6							
Ret/OA	78.9	67.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS									
Cooling Heating									
Diffuser	756	231							
Terminal Main Fan	756 756	231 231							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	71	71							
MinStop/Rh	231	231							
Return	827	302							
Exhaust	71	71							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS									
Cooling Heating									
% OA	0.0	0.0							
cfm/ft²	0.96	0.29							
cfm/ton	354.12								
ft²/ton	369.32								
Btu/hr·ft ²	32.49	-10.64							
No. People	6								

	COOLING COIL SELECTION											
	Total Capacity ton MBh				Sens Cap. MBh	Coil Airflow cfm	E nt °F	ter DB/W	/B/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	2.1	25.6	21.3	748	78.9	63.9	65.0		51.5	56.7		
Aux Clg Opt Vent	0.0 0.0	0.0 0.0	0.0 0.0	0	0.0	0.0 0.0	0.0 0.0	0.0	0.0	0.0		
Total	2.1	25.6										

G	Glass	; (%)		
Floor	789			
Part	0			
Int Door	0			
ExFlr	6			Ш
Roof	896	0	0	П
Wall	66	16	25	
Ext Door	0	0	0	

HEATING COIL SELECTION										
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-8.4	231	51.6	84.2						
Aux Htg	0.0	0	0.0	0.0						
Preheat	0.0	0	0.0	0.0						
Reheat	-4.7	231	51.6	70.0						
Humidif Opt Vent	0.0 0.0	0	0.0	0.0						
Total	-8.4									

Zone Checksums

By RLF

Zone - 1-2-6

	COOLING COIL PEAK				CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 9 / 14 R: 86 / 76 / 1	20	Mo/Hr: OADB:		· ·	Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads				- :			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	, ,	0	0	0.00
Roof Cond	0	840	840	14	0	0		0	-275	7.07
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	308	0	308	5 ;	308	9		-918	-918	23.62
Wall Cond	1,157	473	1,629	27 :	1,157	32		-541	-766	19.70
Partition/Door	0		0	0	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-440	-440	11.33
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	, ,	0.00	0.00	0.00
Infiltration	1,223		1,223	21 ;	286	8	Infiltration	-872	-872	22.45
Sub Total ==>	2,688	1,313	4,001	67	1,751	49	Sub Total ==>	-2,772	-3,270	84.17
Internal Loads							Internal Loads			
Lights	593	148	742	12	593	17	Lights	0	0	0.00
People	900	0	900	15	500	14	People	0	0	0.00
Misc	399	0	399	7	399	11	Misc	0	0	0.00
Sub Total ==>	1,893	148	2,041	34	1,493	42	Sub Total ==>	0	0	0.00
Ceiling Load	328	-328	0	0	328	9	Ceiling Load	-204	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0 :	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		64	-1.66
Exhaust Heat	· ·	-104	-104	-2	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-793	20.42
Duct Heat Pkup		0	0	0			System Plenum Heat		114	-2.93
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	4,909	1,029	5,938	100.00	3,572	100.00	Grand Total ==>	-2,975	-3,885	100.00

TEMPERATURES									
Cooling Heating									
SADB	51.6	130.2							
Ra Plenum	78.8	67.6							
Return	78.8	67.6							
Ret/OA	78.8	67.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS									
Cooling Heating									
Diffuser	137	44							
Terminal Main Fan	137 137	44 44							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	24	24							
MinStop/Rh	44	44							
Return	161	69							
Exhaust	24	24							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS									
Cooling Heating									
% OA	0.0	0.0							
cfm/ft ²	0.50	0.16							
cfm/ton	276.50								
ft²/ton	548.96								
Btu/hr·ft²	21.86	-14.30							
No. People	2								

	COOLING COIL SELECTION											
	Total Capacity Sens Cap. Coil A		Total Capacity Sens Cap.		Enter DB/WB/HR °F °F gr/lb			Leave DB/WB/HR °F °F gr/lb				
Main Clg	0.5	5.9	4.6	cfm 137	78.8	63.9	65.0	51.6		46.5		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.5	5.9										

	AREA Gross Total	AS Glass ft²	(%)	
Floor Part	272 0			Main I Aux H
Int Door ExFir	· 0 28			Prehe Rehea
Roof Wall	295 178	0 0	0 0	Humic Opt Ve
Ext Doo	or 42	0	0	Total

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-3.9	44	51.6	130.2				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.9	44	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0				
Total	-3.9							

By RLF

101 W TLT

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 15 : 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads			_		_		Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	137	137	28	0	0	Roof Cond	0	-47	19.88
Glass Solar	0	0	0	0 :	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	250		250	50	61	27	t contract to the contract to	-151	-151	63.21
Sub Total ==>	250	137	387	78	61	27	Sub Total ==>	-151	-198	83.09
Internal Loads							Internal Loads			
Lights	103	26	128	26	103	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	103	26	128	26	103	46	Sub Total ==>	0	0	0.00
Ceiling Load	59	-59	0	0 :	59	26	Ceiling Load	-35	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		11	-4.67
Exhaust Heat	· ·	-19	-19	-4	ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0 :			Additional Reheat		-46	19.21
Duct Heat Pkup		0	0	0:			System Plenum Heat		-6	2.38
Underfir Sup Ht Pkuj	0		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	412	85	497	100.00	223	100.00	Grand Total ==>	-186	-239	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	135.1					
Ra Plenum	79.0	67.6					
Return	79.0	67.6					
Ret/OA	79.0	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS							
	Cooling	Heating					
Diffuser	9	3					
Terminal Main Fan	9 9	3 3					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	4	4					
MinStop/Rh	3	3					
Return	13	7					
Exhaust	4	4					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	0.18	0.05					
cfm/ton	206.41						
ft²/ton	1,135.76						
Btu/hr·ft²	10.57	-5.08					
No. People	0.0	0.0/1000 ft ²					

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB °F	/WB/HR gr/lb
Main Clg Aux Clg	0.0 0.0	0.5 0.0	0.3 0.0	9	79.0 0.0	63.9 0.0	65.0 0.0	51.6 0.0	42.5 0.0	25.9 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.0	0.5								

	AREAS			
G	Gross Total	Glas:	s (%)	
Floor	47			ı
Part	0			
Int Door	0			ı
ExFlr	0			П
Roof	51	0	0	H
Wall	0	0	0	
Ext Door	0	0	0	11

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-0.2	3	51.6	135.1				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.1	3	51.6	70.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent Total	0.0 -0.2	0	0.0	0.0				

By RLF

102 M TLT

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 15 : 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	Percent Of Total
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	137	137	28	0	0		0	-47	19.88
Glass Solar	0	0	0	0	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0	; Wall Cond	0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	250		250	50	61	27	Infiltration	-151	-151	63.21
Sub Total ==>	250	137	387	78	61	27	Sub Total ==>	-151	-198	83.09
Internal Loads							Internal Loads			
Lights	103	26	128	26	103	46	Lights	0	0	0.00
People	0	0	0	0:	0	0	People	0	0	0.00
Misc	0	0	0	0:	0	0		0	0	0.00
Sub Total ==>	103	26	128	26	103	46	Sub Total ==>	0	0	0.00
Ceiling Load	59	-59	0	0	59	26	Ceiling Load	-35	0	0.00
Ventilation Load	0	-55	0	0 :	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	•				U	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing			0	0 ;	0	•	Exhaust Heat	U	11	-4.67
Exhaust Heat	0	-19	0 -19	0 : -4 :	0	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-19	-19	-4 ; 0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		-46	19.21
Duct Heat Pkup		0	0	0:			System Plenum Heat		-46 -6	2.38
Underfir Sup Ht Pku	ın	U	0	0:			Underfir Sup Ht Pkup		0	0.00
•	h	0	0	0					0	0.00
Supply Air Leakage		U	U	0			Supply Air Leakage		U	0.00
Grand Total ==>	412	85	497	100.00	223	100.00	Grand Total ==>	-186	-239	100.00

TEMPERATURES								
	Cooling Heating							
SADB	51.6	135.1						
Ra Plenum	79.0	67.6						
Return	79.0	67.6						
Ret/OA	79.0	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS							
	Cooling	Heating					
Diffuser	9	3					
Terminal Main Fan	9 9	3 3					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	4	4					
MinStop/Rh	3	3					
Return	13	7					
Exhaust	4	4					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENG	INEERING	скѕ
	Cooling	Heating
% OA	0.0	0.0
cfm/ft²	0.18	0.05
cfm/ton	206.41	
ft²/ton	1,135.76	
Btu/hr·ft²	10.57	-5.08
No. People	0.0	0.0/1000 ft ²

	COOLING COIL SELECTION											
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb		
Main Clg	0.0	0.5	0.3	9		63.9	65.0	51.6		25.9		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.0	0.5										
Total	0.0	0.5										

				- г
	AREAS			
(Gross Total	Glass	S	
		ft²	(%)	
Floor	47			
Part	0			
Int Door	0			ı
ExFlr	0			
Roof	51	0	0	
Wall	0	0	0	
Ext Door	0	0	0	H

I	HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-0.2	3	51.6	135.1						
Aux Htg	0.0	0	0.0	0.0						
Preheat	0.0	0	0.0	0.0						
Reheat	-0.1	3	51.6	70.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent <i>Total</i>	0.0 -0.2	0	0.0	0.0						

By RLF

103 RECEPTION/SCHEDULING

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
Peaked	d at Time:	Mo/Hr	: 7 / 15		Mo/Hr:	7 / 15		Mo/Hr: He	eating Design	
Οι	utside Air:	OADB/WB/HR	1: 88 / 78 / 1	29	OADB:	88		OADB: 38	3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	, 1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	952	952	15	0	0	Roof Cond	0	-328	15.25
Glass Solar	0	0	0	0 :	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	; Wall Cond	0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,731		1,731	27	424	12	Infiltration	-1,043	-1,043	48.57
Sub Total ==>	1,731	952	2,683	42	424	12	Sub Total ==>	-1,043	-1,371	63.81
Internal Loads							Internal Loads			
Lights	710	177	887	14	710	19	Lights	0	0	0.00
People	1,800	0	1,800	28	1,000	27	People	0	0	0.00
Misc	1,109	0	1,109	17	1,109	30	Misc	0	0	0.00
Sub Total ==>	3,619	177	3,797	60	2,819	77	Sub Total ==>	0	0	0.00
Ceiling Load	408	-408	0	0	408	11	Ceiling Load	-244	0	0.00
Ventilation Load	0	0	0	0;	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	O	0	0:	0	-	Adj Air Trans Heat	0	0	0.00
Dehumid. Ov Sizing	U		-		U	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing			0	0 ;		•	Exhaust Heat	U	77	-3.59
Exhaust Heat	0	-129	0 -129	0 ; -2 ;	0	U	OA Preheat Diff.		0	0.00
		-129	-129	-2 ; 0 :			RA Preheat Diff.		0	0.00
Sup. Fan Heat		0	0	0:			Additional Reheat		-751	34.95
Ret. Fan Heat Duct Heat Pkup		0 0	0	0:			System Plenum Heat		-751 -104	4.83
•		U	0	0:			Underfir Sup Ht Pkup		0	0.00
Underfir Sup Ht Pkup	μ	0	0	0					0	0.00
Supply Air Leakage		U	U	0 :			Supply Air Leakage		U	0.00
Grand Total ==>	5,758	593	6,351	100.00	3,651	100.00	Grand Total ==>	-1,287	-2,148	100.00

ТЕМ	PERATURE	S
	Cooling	Heating
SADB	51.6	97.5
Ra Plenum	79.0	67.6
Return	79.0	67.6
Ret/OA	79.0	67.6
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRI	FLOWS	
	Cooling	Heating
Diffuser	140	42
Terminal Main Fan	140 140	42 42
Sec Fan	0	0
Nom Vent	0	0
AHU Vent	0	0
Infil	29	29
MinStop/Rh	42	42
Return	169	71
Exhaust	29	29
Rm Exh	0	0
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENG	ENGINEERING CKS									
	Cooling Heating									
% OA	0.0	0.0								
cfm/ft²	0.43	0.13								
cfm/ton	264.26									
ft²/ton	614.09									
Btu/hr·ft²	19.54	-6.61								
No. People	4.0	12.3/1000 ft ²								

	COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb	
Main Clg	0.5	6.4	4.2	140		63.9	65.0	51.6		43.9	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	0.5	6.4									

	AREAS][
G	ross Total	Glas:	s (%)	
Floor	325		(70)	I
Part	0			4
Int Door	0			F
ExFlr	0			F
Roof	352	0	0	+
Wall	0	0	0	
Ext Door	0	0	0	7

Н	HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-2.2	42	51.6	97.5						
Aux Htg	0.0	0	0.0	0.0						
Preheat	0.0	0	0.0	0.0						
Reheat	-0.9	42	51.6	70.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent Total	0.0 -2.2	0	0.0	0.0						

By RLF

104 EXAM ROOM 1

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	: 7 / 15 : 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design B	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 }	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	340	340	10	0	0	Roof Cond	0	-118	4.83
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	392	0	392	11 :	392	17	Glass/Door Cond	-918	-918	37.50
Wall Cond	428	203	632	18 ;	428	19		-324	-481	19.65
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-206	-206	8.40
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	623		623	18	153	7	!	-376	-376	15.35
Sub Total ==>	1,443	543	1,986	56	973	43	Sub Total ==>	-1,823	-2,098	85.73
Internal Loads							Internal Loads			
Lights	256	64	319	9 :	256	11	Lights	0	0	0.00
People	900	0	900	25	500	22	People	0	0	0.00
Misc	399	0	399	11	399	18	Misc	0	0	0.00
Sub Total ==>	1,555	64	1,619	45	1,155	51	Sub Total ==>	0	0	0.00
Ceiling Load	147	-147	0	0	147	6	Ceiling Load	-88	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0;			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		28	-1.13
Exhaust Heat	· ·	-47	-47	-1	ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-468	19.11
Duct Heat Pkup		0	0	0 :			System Plenum Heat		91	-3.71
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	3,145	414	3,559	100.00	2,274	100.00	Grand Total ==>	-1,910	-2,447	100.00

TEMPERATURES							
	Cooling	Heating					
SADB	51.6	135.6					
Ra Plenum	79.0	67.6					
Return	79.0	67.6					
Ret/OA	79.0	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS						
	Cooling	Heating				
Diffuser	87	26				
Terminal Main Fan	87 87	26 26				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	11	11				
MinStop/Rh	26	26				
Return	98	37				
Exhaust	11	11				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.74	0.22				
cfm/ton	293.76					
ft²/ton	394.52					
Btu/hr·ft²	30.42	-20.91				
No. People	2.0	17.1/1000 ft ²				

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.3	3.6	2.7	87	79.0	63.9	65.0	51.6	49.8	50.4
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.6								

G	AREAS Gross Total	Glas	s	
		ft²	(%)	
Floor	117			Ma
Part	0			Au
Int Door	0			Pre
ExFlr	13			Re
Roof	127	0	0	Hu
Wall	112	0	0	Op
Ext Door	42	0	0	To

HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-2.5	26	51.6	135.6					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	0	0.0	0.0					
Reheat	-0.5	26	51.6	70.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-2.5								

By RLF

105 EXAM ROOM 2

COOLING COIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK			
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 15 :: 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	Percent Of Total
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads				- 1			Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	340	340	13	0	0		0	-118	14.65
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	623		623	25	153	10		-376	-376	46.58
Sub Total ==>	623	340	963	38	153	10	Sub Total ==>	-376	-494	61.23
Internal Loads				:			Internal Loads			
Lights	256	64	319	13	256	18	Lights	0	0	0.00
People	900	0	900	35	500	34	People	0	0	0.00
Misc	399	0	399	16	399	27	Misc	0	0	0.00
Sub Total ==>	1,555	64	1,619	64	1,155	79	Sub Total ==>	0	0	0.00
Ceiling Load	147	-147	0	0 :	147	10	Ceiling Load	-88	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		28	-3.44
Exhaust Heat	ū	-47	-47	-2	ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0 :			Additional Reheat		-299	37.09
Duct Heat Pkup		0	0	0:			System Plenum Heat		-41	5.12
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,325	211	2,536	100.00	1,454	100.00	Grand Total ==>	-463	-806	100.00

TEMPERATURES						
	Cooling	Heating				
SADB	51.6	94.9				
Ra Plenum	79.0	67.6				
Return	79.0	67.6				
Ret/OA	79.0	67.6				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS						
	Cooling	Heating				
Diffuser	56	17				
Terminal Main Fan	56 56	17 17				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	11	11				
MinStop/Rh	17	17				
Return	66	27				
Exhaust	11	11				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS						
	Cooling	Heating				
% OA	0.0	0.0				
cfm/ft²	0.48	0.14				
cfm/ton	263.66					
ft²/ton	553.72					
Btu/hr·ft²	21.67	-6.89				
No. People	2.0	17.1/1000 ft ²				

COOLING COIL SELECTION										
	Total Capacity Sens Cap. Coil Airflow			Coil Airflow	En	ter DB	/WB/HR	Leave DB/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.2	2.5	1.7	56	79.0	63.9	65.0	51.6	47.9	43.8
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.5								

				- I
	AREAS			
(Gross Total		S	
		ft²	(%)	
Floor	117			N
Part	0			1
Int Door	0			F
ExFlr	0			F
Roof	127	0	0	+
Wall	0	0	0	
Ext Door	0	0	0	1 17

HEATING COIL SELECTION							
	Capacity	Coil Airflow	Ent	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-0.8	17	51.6	94.9			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Reheat	-0.3	17	51.6	70.0			
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0			
Total	-0.8						

Project Name: HealthFirst Medico

21184.TRC

Dataset Name:

By RLF

106 EXAM ROOM 3

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	7 / 15 1: 88 / 78 / 1	29	Mo/Hr: OADB:		· ·	Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0		0	0	0.00
Roof Cond	0	333	333	13	0	0		0	-118	14.65
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	623		623	25	153	10	t contract to the contract to	-376	-376	46.58
Sub Total ==>	623	333	956	38	153	10	Sub Total ==>	-376	-494	61.23
Internal Loads							Internal Loads			
Lights	256	64	319	13	256	18	Lights	0	0	0.00
People	900	0	900	36	500	34	People	0	0	0.00
Misc	399	0	399	16	399	27	Misc	0	0	0.00
Sub Total ==>	1,555	64	1,619	64	1,155	79	Sub Total ==>	0	0	0.00
Ceiling Load	147	-147	0	0	147	10	Ceiling Load	-88	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	·	28	-3.44
Exhaust Heat	Ū	-47	-47	-2	O	O	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-299	37.09
Duct Heat Pkup		Ö	0	0			System Plenum Heat		-41	5.12
Underfir Sup Ht Pku	p		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,325	204	2,529	100.00	1,454	100.00	Grand Total ==>	-463	-806	100.00

TEMPERATURES					
Cooling Heating					
SADB	51.6	94.9			
Ra Plenum	79.0	67.6			
Return	79.0	67.6			
Ret/OA	79.0	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS							
Cooling Heating							
Diffuser	56	17					
Terminal Main Fan	56 56	17 17					
Sec Fan	0	0					
Nom Vent	0	0					
AHU Vent	0	0					
Infil	11	11					
MinStop/Rh	17	17					
Return	66	27					
Exhaust	11	11					
Rm Exh	0	0					
Auxiliary	0	0					
Leakage Dwn	0	0					
Leakage Ups	0	0					

ENGINEERING CKS					
Cooling Heating					
% OA	0.0	0.0			
cfm/ft²	0.48	0.14			
cfm/ton	264.38				
ft²/ton	555.23				
Btu/hr·ft²	21.61	-6.89			
No. People	2.0	17.1/1000 ft ²			

COOLING COIL SELECTION										
		Capacity	Sens Cap.	Coil Airflow			/WB/HR			/WB/HR
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.2	2.5	1.7	56	79.0	63.9	65.0	51.6	48.0	43.9
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.5								

	AREAS			
	Gross Total	Glass		
		ft²	(%)	
Floor	117			ı
Part	0			1
Int Door	0			ŀ
ExFlr	0			ı
Roof	127	0	0	ŀ
Wall	0	0	0	ŀ
Ext Door	0	0	0	

HEATING COIL SELECTION						
	Capacity	Coil Airflow	Ent	Lvg		
	MBh	cfm	°F	°F		
Main Htg	-0.8	17	51.6	94.9		
Aux Htg	0.0	0	0.0	0.0		
Preheat	0.0	0	0.0	0.0		
Reheat	-0.3	17	51.6	70.0		
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0		
Total	-0.8					

Project Name: HealthFirst Medico

21184.TRC

Dataset Name:

By RLF

107 EXAMS ROOM 4

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	7 / 16 : 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	291	291	12	0	0		0	-118	14.65
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	649		649	26	153	10	Infiltration	-376	-376	46.58
Sub Total ==>	649	291	940	37	153	10	Sub Total ==>	-376	-494	61.23
Internal Loads							Internal Loads			
Lights	256	64	319	13	256	18	Lights	0	0	0.00
People	900	0	900	36	500	34	People	0	0	0.00
Misc	399	0	399	16	399	27	Misc	0	0	0.00
Sub Total ==>	1,555	64	1,619	64	1,155	79	Sub Total ==>	0	0	0.00
Ceiling Load	140	-140	0	0	147	10	Ceiling Load	-88	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0;	_	_	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		28	-3.44
Exhaust Heat	· ·	-44	-44	-2	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-299	37.09
Duct Heat Pkup		0	0	0			System Plenum Heat		-41	5.12
Underfir Sup Ht Pku	р		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,344	170	2,514	100.00	1,454	100.00	Grand Total ==>	-463	-806	100.00

TEMPERATURES						
Cooling Heating						
SADB	51.6	94.9				
Ra Plenum	78.8	67.6				
Return	78.8	67.6				
Ret/OA	78.8	67.6				
Fn MtrTD	0.0	0.0				
Fn BldTD	0.0	0.0				
Fn Frict	0.0	0.0				

AIRFLOWS						
Cooling Heating						
Diffuser	56	17				
Terminal Main Fan	56 56	17 17				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	11	11				
MinStop/Rh	17	17				
Return	66	27				
Exhaust	11	11				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS					
Cooling Heating					
% OA	0.0	0.0			
cfm/ft²	0.48	0.14			
cfm/ton	265.88				
ft²/ton	558.39				
Btu/hr·ft²	21.49	-6.89			
No. People	2.0	17.1/1000 ft ²			

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm		rter DB °F	/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	0.2 0.0	2.5 0.0	1.6 0.0	55 0	78.8 0.0	63.9 0.0	65.0 0.0	51.6 0.0	47.9 0.0	43.5 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.5								

	AREAS			
(Gross Total	Glass ft ²	; (%)	
		11	(70)	Ш
Floor	117			l
Part	0			
Int Door	0			ı
ExFlr	0			H
Roof	127	0	0	ŀ
Wall	0	0	0	
Ext Door	0	0	0	

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-0.8	17	51.6	94.9				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.3	17	51.6	70.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent Total	0.0 -0.8	0	0.0	0.0				

By RLF

108 EXAM ROOM 5

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	7 / 16 : 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	291	291	12	0	0		0	-118	14.65
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	649		649	26	153	10	Infiltration	-376	-376	46.58
Sub Total ==>	649	291	940	37	153	10	Sub Total ==>	-376	-494	61.23
Internal Loads							Internal Loads			
Lights	256	64	319	13	256	18	Lights	0	0	0.00
People	900	0	900	36	500	34	People	0	0	0.00
Misc	399	0	399	16	399	27	Misc	0	0	0.00
Sub Total ==>	1,555	64	1,619	64	1,155	79	Sub Total ==>	0	0	0.00
Ceiling Load	140	-140	0	0	147	10	Ceiling Load	-88	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0;	_	_	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		28	-3.44
Exhaust Heat	· ·	-44	-44	-2	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-299	37.09
Duct Heat Pkup		0	0	0			System Plenum Heat		-41	5.12
Underfir Sup Ht Pku	р		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,344	170	2,514	100.00	1,454	100.00	Grand Total ==>	-463	-806	100.00

TEMPERATURES								
	Cooling	Heating						
SADB	51.6	94.9						
Ra Plenum	78.8	67.6						
Return	78.8	67.6						
Ret/OA	78.8	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS										
Cooling Heating										
Diffuser	56	17								
Terminal Main Fan	56 56	17 17								
Sec Fan	0	0								
Nom Vent	0	0								
AHU Vent	0	0								
Infil	11	11								
MinStop/Rh	17	17								
Return	66	27								
Exhaust	11	11								
Rm Exh	0	0								
Auxiliary	0	0								
Leakage Dwn	0	0								
Leakage Ups	0	0								

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	cfm/ft ² 0.48 0.						
cfm/ton	265.88						
ft²/ton	558.39						
Btu/hr·ft² 21.49 -6.89							
No. People	2.0	17.1/1000 ft ²					

	COOLING COIL SELECTION									
Total C ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm			WB/HR gr/lb	Lea °F	ve DB/ °F	WB/HR gr/lb	
0.2	2.5	1.6	55	78.8	63.9	65.0	51.6	47.9	43.5	
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
0.2	2.5									
	ton 0.2 0.0 0.0	0.2 2.5 0.0 0.0 0.0 0.0	ton MBh MBh 0.2 2.5 1.6 0.0 0.0 0.0 0.0 0.0	ton MBh MBh cfm 0.2 2.5 1.6 55 0.0 0.0 0.0 0.0 0.0 0.0 0.0	ton MBh MBh cfm °F 0.2 2.5 1.6 55 78.8 0.0 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0.0	ton MBh MBh cfm °F °F 0.2 2.5 1.6 55 78.8 63.9 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0 0 0.0 0.0 0.0 0.0 0 0 0.0 0.0	ton MBh MBh cfm °F °F gr/lb 0.2 2.5 1.6 55 78.8 63.9 65.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	ton MBh MBh cfm °F °F gr/lb °F 0.2 2.5 1.6 55 78.8 63.9 65.0 51.6 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	ton MBh MBh cfm °F °F gr/lb °F °F 0.2 2.5 1.6 55 78.8 63.9 65.0 51.6 47.9 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	

	AREAS			
	Gross Total	Glass		
		ft²	(%)	
Floor	117			N
Part	0			1
Int Door	0			F
ExFlr	0			F
Roof	127	0	0	H
Wall	0	0	0	C
Ext Door	0	0	0	7

H	HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-0.8	17	51.6	94.9					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	0	0.0	0.0					
Reheat	-0.3	17	51.6	70.0					
Humidif	0.0	0	0.0	0.0					
Opt Vent Total	0.0 -0.8	0	0.0	0.0					

Project Name: HealthFirst Medico

21184.TRC

Dataset Name:

By RLF

109 PROVIDER OFF

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 17 R: 87 / 78 / 1	32	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0 }	0	0		0	0	0.00
Roof Cond	0	247	247	7	0	0		0	-118	5.34
Glass Solar	341	0	341	9	461	18	Glass Solar	0	0	0.00
Glass/Door Cond	230	0	230	6 :	128	5		-590	-590	26.65
Wall Cond	486	208	694	19 ;	574	23		-363	-520	23.52
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-206	-206	9.29
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	632		632	17	74	3	Infiltration	-376	-376	16.98
Sub Total ==>	1,689	455	2,144	58	1,237	49	Sub Total ==>	-1,534	-1,810	81.78
Internal Loads							Internal Loads			
Lights	256	64	319	9:	256	10	Lights	0	0	0.00
People	900	0	900	24	500	20	People	0	0	0.00
Misc	399	0	399	11	399	16		0	0	0.00
Sub Total ==>	1,555	64	1,619	43	1,155	46	Sub Total ==>	0	0	0.00
Ceiling Load	129	-129	0	0:	110	4	Ceiling Load	-88	0	0.00
Ventilation Load	0	0	0	0 :	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0:	-	_	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	•	28	-1.25
Exhaust Heat	Ū	-41	-41	-1	O	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		•	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-515	23.26
Duct Heat Pkup		Õ	Ő	0			System Plenum Heat		84	-3.79
Underfir Sup Ht Pku	q	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	· P	0	0	0 :			Supply Air Leakage		0	0.00
Grand Total ==>	3,373	349	3,722	100.00	2,503	100.00	Grand Total ==>	-1,622	-2,213	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	120.6						
Ra Plenum	78.5	67.6						
Return	78.5	67.6						
Ret/OA	78.5	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS								
Cooling Heating								
Diffuser	96	29						
Terminal Main Fan	96 96	29 29						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	11	11						
MinStop/Rh	29	29						
Return	106	39						
Exhaust	11	11						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.82	0.25				
cfm/ton	309.05					
ft²/ton	377.18					
Btu/hr·ft²	31.81	-18.91				
No. People	2.0	17.1/1000 ft ²				

COOLING COIL SELECTION										
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	En °F		/WB/HR gr/lb	Lea °F	ve DB °F	/WB/HR gr/lb
Main Clg	0.3	3.7	2.8	95		63.8	65.0	51.6		51.9
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.7								

	AREAS			
(Gross Total	Glass		
		ft²	(%)	
Floor	117			1
Part	0			1
Int Door	0			F
ExFlr	13			F
Roof	127	0	0	ŀ
Wall	154	33	21	(
Ext Door	0	0	0	7

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-2.2	29	51.6	120.6				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.6	29	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0				
Total	-2.2							

By RLF

110 EXAM ROOM 6

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	7 / 15 1: 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	328	328	13	0	0		0	-117	14.65
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	, ,	0.00	0.00	0.00
Infiltration	618		618	25 ;	151	10	t contract to the contract to	-372	-372	46.52
Sub Total ==>	618	328	946	38	151	10	Sub Total ==>	-372	-490	61.16
Internal Loads				:			Internal Loads			
Lights	253	63	317	13	253	18	Lights	0	0	0.00
People	900	0	900	36	500	35	People	0	0	0.00
Misc	396	0	396	16 [:]	396	27	Misc	0	0	0.00
Sub Total ==>	1,549	63	1,613	64	1,149	79	Sub Total ==>	0	0	0.00
Ceiling Load	146	-146	0	0 :	146	10	Ceiling Load	-87	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0 :	-		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	·	28	-3.44
Exhaust Heat	Ū	-46	-46	-2	O	O	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-297	37.15
Duct Heat Pkup		Ö	0	0			System Plenum Heat		-41	5.12
Underfir Sup Ht Pku	D		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,313	200	2,513	100.00	1,446	100.00	Grand Total ==>	-459	-801	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	94.8					
Ra Plenum	79.0	67.6					
Return	79.0	67.6					
Ret/OA	79.0	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	55	17						
Terminal Main Fan	55 55	17 17						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	10	10						
MinStop/Rh	17	17						
Return	66	27						
Exhaust	10	10						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.48	0.14				
cfm/ton	264.56					
ft ² /ton	553.98					
Btu/hr·ft²	21.66	-6.90				
No. People	2.0	17.2/1000 ft ²				

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB °F	/WB/HR gr/lb
Main Clg Aux Clg	0.2 0.0	2.5 0.0	1.7 0.0	55 0	79.0 0.0	63.9 0.0	65.0 0.0	51.6 0.0	48.0 0.0	44.0 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.5								

	AREAS			
	Gross Total	Glas		
		ft²	(%)	
Floor	116			
Part	0			
Int Door	0			
ExFlr	0			П
Roof	126	0	0	П
Wall	0	0	0	l
Ext Door	0	0	0	

HEATING COIL SELECTION							
	Capacity	Coil Airflow	Ent	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-0.8	17	51.6	94.8			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Reheat	-0.3	17	51.6	70.0			
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0			
Total	-0.8						

By RLF

111 TEAM STATION

COOLING COIL PEAK				CLG SPACE PEAK			HEATING COIL PEAK			
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 16 R: 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	373	373	10	0	0	,	0	-152	13.56
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	832		832	22	196	9	Infiltration	-482	-482	43.05
Sub Total ==>	832	373	1,205	31 ;	196	9	Sub Total ==>	-482	-633	56.61
Internal Loads							Internal Loads			
Lights	328	82	410	11	328	15	Lights	0	0	0.00
People	1,800	0	1,800	47	1,000	45	People	0	0	0.00
Misc	512	0	512	13	512	23	Misc	0	0	0.00
Sub Total ==>	2,640	82	2,722	70	1,840	83	Sub Total ==>	0	0	0.00
Ceiling Load	180	-180	0	0 :	188	8	Ceiling Load	-112	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	ŭ		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	36	-3.18
Exhaust Heat	O	-57	-57	-1	O	O	OA Preheat Diff.		0	0.00
Sup. Fan Heat		٠.	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-457	40.88
Duct Heat Pkup		0	Ö	0			System Plenum Heat		-64	5.69
Underfir Sup Ht Pku	D	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 :			Supply Air Leakage		0	0.00
Grand Total ==>	3,652	218	3,870	100.00	2,224	100.00	Grand Total ==>	-594	-1,119	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	90.9						
Ra Plenum	78.8	67.6						
Return	78.8	67.6						
Ret/OA	78.8	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS									
Cooling Heating									
Diffuser	85	26							
Terminal Main Fan	85 85	26 26							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	14	14							
MinStop/Rh	26	26							
Return	99	39							
Exhaust	14	14							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS								
Cooling Heating								
% OA	0.0	0.0						
cfm/ft²	0.57	0.17						
cfm/ton	264.10							
ft²/ton	465.10							
Btu/hr·ft²	25.80	-7.46						
No. People	4.0	26.7/1000 ft ²						

COOLING COIL SELECTION										
	Total (Total Capacity Sens Cap.		Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.3	3.9	2.4	85	78.8	63.9	65.0	51.6	47.8	43.1
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.9								

	AREAS			
	Gross Total	Glass ft ²	s (%)	
		11	(/0)	
Floor	150			l
Part	0			
Int Door	0			H
ExFlr	0			H
Roof	163	0	0	H
Wall	0	0	0	H
Ext Door	0	0	0	H

HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-1.1	26	51.6	90.9					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	0	0.0	0.0					
Reheat	-0.5	26	51.6	70.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-1.1								

By RLF

112 POC

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 16 : 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	50	50	24	0	0	Roof Cond	0	-20	20.15
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	111		111	53	26	27	Infiltration	-64	-64	63.21
Sub Total ==>	111	50	161	77	26	27	Sub Total ==>	-64	-85	83.35
Internal Loads							Internal Loads			
Lights	44	11	55	26	44	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0:	0	0	Misc	0	0	0.00
Sub Total ==>	44	11	55	26	44	46	Sub Total ==>	0	0	0.00
Ceiling Load	24	-24	0	0 :	25	26	Ceiling Load	-15	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0	_	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	Ü		0	0	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		5	-4.68
Exhaust Heat	Ü	-8	-8	-4	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-20	19.21
Duct Heat Pkup		Ö	0	0			System Plenum Heat		-2	2.11
Underfir Sup Ht Pku	0		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	179	30	208	100.00	95	100.00	Grand Total ==>	-79	-102	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	135.1						
Ra Plenum	78.8	67.6						
Return	78.8	67.6						
Ret/OA	78.8	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS								
Cooling Heating								
Diffuser	4	1						
Terminal	4	1						
Main Fan	4	1						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	2	2						
MinStop/Rh	1	1						
Return	5	3						
Exhaust	2	2						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	0.18	0.05					
cfm/ton	209.33						
ft²/ton	1,151.75						
Btu/hr·ft²	10.42	-5.08					
No. People	0.0	0.0/1000 ft ²					

	COOLING COIL SELECTION											
	Total (ton	Total Capacity ton MBh				Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB °F	/WB/HR gr/lb
Main Clg Aux Clg	0.0 0.0	0.2 0.0	0.1 0.0	4	78.8 0.0	63.9 0.0	65.0 0.0	51.6 0.0	42.2 0.0	25.0 0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.0	0.2										

Gre	AREAS	Glass	s (%)	
Floor Part	20 0			N
Int Door	0			F
ExFlr	0			F
Roof	22	0	0	
Wall	0	0	0	
Ext Door	0	0	0	117

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-0.1	1	51.6	135.1				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	0.0	1	51.6	70.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0	0	0.0	0.0				
Total	-0.1							

By RLF

113 ELEC

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 15 : 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	150	150	11	0	0		0	-56	7.58
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	284	86	369	28 ;	339	37		-214	-281	38.12
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-87	-87	11.78
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	293		293	22 :	35	4	1	-177	-177	23.98
Sub Total ==>	577	235	812	62	374	41	Sub Total ==>	-478	-600	81.46
Internal Loads				:			Internal Loads			
Lights	120	30	150	11	120	13	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	375	0	375	29	375	41		0	0	0.00
Sub Total ==>	496	30	526	40	496	54	Sub Total ==>	0	0	0.00
Ceiling Load	69	-69	0	0 :	52	6	Ceiling Load	-41	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	ŭ	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	ŭ	13	-1.77
Exhaust Heat	U	-22	-22	-2	O .	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-189	25.73
Duct Heat Pkup		0	Ö	0:			System Plenum Heat		40	-5.42
Underfir Sup Ht Pku	D	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,141	175	1,316	100.00	921	100.00	Grand Total ==>	-519	-736	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	114.0					
Ra Plenum	79.0	67.6					
Return	79.0	67.6					
Ret/OA	79.0	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	35	11						
Terminal Main Fan	35 35	11 11						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	5	5						
MinStop/Rh	11	11						
Return	40	16						
Exhaust	5	5						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.64	0.19				
cfm/ton	321.71					
ft²/ton	501.56					
Btu/hr·ft²	23.93	-13.39				
No. People	0.0	0.0/1000 ft ²				

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	En °F		/WB/HR gr/lb	Lea °F	ve DB	WB/HR gr/lb
Main Clg	0.1	1.3	1.1	35	79.0	63.9	65.0	51.6	51.2	55.3
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.3								

	AREAS			
(Gross Total	Glass		
		ft²	(%)	
Floor	55			ı
Part	0			1
Int Door	0			ı
ExFlr	5			ı
Roof	60	0	0	ŀ
Wall	65	0	0	(
Ext Door	0	0	0	

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-0.7	11	51.6	114.0				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.2	11	51.6	70.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent	0.0		0.0	0.0				
Total	-0.7							

By RLF

114 EVS

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	ed at Time: Outside Air:	Mo/H OADB/WB/HF	r: 7 / 17 R: 87 / 78 / 1	32	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0 }	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	121	121	9	0	0	Roof Cond	0	-58	4.55
Glass Solar	341	0	341	24	461	47		0	0	0.00
Glass/Door Cond	230	0	230	16 :	128	13		-590	-590	46.48
Wall Cond	154	107	261	19 ;	182	18	Wall Cond	-115	-196	15.43
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-105	-105	8.30
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	308		308	22	36	4	Infiltration	-183	-183	14.42
Sub Total ==>	1,033	227	1,260	90	808	82	Sub Total ==>	-993	-1,131	89.18
Internal Loads							Internal Loads			
Lights	125	31	156	11	125	13	Lights	0	0	0.00
People	0	0	0	0;	0	0	People	0	0	0.00
Misc	0	0	0	0:	0	0	Misc	0	0	0.00
Sub Total ==>	125	31	156	11	125	13	!	0	0	0.00
Ceiling Load	63	-63	0	0	54	5	Ceiling Load	-43	0	0.00
Ventilation Load	0	-03	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	U	0	0	0	-	Adj Air Trans Heat	0	0	0.00
Dehumid. Ov Sizing	-		_		U	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	•		0	0 :		•	Exhaust Heat	U	14	-1.07
Exhaust Heat	0	-20	0 -20	0 ; -1	0	0	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-20	-20 0	0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		-203	15.98
Duct Heat Pkup		0	0	0:			System Plenum Heat		-203 52	-4.10
Underfir Sup Ht Pku	ın	U	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
,		•							_	
Grand Total ==>	1,220	176	1,396	100.00	986	100.00	Grand Total ==>	-1,036	-1,269	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	152.0					
Ra Plenum	78.5	67.6					
Return	78.5	67.6					
Ret/OA	78.5	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	38	11						
Terminal Main Fan	38 38	11 11						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	5	5						
MinStop/Rh	11	11						
Return	43	16						
Exhaust	5	5						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS								
Cooling Heating								
% OA	0.0	0.0						
cfm/ft²	0.66	0.20						
cfm/ton	324.62							
ft²/ton	489.98							
Btu/hr·ft²	24.49	-22.26						
No. People	0.0	0.0/1000 ft ²						

COOLING COIL SELECTION											
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb	
Main Clg Aux Clg	0.1 0.0	1.4 0.0	1.2 0.0	37 0	78.5 0.0	63.8 0.0	65.0 0.0	51.6 0.0	51.0 0.0	54.7 0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	0.1	1.4									

	AREAS			
(Gross Total	Glass		
		ft²	(%)	
Floor	57			
Part	0			
Int Door	0			
ExFlr	7			
Roof	62	0	0	
Wall	79	33	42	ŀ
Ext Door	0	0	0	

Н	EATING COI	L SELECTI	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-1.3	11	51.6	152.0
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-0.2	11	51.6	70.0
Humidif	0.0	0	0.0	0.0
Opt Vent Total	0.0 -1.3	0	0.0	0.0

By RLF

115 SOIL

	COOLING COIL PEAK				CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	: 7 / 15 : 88 / 78 / 1	29	Mo/Hr: OADB:		· ·	Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	152	152	17	0	0		0	-57	9.53
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	240	72	312	35 ;	240	47		-181	-237	39.83
Partition/Door	0		0	0	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-73	-73	12.31
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	, ,	0.00	0.00	0.00
Infiltration	298		298	33 ;	73	14	t contract to the contract to	-180	-180	30.19
Sub Total ==>	538	225	763	85	313	62	Sub Total ==>	-434	-547	91.86
Internal Loads				:			Internal Loads			
Lights	122	31	153	17	122	24	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	122	31	153	17	122	24	Sub Total ==>	0	0	0.00
Ceiling Load	70	-70	0	0 :	70	14	Ceiling Load	-42	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0:			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	-	13	-2.23
Exhaust Heat	· ·	-22	-22	-2	O	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-104	17.45
Duct Heat Pkup		Ö	0	0			System Plenum Heat		42	-7.08
Underfir Sup Ht Pku	p		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	731	163	893	100.00	505	100.00	Grand Total ==>	-476	-596	100.00

TEMPERATURES									
Cooling Heating									
SADB	51.6	143.6							
Ra Plenum	79.0	67.6							
Return	79.0	67.6							
Ret/OA	79.0	67.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS									
Cooling Heating									
Diffuser	19	6							
Terminal Main Fan	19 19	6 6							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	5	5							
MinStop/Rh	6	6							
Return	24	11							
Exhaust	5	5							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS								
Cooling Heating								
% OA	0.0	0.0						
cfm/ft²	0.35	0.10						
cfm/ton	260.05							
ft²/ton	752.22							
Btu/hr·ft²	15.95	-10.63						
No. People	0.0	0.0/1000 ft ²						

COOLING COIL SELECTION											
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F		/WB/HR gr/lb	
Main Clg	0.1	0.9	0.7	19	79.0	63.9	65.0	51.6	47.7	42.9	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	0.1	0.9									

Gros	AREAS s Total	Glass	; (%)	
Floor Part	56 0			N
Int Door ExFIr Roof	0 5 61	0	0	P R H
Wall	55	0	0	C
Ext Door	0	0	0	7

HE	ATING COI	L SELECTI	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-0.6	6	51.6	143.6
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-0.1	6	51.6	70.0
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0
Total	-0.6			

By RLF

116 MANAGER OFF

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	ed at Time: outside Air:	Mo/Hi OADB/WB/HR	r: 7 / 17 R: 87 / 78 / 1	32	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	Percent Of Total
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0		0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	216	216	7	0	0	Roof Cond	0	-103	5.67
Glass Solar	341	0	341	12	373	20	Glass Solar	0	0	0.00
Glass/Door Cond	230	0	230	8 ;	204	11 :	Glass/Door Cond	-590	-590	32.36
Wall Cond	318	157	474	16 :	350	19	Wall Cond	-238	-356	19.52
Partition/Door	0		0	0 :	0	0 :	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-155	-155	8.49
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	551		551	19	103	6	Infiltration	-327	-327	17.97
Sub Total ==>	1,440	373	1,812	61	1,029	56	Sub Total ==>	-1,309	-1,531	84.00
Internal Loads						:	Internal Loads			
Lights	223	56	279	9	223	12	Lights	0	0	0.00
People	900	0	900	30	500	27	People	0	0	0.00
Misc	0	0	0	0:	0	0		0	0	0.00
Sub Total ==>	1,123	56	1,179	40	723	39	Sub Total ==>	0	0	0.00
Ceiling Load	112	-112	0	0	98	5	Ceiling Load	-76	0	0.00
Ventilation Load	0	0	0	0 :	0	0	.	0	0	0.00
Adj Air Trans Heat	0	O	0	0	0	- ,	Adj Air Trans Heat	0	0	0.00
Dehumid. Ov Sizing	-		-		U	U :	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing			0	0 :	0		Exhaust Heat	U	24	-1.33
Exhaust Heat	0	-36	0 -36	0 ; -1 ·	0	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-30	-36	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		-381	20.88
Duct Heat Pkup		0	0	0:		;	System Plenum Heat		-361 65	-3.55
Underfir Sup Ht Pku	ın	U	0	0:		;	Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,675	280	2,955	100.00	1,850	100.00	Grand Total ==>	-1,386	-1,823	100.00

TEMPERATURES					
	Cooling	Heating			
SADB	51.6	128.5			
Ra Plenum	78.5	67.6			
Return	78.5	67.6			
Ret/OA	78.5	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS						
	Cooling	Heating				
Diffuser	71	21				
Terminal Main Fan	71 71	21 21				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	9	9				
MinStop/Rh	21	21				
Return	80	30				
Exhaust	9	9				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS						
	Cooling	Heating				
% OA	0.0	0.0				
cfm/ft²	0.69	0.21				
cfm/ton	287.82					
ft²/ton	414.18					
Btu/hr·ft²	28.97	-17.87				
No. People	2.0	19.6/1000 ft²				

COOLING COIL SELECTION										
	Total Capacity		Sens Cap.	Coil Airflow			/WB/HR			/WB/HR
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.3	3.0	2.1	71	78.5	63.8	65.0	51.6	49.2	48.1
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.0								

	AREAS			
(Gross Total	Glas:	s (%)	
Floor	102		(70)	,
Part	0			
Int Door	0			F
ExFlr	10			F
Roof	111	0	0	H
Wall	116	33	28	
Ext Door	0	0	0	7

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-1.8	21	51.6	128.5				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.4	21	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0				
Total	-1.8							

Project Name: HealthFirst Medico

21184.TRC

Dataset Name:

By RLF

117 BREAK ROOM

	COOLING C	OIL PEAK			CLG SPACE	PEAK	K HEATING COIL PEAK			
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	r: 7 / 17 R: 87 / 78 / 1	32	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	, 1	Btu/h	Btu/h	(%)
Envelope Loads				1		` '	Envelope Loads			` '
Skylite Solar	0	0	0	0 :	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	389	389	5	0	0	Roof Cond	0	-186	4.80
Glass Solar	341	0	341	4	373	7	Glass Solar	0	0	0.00
Glass/Door Cond	411	0	411	5 :	364	7	Glass/Door Cond	-1,049	-1,049	27.02
Wall Cond	784	337	1,122	14 ;	863	17	; Wall Cond	-586	-841	21.67
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-333	-333	8.58
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,000		1,000	13	187	4	Infiltration	-594	-594	15.30
Sub Total ==>	2,536	726	3,262	41	1,787	36	Sub Total ==>	-2,562	-3,003	77.37
Internal Loads							Internal Loads			
Lights	404	101	505	6	404	8	Lights	0	0	0.00
People	3,600	0	3,600	45	2,000	40		0	0	0.00
Misc	631	0	631	8	631	13		0	0	0.00
Sub Total ==>	4,636	101	4,737	60	3,036	61	Sub Total ==>	0	0	0.00
Ceiling Load	204	-204	0	0	178	4	Ceiling Load	-139	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	o o	· ·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	· ·	44	-1.13
Exhaust Heat	U	-65	-65	-1	O	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		•	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-1,028	26.50
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		106	-2.74
Underfir Sup Ht Pku	ıp		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	7,375	559	7,934	100.00	5,001	100.00	Grand Total ==>	-2,701	-3,881	100.00

TEMPERATURES					
	Cooling	Heating			
SADB	51.6	112.2			
Ra Plenum	78.5	67.6			
Return	78.5	67.6			
Ret/OA	78.5	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS								
	Cooling Heating							
Diffuser	192	57						
Terminal Main Fan	192 192	57 57						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	17	17						
MinStop/Rh	57	57						
Return	208	74						
Exhaust	17	17						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
	Cooling	Heating				
% OA	0.0	0.0				
cfm/ft²	1.04	0.31				
cfm/ton	289.72					
ft ² /ton	279.80					
Btu/hr·ft²	42.89	-20.98				
No. People	8.0	43.2/1000 ft ²				

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm		ter DB °F	/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.7	7.9	5.6	191		63.8	65.0	51.6		48.7
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.7	7.9								

	AREAS			
(Gross Total	Glass		
		ft²	(%)	
Floor	185			ı
Part	0			1
Int Door	0			ŀ
ExFlr	21			ı
Roof	200	0	0	ŀ
Wall	229	33	14	ŀ
Ext Door	21	0	0	:

HEATING COIL SELECTION						
	Capacity	Coil Airflow	Ent	Lvg		
	MBh	cfm	°F	°F		
Main Htg	-3.9	57	51.6	112.2		
Aux Htg	0.0	0	0.0	0.0		
Preheat	0.0	0	0.0	0.0		
Reheat	-1.2	57	51.6	70.0		
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0		
Total	-3.9					

By RLF

118 S TLT

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	r: 7 / 18 R: 85 / 77 / 1	27	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	! !	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	260	260	9	0	0		0	-119	7.95
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	1,754	565	2,319	80 :	1,754	91		-617	-808	53.92
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-250	-250	16.66
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	218		218	7	45	2	Infiltration	-141	-141	9.43
Sub Total ==>	1,972	825	2,797	96	1,799	93	Sub Total ==>	-1,008	-1,318	87.96
Internal Loads							Internal Loads			
Lights	96	24	120	4	96	5	Lights	0	0	0.00
People	0	0	0	0 :	0	0	, 0	0	0	0.00
Misc	0	0	0	0:	0	0		0	0	0.00
Sub Total ==>	96	24	120	4	96	5	Sub Total ==>	0	0	0.00
Ceiling Load	42	-42	0	0	42	2	Ceiling Load	-33	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0;			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	٥	Exhaust Heat	ŭ	10	-0.70
Exhaust Heat	U	-13	-13	0	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-398	26.59
Duct Heat Pkup		0	0	0:			System Plenum Heat		208	-13.86
Underfir Sup Ht Pku	ın	ŭ	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,110	793	2,903	100.00	1,937	100.00	Grand Total ==>	-1,041	-1,498	100.00

TEMPERATURES					
Cooling Heating					
SADB	51.6	112.0			
Ra Plenum	78.0	67.6			
Return	78.0	67.6			
Ret/OA	78.0	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS						
Cooling Heating						
Diffuser	74	22				
Terminal Main Fan	74 74	22 22				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	4	4				
MinStop/Rh	22	22				
Return	78	26				
Exhaust	4	4				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS					
Cooling Heating					
% OA	0.0	0.0			
cfm/ft²	1.69	0.51			
cfm/ton	306.69				
ft²/ton	181.86				
Btu/hr·ft²	65.98	-34.05			
No. People	0.0	0.0/1000 ft ²			

COOLING COIL SELECTION										
	Total (Capacity	Sens Cap.	Coil Airflow	Er	iter DB	/WB/HR	Lea	ve DB	/WB/HR
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.2	2.9	2.7	74	78.0	63.6	65.0	51.6	50.1	51.4
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.9								

	AREAS			
(Gross Total	Glass	-	
		ft²	(%)	
Floor	44			ı
Part	0			1
Int Door	0			ı
ExFlr	16			ı
Roof	128	0	0	ŀ
Wall	187	0	0	(
Ext Door	0	0	0	

HEATING COIL SELECTION						
	Capacity	Coil Airflow	Ent	Lvg		
	MBh	cfm	°F	°F		
Main Htg	-1.5	22	51.6	112.0		
Aux Htg	0.0	0	0.0	0.0		
Preheat	0.0	0	0.0	0.0		
Reheat	-0.5	22	51.6	70.0		
Humidif	0.0	0	0.0	0.0		
Opt Vent	0.0		0.0	0.0		
Total	-1.5					

By RLF

119 CONF/CONSULT

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	r: 8 / 17 R: 86 / 78 / 1	31	Mo/Hr: OADB:		· ·	Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1 1	Btu/h	Btu/h	(%)
Envelope Loads				- :			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	203	203	4	0	0		0	-102	5.01
Glass Solar	992	0	992	17	992	26	Glass Solar	0	0	0.00
Glass/Door Cond	109	0	109	2 :	109	3		-295	-295	14.44
Wall Cond	1,337	547	1,884	33 ;	1,337	34		-284	-394	19.27
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	-144	-144	7.05
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	536		536	9	113	3	Infiltration	-327	-327	16.03
Sub Total ==>	2,975	751	3,725	65	2,551	66	Sub Total ==>	-1,050	-1,262	61.80
Internal Loads							Internal Loads			
Lights	223	56	279	5	223	6	Lights	0	0	0.00
People	1,800	0	1,800	31	1,000	26	People	0	0	0.00
Misc	0	0	0	0	0	0		0	0	0.00
Sub Total ==>	2,023	56	2,079	36	1,223	31	Sub Total ==>	0	0	0.00
Ceiling Load	109	-109	0	0	109	3	Ceiling Load	-76	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :	_		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		24	-1.18
Exhaust Heat	· ·	-34	-34	-1	Ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-799	39.09
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		-6	0.29
Underfir Sup Ht Pku	ıp	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	5,106	663	5,769	100.00	3,883	100.00	Grand Total ==>	-1,126	-2,042	100.00

TEMPERATURES					
Cooling Heating					
SADB	51.6	92.7			
Ra Plenum	78.4	67.6			
Return	78.4	67.6			
Ret/OA	78.4	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS					
Cooling Heating					
Diffuser	149	45			
Terminal Main Fan	149 149	45 45			
Sec Fan	0	0			
Nom Vent	0	0			
AHU Vent	0	0			
Infil	9	9			
MinStop/Rh	45	45			
Return	158	54			
Exhaust	9	9			
Rm Exh	0	0			
Auxiliary	0	0			
Leakage Dwn	0	0			
Leakage Ups	0	0			

ENGINEERING CKS					
Cooling Heating					
% OA	0.0	0.0			
cfm/ft²	1.46	0.44			
cfm/ton	309.34				
ft²/ton	212.15				
Btu/hr·ft²	56.56	-20.02			
No. People	4.0	39.2/1000 ft ²			

COOLING COIL SELECTION											
Total C ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm			/WB/HR gr/lb	Lea °F	ve DB/ °F	WB/HR gr/lb		
0.5	5.8	4.6	149			65.0			52.3		
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
0.5	5.8										
	ton 0.5 0.0 0.0	0.5 5.8 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. 0.5 5.8 4.6 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm 0.5 5.8 4.6 149 0.0 0.0 0.0 0 0.0 0.0 0 0	Total Capacity ton Sens Cap. MBh Coil Airflow MBh Er cfm 0.5 5.8 4.6 149 78.4 0.0 0.0 0.0 0 0 0.0 0.0 0.0 0.0 0 0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Enter DB, °F °F 0.5 5.8 4.6 149 78.4 63.7 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow cfm Enter DB/WB/HR 0.5 5.8 4.6 149 78.4 63.7 65.0 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0.0 0.0 0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow cfm Enter DB/WB/HR °F Lea 0.5 5.8 4.6 149 78.4 63.7 65.0 51.6 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow cfm Enter DB/WB/HR °F °F Leave DB/ °F °F 0.5 5.8 4.6 149 78.4 63.7 65.0 51.6 50.3 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0		

	AREAS			
(Gross Total	Glass		
		ft²	(%)	
Floor	102			ľ
Part	0			1
Int Door	0			F
ExFlr	9			F
Roof	110	0	0	H
Wall	108	16	15	
Ext Door	0	0	0	7

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-2.0	45	51.6	92.7				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.9	45	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0				
Total	-2.0							

By RLF

120 PROVIDER OFF

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 8 / 17 R: 86 / 78 / 1	31	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:		;	Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	, ,	0	0	0.00
Roof Cond	0	294	294	6	0	0		0	-114	5.72
Glass Solar	992	0	992	20 ;	992	29	Glass Solar	0	0	0.00
Glass/Door Cond	109	0	109	2 :	109	3		-295	-295	14.87
Wall Cond	1,344	550	1,894	37 :	1,344	39		-285	-396	19.95
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-145	-145	7.29
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	594		594	12	125	4	Infiltration	-363	-363	18.29
Sub Total ==>	3,040	843	3,883	77	2,571	75	Sub Total ==>	-1,087	-1,311	66.12
Internal Loads							Internal Loads			
Lights	247	62	309	6	247	7	Lights	0	0	0.00
People	900	0	900	18	500	15	People	0	0	0.00
Misc	0	0	0	0 :	0	0		0	0	0.00
Sub Total ==>	1,147	62	1,209	24	747	22	Sub Total ==>	0	0	0.00
Ceiling Load	121	-121	0	0	121	4	Ceiling Load	-85	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	· ·		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	27	-1.35
Exhaust Heat	O	-38	-38	-1	O	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		00	0	0		;	RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-707	35.65
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		8	-0.42
Underfir Sup Ht Pku	ıp	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0		:	Supply Air Leakage		0	0.00
Grand Total ==>	4,307	746	5,054	100.00	3,438	100.00	Grand Total ==>	-1,172	-1,983	100.00

TEMPERATURES									
Cooling Heating									
SADB	51.6	96.6							
Ra Plenum	78.4	67.6							
Return	78.4	67.6							
Ret/OA	78.4	67.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS											
Cooling Heating											
Diffuser	132	40									
Terminal Main Fan	132 132	40 40									
Sec Fan	0	0									
Nom Vent	0	0									
AHU Vent	0	0									
Infil	10	10									
MinStop/Rh	40	40									
Return	142	50									
Exhaust	10	10									
Rm Exh	0	0									
Auxiliary	0	0									
Leakage Dwn	0	0									
Leakage Ups	0	0									

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.17	0.35					
cfm/ton	312.70						
ft²/ton	268.31						
Btu/hr·ft²	44.72	-17.55					
No. People	2.0	17.7/1000 ft ²					

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.4	5.1	4.2	132	78.4	63.7	65.0	51.6	50.5	52.9
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.4	5.1								

AREAS Gross Total Glass ft² (%)								
Floor Part	113 0		(70)	Ma Au				
Int Door	0			Pre				
ExFir Roof	9 122	0	0	Re Hu				
Wall	108	16	15	Op				
Ext Door	0	0	0	To				

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-2.0	40	51.6	96.6				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.8	40	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0				
Total	-2.0							

By RLF

121 EXAM ROOM 10

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 8 / 17 R: 86 / 78 / 1	31	Mo/Hr: OADB:			Mo/Hr: He OADB: 3	eating Design 8	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	· ·	Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	303	303	4 :	0	0	,	0	-117	4.33
Glass Solar	1,985	0	1,985	29 ;	1,985	40	-	0	0	0.00
Glass/Door Cond	218	0	218	3 ;	218	4		-590	-590	21.77
Wall Cond	1,407	682	2,089	31 ;	1,407	28		-299	-435	16.07
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-179	-179	6.62
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	,	0.00	0.00	0.00
Infiltration	610		610	9 :	128	3	Infiltration	-372	-372	13.75
Sub Total ==>	4,220	985	5,205	77	3,738	75	Sub Total ==>	-1,440	-1,694	62.53
Internal Loads							Internal Loads			
Lights	253	63	317	5 :	253	5	Lights	0	0	0.00
People	900	0	900	13	500	10	People	0	0	0.00
Misc	396	0	396	6	396	8	Misc	0	0	0.00
Sub Total ==>	1,549	63	1,613	24	1,149	23	Sub Total ==>	0	0	0.00
Ceiling Load	124	-124	0	0	124	2	Ceiling Load	-87	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0;		•	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		28	-1.02
Exhaust Heat	· ·	-39	-39	-1	ŭ	ŭ	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-1,031	38.04
Duct Heat Pkup		0	0	0			System Plenum Heat		-12	0.45
Underfir Sup Ht Pku	ıp		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	5,893	885	6,779	100.00	5,011	100.00	Grand Total ==>	-1,527	-2,709	100.00

TEMPERATURES									
Cooling Heating									
SADB	51.6	93.8							
Ra Plenum	78.4	67.6							
Return	78.4	67.6							
Ret/OA	78.4	67.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS						
	Cooling	Heating				
Diffuser	192	58				
Terminal Main Fan	192 192	58 58				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	10	10				
MinStop/Rh	58	58				
Return	202	68				
Exhaust	10	10				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.65	0.50					
cfm/ton	339.83						
ft²/ton	205.35						
Btu/hr·ft²	58.44	-23.36					
No. People	2.0	17.2/1000 ft ²					

Main Clg 0.6 6.8 5.9 192 78.4.63.7 6	r/lb °F °F gr/lb
•	5.0 51.6 51.5 56.7
Aux Clg 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0.0 0.0	0.0
Opt Vent 0.0 0.0 0.0 0.0 0.0 0.0 0.0	0.0 0.0 0.0

	AREAS			
(Gross Total	Glas:	s (%)	
			(70)	
Floor	116			
Part	0			1
Int Door	0			F
ExFlr	11			F
Roof	126	0	0	ŀ
Wall	135	33	25	
Ext Door	0	0	0	7

Н	EATING COI	L SELECTI	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-2.7	58	51.6	93.8
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-1.2	58	51.6	70.0
Humidif	0.0	0	0.0	0.0
Opt Vent <i>Total</i>	0.0 -2.7	0	0.0	0.0

By RLF

122 EXAM ROOM 9

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time:		r: 8 / 17	:	Mo/Hr:				eating Design	
	utside Air:	OADB/WB/HR	(: 80 / 78 / 1	31	OADB:	80	1 1 1	OADB: 38	5	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				1			Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0		0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	303	303	5	0	0		0	-117	4.49
Glass Solar	1,985	0	1,985	30	1,985	41	Glass Solar	0	0	0.00
Glass/Door Cond	218	0	218	3 ;	218	5		-590	-590	22.60
Wall Cond	1,221	621	1,841	28 :	1,221	25		-259	-384	14.70
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		-163	-163	6.26
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	610		610	9 :	128	3		-372	-372	14.27
Sub Total ==>	4,034	924	4,958	76	3,552	74	Sub Total ==>	-1,384	-1,626	62.32
Internal Loads							Internal Loads			
Lights	253	63	317	5 :	253	5	Lights	0	0	0.00
People	900	0	900	14	500	10	People	0	0	0.00
Misc	396	0	396	6	396	8	Misc	0	0	0.00
Sub Total ==>	1,549	63	1,613	25	1,149	24	Sub Total ==>	0	0	0.00
Ceiling Load	124	-124	0	0	124	3	Ceiling Load	-87	0	0.00
Ventilation Load	0	0	0	0:	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	-	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0;	_	•	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		28	-1.05
Exhaust Heat		-39	-39	-1			OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0 :			Additional Reheat		-992	38.02
Duct Heat Pkup		0	0	0 :			System Plenum Heat		-19	0.71
Underfir Sup Ht Pku	р		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	-	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	5,707	825	6,531	100.00	4,825	100.00	Grand Total ==>	-1,471	-2,610	100.00

TEMPERATURES					
	Cooling	Heating			
SADB	51.6	93.8			
Ra Plenum	78.4	67.6			
Return	78.4	67.6			
Ret/OA	78.4	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS					
	Cooling	Heating			
Diffuser	185	55			
Terminal Main Fan	185 185	55 55			
Sec Fan	0	0			
Nom Vent	0	0			
AHU Vent	0	0			
Infil	10	10			
MinStop/Rh	55	55			
Return	195	66			
Exhaust	10	10			
Rm Exh	0	0			
Auxiliary	0	0			
Leakage Dwn	0	0			
Leakage Ups	0	0			

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.59	0.48					
cfm/ton	339.57						
ft²/ton	213.13						
Btu/hr·ft²	56.30	-22.50					
No. People	2.0	17.2/1000 ft ²					

			COOLIN	G COIL SELE	CTIO	N				
	Total C ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm		ter DB °F	/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.5	6.5	5.7	185	78.4	63.7	65.0	51.6	51.5	56.7
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	6.5								

(AREAS Gross Total	Glas:	s (%)	
Floor Part	116 0			1
Int Door ExFir	0 10	•		F
Roof Wall	126 123	0 33	0 27	(
Ext Door	0	0	0	7

HE	ATING COI	L SELECTI	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-2.6	55	51.6	93.8
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-1.1	55	51.6	70.0
Humidif	0.0	0	0.0	0.0
Opt Vent <i>Total</i>	0.0 -2.6	0	0.0	0.0

By RLF

123 EXAM ROOM 8

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	:: 8 / 17 :: 86 / 78 / 1	31	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0 }	0	0		0	0	0.00
Roof Cond	0	303	303	5	0	0		0	-117	5.32
Glass Solar	992	0	992	17 ;	992	24	Glass Solar	0	0	0.00
Glass/Door Cond	109	0	109	2 ;	109	3		-295	-295	13.37
Wall Cond	1,557	619	2,176	38 ;	1,557	38		-330	-455	20.62
Partition/Door	0		0	0	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		-163	-163	7.39
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	610		610	11 ;	128	3		-372	-372	16.89
Sub Total ==>	3,269	922	4,191	73	2,787	69	Sub Total ==>	-1,160	-1,402	63.58
Internal Loads							Internal Loads			
Lights	253	63	317	5	253	6	Lights	0	0	0.00
People	900	0	900	16	500	12		0	0	0.00
Misc	396	0	396	7	396	10		0	0	0.00
Sub Total ==>	1,549	63	1,613	28	1,149	28	Sub Total ==>	0	0	0.00
Ceiling Load	124	-124	0	0	124	3	Ceiling Load	-87	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	ŭ	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	· ·	28	-1.25
Exhaust Heat	· ·	-39	-39	-1	O	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-835	37.86
Duct Heat Pkup		0	0	0			System Plenum Heat		4	-0.19
Underfir Sup Ht Pku	р		0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	4,942	823	5,764	100.00	4,060	100.00	Grand Total ==>	-1,247	-2,205	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	94.0						
Ra Plenum	78.4	67.6						
Return	78.4	67.6						
Ret/OA	78.4	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS									
Cooling Heating									
Diffuser	156	47							
Terminal Main Fan	156 156	47 47							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	10	10							
MinStop/Rh	47	47							
Return	166	57							
Exhaust	10	10							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	1.34	0.40					
cfm/ton	323.73						
ft²/ton	241.49						
Btu/hr·ft²	49.69	-19.01					
No. People	2.0	17.2/1000 ft ²					

COOLING COIL SELECTION										
Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm			/WB/HR gr/lb	Lea °F	ve DB/ °F	/WB/HR gr/lb	
0.5	5.8	4.9	156	78.4	63.7	65.0	51.6	51.0	54.8	
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
0.5	5.8									
	ton 0.5 0.0 0.0	0.5 5.8 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh 0.5 5.8 4.9 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow MBh 0.5 5.8 4.9 156 0.0 0.0 0.0 0 0.0 0.0 0 0	Total Capacity ton Sens Cap. MBh Coil Airflow MBh Er cfm 0.5 5.8 4.9 156 78.4 0.0 0.0 0.0 0 0 0.0 0.0 0.0 0.0 0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow Cfm Enter DB, °F °F 0.5 5.8 4.9 156 78.4 63.7 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0.0 0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow cfm Enter DB/WB/HR 0.5 5.8 4.9 156 78.4 63.7 65.0 0.0 0.0 0.0 0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow cfm Enter DB/WB/HR °F Lea 0.5 5.8 4.9 156 78.4 63.7 65.0 51.6 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Total Capacity ton Sens Cap. MBh Coil Airflow cfm Enter DB/WB/HR °F °F Leave DB/ °F °F 0.5 5.8 4.9 156 78.4 63.7 65.0 51.6 51.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	

	AREAS			
(Gross Total	Glass		
		ft²	(%)	
Floor	116			1
Part	0			1
Int Door	0			F
ExFlr	10			F
Roof	126	0	0	ŀ
Wall	122	16	14	(
Ext Door	0	0	0	7

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-2.2	47	51.6	94.0				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-1.0	47	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0				
Total	-2.2							

By RLF

124 MECH

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 11 / 14 R: 75 / 63 / 6	9	Mo/Hr: OADB:	,		Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	i !	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	. ,	0	0	0.00
Roof Cond	0	220	220	7	0	0		0	-125	8.74
Glass Solar	901	0	901	30 ;	994	43		0	0	0.00
Glass/Door Cond	-10	0	-10	0 :	-66	-3	Glass/Door Cond	-295	-295	20.68
Wall Cond	1,353	555	1,907	63 ;	1,358	59		-283	-393	27.53
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-144	-144	10.08
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	,	0.00	0.00	0.00
Infiltration	9		9	0 :	-24	-1	Infiltration	-132	-132	9.23
Sub Total ==>	2,252	774	3,027	100	2,262	98	Sub Total ==>	-853	-1,087	76.26
Internal Loads							Internal Loads			
Lights	0	0	0	0 :	0	0	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	0	0	0	0	0	0	Sub Total ==>	0	0	0.00
Ceiling Load	41	-41	0	0 :	37	2	Ceiling Load	-31	0	0.00
Ventilation Load	0	0	0	0:	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	ŭ		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	ŭ	10	-0.68
Exhaust Heat	O	-13	-13	0 :	o o		OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0 :			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-473	33.15
Duct Heat Pkup		Ö	Ö	0:			System Plenum Heat		124	-8.72
Underfir Sup Ht Pku	a	='	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 :		:	Supply Air Leakage		0	0.00
Grand Total ==>	2,293	721	3,014	100.00	2,298	100.00	Grand Total ==>	-884	-1,426	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	100.0						
Ra Plenum	78.1	67.6						
Return	78.1	67.6						
Ret/OA	78.1	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS									
Cooling Heating									
Diffuser	88	26							
Terminal Main Fan	88 88	26 26							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	4	4							
MinStop/Rh	26	26							
Return	92	30							
Exhaust	4	4							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS								
Cooling Heating								
% OA	0.0	0.0						
cfm/ft²	2.15	0.64						
cfm/ton	350.50							
ft ² /ton	163.24							
Btu/hr·ft²	73.51	-34.78						
No. People	0.0	0.0/1000 ft ²						

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.3	3.0	3.0	87	78.1	63.6	65.0	51.6	51.5	56.7
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.3	3.0								

	AREAS			
(Gross Total	Glass ft ²		
		IL	(%)	
Floor	41			ı
Part	0			
Int Door	0			ı
ExFlr	9			ı
Roof	134	0	0	ı
Wall	108	16	15	
Ext Door	0	0	0	:

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-1.4	26	51.6	100.0				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.5	26	51.6	70.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent <i>Total</i>	0.0 -1.4	0	0.0	0.0				

By RLF

125 TEAM STATION

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	r: 7 / 16 R: 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				:			Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	542	542	10	0	0		0	-200	13.17
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,099		1,099	20	258	8	Infiltration	-636	-636	41.85
Sub Total ==>	1,099	542	1,641	30	258	8	Sub Total ==>	-636	-836	55.02
Internal Loads							Internal Loads			
Lights	433	108	541	10	433	14	Lights	0	0	0.00
People	2,700	0	2,700	49	1,500	48	People	0	0	0.00
Misc	676	0	676	12	676	22		0	0	0.00
Sub Total ==>	3,808	108	3,916	71	2,608	84	Sub Total ==>	0	0	0.00
Ceiling Load	237	-237	0	0	249	8	Ceiling Load	-148	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	· ·	0	0	0		Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	ŭ	ŭ	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		47	-3.09
Exhaust Heat	· ·	-75	-75	-1	· ·	ŭ	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-641	42.17
Duct Heat Pkup		Ö	Ö	0:			System Plenum Heat		-90	5.90
Underfir Sup Ht Pku	p		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	5,144	338	5,482	100.00	3,115	100.00	Grand Total ==>	-784	-1,519	100.00

TEMPERATURES								
	Cooling Heating							
SADB	51.6	89.7						
Ra Plenum	78.8	67.6						
Return	78.8	67.6						
Ret/OA	78.8	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS									
Cooling Heating									
Diffuser	119	36							
Terminal Main Fan	119 119	36 36							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	18	18							
MinStop/Rh	36	36							
Return	137	54							
Exhaust	18	18							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	0.60	0.18					
cfm/ton	261.18						
ft ² /ton	433.38						
Btu/hr·ft²	27.69	-7.67					
No. People	6.0	30.3/1000 ft ²					

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm		rter DB °F	/WB/HR gr/lb	Lea °F	ve DB °F	/WB/HR gr/lb
Main Clg	0.5	5.5	3.4	119	78.8	63.9	65.0	51.6	47.6	42.4
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.5	5.5								

	AREAS			
G	ross Total	Glass		
		ft²	(%)	
Floor	198			r
Part	0			1
Int Door	0			F
ExFlr	0			F
Roof	215	0	0	H
Wall	0	0	0	
Ext Door	0	0	0	7

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-1.5	36	51.6	89.7				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-0.7	36	51.6	70.0				
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0				
Total	-1.5							

By RLF

126 B TLT

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HR	7 / 16 : 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	313	313	17	0	0	Roof Cond	0	-127	12.68
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 :	0	0		0	0	0.00
Partition/Door	0		0	0	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	1,099		1,099	59 ;	258	27	!	-636	-636	63.21
Sub Total ==>	1,099	313	1,412	75	258	27	Sub Total ==>	-636	-763	75.89
Internal Loads							Internal Loads			
Lights	433	108	541	29	433	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	433	108	541	29	433	46	Sub Total ==>	0	0	0.00
Ceiling Load	237	-237	0	0	249	26	Ceiling Load	-148	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	ŭ	· ·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		47	-4.67
Exhaust Heat	Ü	-75	-75	-4	ŭ	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-193	19.21
Duct Heat Pkup		0	0	0 :			System Plenum Heat		-96	9.58
Underfir Sup Ht Pkup	0		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,768	110	1,878	100.00	939	100.00	Grand Total ==>	-784	-1,006	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	135.2					
Ra Plenum	78.8	67.6					
Return	78.8	67.6					
Ret/OA	78.8	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS									
Cooling Heating									
Diffuser	36	11							
Terminal Main Fan	36 36	11 11							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	18	18							
MinStop/Rh	11	11							
Return	54	29							
Exhaust	18	18							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENG	ENGINEERING CKS								
Cooling Heating									
% OA	0.0	0.0							
cfm/ft²	0.18	0.05							
cfm/ton	229.92								
ft²/ton	1,265.22								
Btu/hr·ft²	9.48	-5.08							
No. People	0.0	0.0/1000 ft ²							

	COOLING COIL SELECTION											
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	En °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb		
Main Clg	0.2	1.9	1.0	35	78.8	63.9	65.0	51.6	44.6	32.4		
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.2	1.9										

	AREAS			
	Gross Total	Glass ft ²		
		IL-	(%)	
Floor	198			N
Part	0			4
Int Door	0			F
ExFlr	0			F
Roof	137	0	0	H
Wall	0	0	0	C
Ext Door	0	0	0	7

HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg					
	MBh	cfm	°F	°F					
Main Htg	-1.0	11	51.6	135.2					
Aux Htg	0.0	0	0.0	0.0					
Preheat	0.0	0	0.0	0.0					
Reheat	-0.2	11	51.6	70.0					
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0					
Total	-1.0								

By RLF

127 CLEAN STORAGE

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hr OADB/WB/HR	7 / 16 1: 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total		Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	, ,	0	0	0.00
Roof Cond	0	280	280	28	0	0		0	-93	19.92
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0 :		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	,	0.00	0.00	0.00
Infiltration	511		511	51 :	120	27		-295	-295	63.21
Sub Total ==>	511	280	790	79	120	27	Sub Total ==>	-295	-388	83.12
Internal Loads							Internal Loads			
Lights	201	50	251	25	201	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	0	0	0	0	0	0		0	0	0.00
Sub Total ==>	201	50	251	25	201	46	Sub Total ==>	0	0	0.00
Ceiling Load	110	-110	0	0 :	116	26	Ceiling Load	-69	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	ŭ		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	ŭ	22	-4.67
Exhaust Heat	U	-35	-35	-3	O .	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		00	0	0:		,	RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-90	19.21
Duct Heat Pkup		0	0	0			System Plenum Heat		-11	2.34
Underfir Sup Ht Pku	n	-	0	0			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0 }		:	Supply Air Leakage		0	0.00
Grand Total ==>	822	185	1,007	100.00	436	100.00	Grand Total ==>	-364	-467	100.00

TEMP	TEMPERATURES							
	Cooling	Heating						
SADB	51.6	135.2						
Ra Plenum	78.8	67.6						
Return	78.8	67.6						
Ret/OA	78.8	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS								
	Cooling	Heating						
Diffuser	17	5						
Terminal	17	5						
Main Fan	17	5						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	8	8						
MinStop/Rh	5	5						
Return	25	13						
Exhaust	8	8						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS								
Cooling Heating								
% OA	0.0	0.0						
cfm/ft²	0.18	0.05						
cfm/ton	199.33							
ft²/ton	1,096.84							
Btu/hr·ft²	10.94	-5.08						
No. People	0.0	0.0/1000 ft ²						

	COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm		rter DB °F	/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb	
Main Clg	0.1	1.0	0.6	16	78.8	63.9	65.0	51.6	40.9	20.8	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	
Total	0.1	1.0									

	AREAS			
C	Gross Total	Glass		
		ft²	(%)	
Floor	92			ı
Part	0			
Int Door	0			ŀ
ExFlr	0			ı
Roof	100	0	0	ı
Wall	0	0	0	
Ext Door	0	0	0	

Н	HEATING COIL SELECTION									
	Capacity	Coil Airflow	Ent	Lvg						
	MBh	cfm	°F	°F						
Main Htg	-0.5	5	51.6	135.2						
Aux Htg	0.0	0	0.0	0.0						
Preheat	0.0	0	0.0	0.0						
Reheat	-0.1	5	51.6	70.0						
Humidif	0.0	0	0.0	0.0						
Opt Vent <i>Total</i>	0.0 -0.5	0	0.0	0.0						

By RLF

128 COMM

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	1	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	363	363	3	0	0		0	-129	3.93
Glass Solar	0	0	0	0 ;	0	0	,	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 ;	0	0	-	0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	,	0.00	0.00	0.00
Infiltration	479		479	4 :	117	1	1	-289	-289	8.79
Sub Total ==>	479	363	842	6 ;	117	1	Sub Total ==>	-289	-418	12.72
Internal Loads							Internal Loads			
Lights	197	49	246	2	197	2	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	12,000	0	12,000	92	12,000	97	Misc	0	0	0.00
Sub Total ==>	12,197	49	12,246	94	12,197	98	Sub Total ==>	0	0	0.00
Ceiling Load	113	-113	0	0 :	113	1	Ceiling Load	-67	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	_		0	0 :	-	_	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	ŭ	21	-0.65
Exhaust Heat	Ū	-36	-36	0:	O	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-2,556	77.72
Duct Heat Pkup		0	0	0			System Plenum Heat		-336	10.21
Underfir Sup Ht Pku	p		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	•	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	12,789	263	13,052	100.00	12,427	100.00	Grand Total ==>	-356	-3,289	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	72.2					
Ra Plenum	79.0	67.6					
Return	79.0	67.6					
Ret/OA	79.0	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	476	143						
Terminal Main Fan	476 476	143 143						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	8	8						
MinStop/Rh	143	143						
Return	484	151						
Exhaust	8	8						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	5.29	1.59					
cfm/ton	437.65						
ft²/ton	82.75						
Btu/hr·ft²	145.02	-36.54					
No. People	0.0	0.0/1000 ft ²					

COOLING COIL SELECTION													
	Total (Total Capacity ton MBh				Coil Airflow cfm		Enter DB/WB/HR °F °F gr/lb			Leave DB/WB/HR °F °F gr/lb		
Main Clg	1.1	13.1	12.7	476		63.9	65.0		51.5	56.7			
Aux Clg	0.0	0.0	0.0	0	0.0		0.0	0.0	0.0	0.0			
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0			
Total	1.1	13.1											

	AREAS			
	Gross Total	Glass ft ²	s (%)	
Floor	90		(/-/	Ma
Part	0			Αu
Int Door	0			Pr
ExFlr	0			Re
Roof	139	0	0	Hu
Wall	0	0	0	Or
Ext Door	r 0	0	0	To

HEATING COIL SELECTION								
	Capacity	Coil Airflow	Ent	Lvg				
	MBh	cfm	°F	°F				
Main Htg	-3.3	143	51.6	72.2				
Aux Htg	0.0	0	0.0	0.0				
Preheat	0.0	0	0.0	0.0				
Reheat	-2.9	143	51.6	70.0				
Humidif	0.0	0	0.0	0.0				
Opt Vent <i>Total</i>	0.0 -3.3	0	0.0	0.0				

By RLF

129 CORR CENTRAL

(COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	l at Time: itside Air:	Mo/Hi OADB/WB/HR	7 / 16 : 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	1 1 1 1	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads			_		_		Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	309	309	24	0	0	Roof Cond	0	-126	14.48
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0	Glass/Door Cond	0	0	0.00
Wall Cond	0	0	0	0 ;	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0.00	0	Floor	-235	-235	27.06
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	691		691	53	162	27	!	-400	-400	46.10
Sub Total ==>	691	309	1,001	77	162	27	Sub Total ==>	-635	-760	87.65
Internal Loads							Internal Loads			
Lights	272	68	340	26	272	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0	0	0	Misc	0	0	0.00
Sub Total ==>	272	68	340	26	272	46	Sub Total ==>	0	0	0.00
Ceiling Load	149	-149	0	0	156	26	Ceiling Load	-93	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing			0	0 :			Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		30	-3.41
Exhaust Heat	ŭ	-47	-47	-4	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-122	14.01
Duct Heat Pkup		0	0	0			System Plenum Heat		-15	1.75
Underfir Sup Ht Pkup)		0	0 :			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage		0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,112	181	1,294	100.00	591	100.00	Grand Total ==>	-728	-867	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	166.2					
Ra Plenum	78.8	67.6					
Return	78.8	67.6					
Ret/OA	78.8	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	23	7						
Terminal Main Fan	23 23	7 7						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	11	11						
MinStop/Rh	7	7						
Return	34	18						
Exhaust	11	11						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	0.18	0.05					
cfm/ton	209.98						
ft²/ton	1,155.44						
Btu/hr·ft²	10.39	-6.96					
No. People	0.0	0.0/1000 ft ²					

COOLING COIL SELECTION										
			·				/WB/HR	Leave DB/WB/HR		
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.1	1.3	0.8	22	78.8	63.9	65.0	51.6	42.3	25.3
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.3								
Total	0.1	1.3								

	AREAS Gross Total	Glass	(%)	
Floor Part	125 0			M: A:
Int Door ExFir Roof	. 0 15 135	0	0	Pr Re
Wall	0	0	0	O
Ext Doo	r 0	0	0	To

HEATING COIL SELECTION						
	Capacity	Coil Airflow	Ent	Lvg		
	MBh	cfm	°F	°F		
Main Htg	-0.9	7	51.6	166.2		
Aux Htg	0.0	0	0.0	0.0		
Preheat	0.0	0	0.0	0.0		
Reheat	-0.1	7	51.6	70.0		
Humidif	0.0	0	0.0	0.0		
Opt Vent	0.0		0.0	0.0		
Total	-0.9					

Project Name: HealthFirst Medico

21184.TRC

Dataset Name:

By RLF

129 CORR NORTH

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 7 / 15 R: 88 / 78 / 1	29	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	Skylite Solar	0	0	0.00
Skylite Cond	0	0	0	0 :	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	207	207	14	0	0	Roof Cond	0	-77	5.21
Glass Solar	0	0	0	0 ;	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	196	0	196	13 ;	196	21	Glass/Door Cond	-459	-459	30.93
Wall Cond	358	145	503	34 :	358	39		-271	-383	25.78
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0	0.00	0		-235	-235	15.82
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	408		408	27	100	11		-246	-246	16.57
Sub Total ==>	962	352	1,314	88	654	71	Sub Total ==>	-1,210	-1,399	94.30
Internal Loads							Internal Loads			
Lights	167	42	209	14	167	18	Lights	0	0	0.00
People	0	0	0	0	0	0	People	0	0	0.00
Misc	0	0	0	0:	0	0		0	0	0.00
Sub Total ==>	167	42	209	14	167	18	Sub Total ==>	0	0	0.00
Ceiling Load	96	-96	0	0	96	10	Ceiling Load	-57	0	0.00
Ventilation Load	0	0	0	0	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	Ŭ	0	0	0	-	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	Ü		0	0	Ü	Ū	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat		18	-1.22
Exhaust Heat	Ü	-30	-30	-2	· ·	·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-189	12.71
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		86	-5.79
Underfir Sup Ht Pkuj	D	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	1,225	267	1,492	100.00	917	100.00	Grand Total ==>	-1,267	-1,484	100.00

TEMPERATURES					
Cooling Heating					
SADB	51.6	177.9			
Ra Plenum	79.0	67.6			
Return	79.0	67.6			
Ret/OA	79.0	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS					
	Cooling	Heating			
Diffuser	35	11			
Terminal Main Fan	35 35	11 11			
Sec Fan	0	0			
Nom Vent	0	0			
AHU Vent	0	0			
Infil	7	7			
MinStop/Rh	11	11			
Return	42	17			
Exhaust	7	7			
Rm Exh	0	0			
Auxiliary	0	0			
Leakage Dwn	0	0			
Leakage Ups	0	0			

ENGINEERING CKS					
Cooling Heating					
% OA	0.0	0.0			
cfm/ft²	0.46	0.14			
cfm/ton	282.42				
ft²/ton	615.81				
Btu/hr·ft²	19.49	-19.37			
No. People	0.0	0.0/1000 ft ²			

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F		/WB/HR gr/lb
Main Clg	0.1	1.5	1.2	35	79.0	63.9	65.0	51.6	49.1	48.0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.5								

	AREAS			
	Gross Total	Glass ft²	; (%)	
Floor Part	77 0			Main Ht Aux Htg
Int Door	0 15			Preheat Reheat
Roof Wall	83 89	0 0	0 0	Humidit Opt Ver
Ext Doo	r 21	0	0	Total

HEATING COIL SELECTION						
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F		
Main Htg Aux Htg	-1.5 0.0	11 0	51.6 0.0	177.9 0.0		
Preheat Reheat Humidif Opt Vent	0.0 -0.2 0.0 0.0	0 11 0	0.0 51.6 0.0 0.0	0.0 70.0 0.0 0.0		
Total	-1.5	U	0.0	0.0		

By RLF

129 CORR SOUTH

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 9 / 14 R: 86 / 76 / 1	20	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	t contract the contract of the	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads				_ :	_		Envelope Loads	_		
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	, -	0	0	0.00
Roof Cond	0	479	479	18	0	0		0	-156	10.87
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	813	262	1,075	41	970	61		-218	-285	19.80
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		-235	-235	16.32
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	696		696	27	102	6	Infiltration	-496	-496	34.52
Sub Total ==>	1,509	741	2,250	86	1,072	68	Sub Total ==>	-949	-1,172	81.51
Internal Loads							Internal Loads			
Lights	338	84	422	16	338	21	Lights	0	0	0.00
People	0	0	0	0 :	0	0	People	0	0	0.00
Misc	0	0	0	0 :	0	0	Misc	0	0	0.00
Sub Total ==>	338	84	422	16	338	21	Sub Total ==>	0	0	0.00
Ceiling Load	187	-187	0	0 :	174	11	Ceiling Load	-116	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0 :	· ·	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	· ·	37	-2.55
Exhaust Heat	O	-59	-59	-2	· ·	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-326	22.64
Duct Heat Pkup		Õ	ő	0			System Plenum Heat		23	-1.60
Underfir Sup Ht Pku	D	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	I:	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,034	580	2,613	100.00	1,583	100.00	Grand Total ==>	-1,065	-1,438	100.00

TEMPERATURES					
Cooling Heating					
SADB	51.6	122.5			
Ra Plenum	78.8	67.6			
Return	78.8	67.6			
Ret/OA	78.8	67.6			
Fn MtrTD	0.0	0.0			
Fn BldTD	0.0	0.0			
Fn Frict	0.0	0.0			

AIRFLOWS						
Cooling Heating						
Diffuser	61	18				
Terminal Main Fan	61 61	18 18				
Sec Fan	0	0				
Nom Vent	0	0				
AHU Vent	0	0				
Infil	14	14				
MinStop/Rh	18	18				
Return	75	32				
Exhaust	14	14				
Rm Exh	0	0				
Auxiliary	0	0				
Leakage Dwn	0	0				
Leakage Ups	0	0				

ENGINEERING CKS					
Cooling Heating					
% OA	0.0	0.0			
cfm/ft²	0.39	0.12			
cfm/ton	278.52				
ft²/ton	710.13				
Btu/hr·ft²	16.90	-9.30			
No. People	0.0	0.0/1000 ft ²			

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm		rter DB °F	/WB/HR gr/lb	Lea °F	ve DB °F	/WB/HR gr/lb
Main Clg	0.2	2.6	2.1	57	78.8	63.9	65.0	51.6	47.9	43.6
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.6								

(AREAS Gross Total	Glass ft²	s (%)	
Floor Part	155 0			l
Int Door	0			ĺ
ExFlr	15			
Roof	168	0	0	H
Wall	66	0	0	(
Ext Door	0	0	0	Н

Н	EATING COI	L SELECTI	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-1.4	18	51.6	122.5
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-0.4	18	51.6	70.0
Humidif	0.0	0	0.0	0.0
Opt Vent Total	0.0 0.0 -1.4	0	0.0	0.0

By RLF

130 CORR

	SSSEM C	OIL PEAK			CLG SPACE	PEAN		HEATING CO	VIL PEAN	
	ed at Time: outside Air:	Mo/Hr OADB/WB/HR	: 7 / 16 : 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 3	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	!	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	Skylite Cond	0	0	0.00
Roof Cond	0	246	246	24	0	0		0	-100	19.80
Glass Solar	0	0	0	0 :	0	0	Glass Solar	0	0	0.00
Glass/Door Cond	0	0	0	0 :	0	0		0	0	0.00
Wall Cond	0	0	0	0 ;	0	0	; Wall Cond	0	0	0.00
Partition/Door	0		0	0 :	0	0	Partition/Door	0	0	0.00
Floor	0		0	0 :	0.00	0	Floor	0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00
Infiltration	549		549	53	129	27	Infiltration	-318	-318	63.21
Sub Total ==>	549	246	796	77	129	27	Sub Total ==>	-318	-417	83.01
Internal Loads							Internal Loads			
Lights	216	54	270	26	216	46	Lights	0	0	0.00
People	0	0	0	0:	0	0	People	0	0	0.00
Misc	0	0	0	0:	0	0	Misc	0	0	0.00
Sub Total ==>	216	54	270	26	216	46	Sub Total ==>	0	0	0.00
Ceiling Load	119	-119	0	0	124	26	Ceiling Load	-74	0	0.00
Ventilation Load	0	0	0	0:	0		Ventilation Load	0	0	0.00
Adj Air Trans Heat	0	v	0	0	0		Adj Air Trans Heat	0	0	0.00
Dehumid. Ov Sizing	•		0		U	U	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0 :	0	0	Exhaust Heat	U	23	-4.67
Exhaust Heat	U	-38	-38	-4 ·	U	U	OA Preheat Diff.		0	0.00
Sup. Fan Heat		-30	-36	0:			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0:			Additional Reheat		-97	19.21
Duct Heat Pkup		0	0	0:			System Plenum Heat		-97 -12	2.45
Underfir Sup Ht Pku	ın	U	0	0			Underfir Sup Ht Pkup		0	0.00
•	•	0	0	0					0	0.00
Supply Air Leakage		U	U	0			Supply Air Leakage		U	0.00
Grand Total ==>	884	144	1,028	100.00	470	100.00	Grand Total ==>	-392	-503	100.00

TEMPERATURES								
Cooling Heating								
SADB	51.6	135.2						
Ra Plenum	78.8	67.6						
Return	78.8	67.6						
Ret/OA	78.8	67.6						
Fn MtrTD	0.0	0.0						
Fn BldTD	0.0	0.0						
Fn Frict	0.0	0.0						

AIRFLOWS									
Cooling Heating									
Diffuser	18	5							
Terminal Main Fan	18 18	5 5							
Sec Fan	0	0							
Nom Vent	0	0							
AHU Vent	0	0							
Infil	9	9							
MinStop/Rh	5	5							
Return	27	14							
Exhaust	9	9							
Rm Exh	0	0							
Auxiliary	0	0							
Leakage Dwn	0	0							
Leakage Ups	0	0							

ENGINEERING CKS							
Cooling Heating							
% OA	0.0	0.0					
cfm/ft²	0.18	0.05					
cfm/ton	209.93						
ft²/ton	1,155.17						
Btu/hr·ft²	10.39	-5.08					
No. People	0.0	0.0/1000 ft ²					

COOLING COIL SELECTION										
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg	0.1	1.0	0.6	18	78.8	63.9	65.0	51.6	42.3	25.2
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.0								

	AREAS][
G	ross Total	Glass ft²	s (%)	
Floor Part	99 0			M
Int Door	0			F
ExFlr	0			F
Roof	107	0	0	+
Wall	0	0	0	
Ext Door	0	0	0	117

HE	EATING COI	L SELECTI	ON	
	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F
Main Htg Aux Htg	-0.5 0.0	5 0	51.6 0.0	135.2 0.0
Preheat Reheat Humidif Opt Vent	0.0 -0.1 0.0 0.0	0 5 0	0.0 51.6 0.0 0.0	0.0 70.0 0.0 0.0
Total	-0.5	Ü	0.0	0.0

By RLF

131 CORR

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
	d at Time: utside Air:	Mo/Hi OADB/WB/HF	r: 7 / 16 R: 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	. ,	0	0	0.00
Roof Cond	0	556	556	24	0	0		0	-226	19.88
Glass Solar	0	0	0	0 ;	0	0	-	0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		0	0	0.00
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	,	0.00	0.00	0.00
Infiltration	1,243		1,243	53	292	27		-719	-719	63.21
Sub Total ==>	1,243	556	1,799	77	292	27	Sub Total ==>	-719	-945	83.08
Internal Loads							Internal Loads			
Lights	489	122	612	26	489	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	0	0	0	0	0	0		0	0	0.00
Sub Total ==>	489	122	612	26	489	46	Sub Total ==>	0	0	0.00
Ceiling Load	268	-268	0	0 :	281	26	Ceiling Load	-168	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	ŭ	·	Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	ŭ	53	-4.67
Exhaust Heat	Ū	-85	-85	-4:	· ·	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat		00	0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-219	19.21
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		-27	2.38
Underfir Sup Ht Pku	D	-	0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	I:	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,001	325	2,326	100.00	1,063	100.00	Grand Total ==>	-887	-1,138	100.00

TEMPERATURES									
	Cooling Heating								
SADB	51.6	135.2							
Ra Plenum	78.8	67.6							
Return	78.8	67.6							
Ret/OA	78.8	67.6							
Fn MtrTD	0.0	0.0							
Fn BldTD	0.0	0.0							
Fn Frict	0.0	0.0							

AIRFLOWS								
Cooling Heating								
Diffuser	41	12						
Terminal Main Fan	41 41	12 12						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	20	20						
MinStop/Rh	12	12						
Return	61	32						
Exhaust	20	20						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.18	0.05				
cfm/ton	210.02					
ft²/ton	1,155.67					
Btu/hr·ft²	10.38	-5.08				
No. People	0.0	0.0/1000 ft ²				

COOLING COIL SELECTION										
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb
Main Clg Aux Clg	0.2 0.0	2.3 0.0	1.4 0.0	40 0	78.8 0.0	63.9 0.0	65.0 0.0	51.6 0.0	42.3 0.0	25.3 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.2	2.3								

	ARE	AS		
	Gross Total	Glas		
		ft²	(%)	
Floor	224			Mair
Part	0			Aux
Int Doo	r 0			Preh
ExFlr	0			Reh
Roof	243	0	0	Hum
Wall	0	0	0	Opt
Ext Doc	or 0	0	0	Tota

HEATING COIL SELECTION							
	Capacity	Coil Airflow	Ent	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-1.1	12	51.6	135.2			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Reheat	-0.3	12	51.6	70.0			
Humidif	0.0	0	0.0	0.0			
Opt Vent Total	0.0 0.0 -1.1	0	0.0	0.0			

By RLF

132 CORR NORTH

	COOLING C	OIL PEAK			CLG SPACE	PEAK		HEATING CO	IL PEAK	
1	d at Time: utside Air:	Mo/Hi OADB/WB/HR	r: 7 / 16 R: 88 / 78 / 1	33	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	ating Design	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	· · · · · · · · · · · · · · · · · · ·	Space Peak Space Sens	Coil Peak Tot Sens	I
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)		Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0		0	0	0.00
Roof Cond	0	331	331	27	0	0		0	-114	17.24
Glass Solar	0	0	0	0 ;	0	0		0	0	0.00
Glass/Door Cond	0	0	0	0 ;	0	0		0	0	0.00
Wall Cond	0	0	0	0 :	0	0 :		0	0	0.00
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0 :	0.00	0		-88	-88	13.26
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	, ,	0.00	0.00	0.00
Infiltration	629		629	51 :	148	27		-364	-364	54.83
Sub Total ==>	629	331	960	78	148	27	Sub Total ==>	-452	-566	85.33
Internal Loads							Internal Loads			
Lights	248	62	310	25	248	46	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	0	0	0	0	0	0		0	0	0.00
Sub Total ==>	248	62	310	25	248	46	Sub Total ==>	0	0	0.00
Ceiling Load	136	-136	0	0 :	142	26	Ceiling Load	-85	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	· ·		0	0	· ·		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	·	27	-4.05
Exhaust Heat	O	-43	-43	-4:	· ·	0	OA Preheat Diff.		0	0.00
Sup. Fan Heat		.0	0	0		;	RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-111	16.66
Duct Heat Pkup		ő	Ö	0			System Plenum Heat		-14	2.06
Underfir Sup Ht Pku	n		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0		:	Supply Air Leakage		0	0.00
Grand Total ==>	1,012	214	1,227	100.00	538	100.00	Grand Total ==>	-537	-664	100.00

TEMPERATURES							
Cooling Heating							
SADB	51.6	147.9					
Ra Plenum	78.8	67.6					
Return	78.8	67.6					
Ret/OA	78.8	67.6					
Fn MtrTD	0.0	0.0					
Fn BldTD	0.0	0.0					
Fn Frict	0.0	0.0					

AIRFLOWS								
Cooling Heating								
Diffuser	21	6						
Terminal	21	6						
Main Fan	21	6						
Sec Fan	0	0						
Nom Vent	0	0						
AHU Vent	0	0						
Infil	10	10						
MinStop/Rh	6	6						
Return	31	16						
Exhaust	10	10						
Rm Exh	0	0						
Auxiliary	0	0						
Leakage Dwn	0	0						
Leakage Ups	0	0						

ENGINEERING CKS						
Cooling Heating						
% OA	0.0	0.0				
cfm/ft²	0.18	0.05				
cfm/ton	201.49					
ft ² /ton	1,108.74					
Btu/hr·ft²	10.82	-5.85				
No. People	0.0	0.0/1000 ft ²				

			COOLIN	G COIL SELE	CTIO	N				
	Total (Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F		/WB/HF gr/lb
Main Clg Aux Clg	0.1 0.0	1.2 0.0	0.7 0.0	20 0	78.8 0.0	63.9 0.0	65.0 0.0	51.6 0.0	41.2 0.0	21.8 0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.2								

	AREAS			
G	Fross Total	Glas:	s (%)	
		11	(/0)	
Floor	113			N
Part	0			4
Int Door	0			F
ExFlr	6			F
Roof	123	0	0	H
Wall	0	0	0	
Ext Door	0	0	0	7

HEATING COIL SELECTION							
	Capacity	Coil Airflow	Ent	Lvg			
	MBh	cfm	°F	°F			
Main Htg	-0.7	6	51.6	147.9			
Aux Htg	0.0	0	0.0	0.0			
Preheat	0.0	0	0.0	0.0			
Reheat	-0.1	6	51.6	70.0			
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0			
Total	-0.7						

Room Checksums

By RLF

132 CORR SOUTH

	COOLING COIL PEAK				CLG SPACE	PEAK		HEATING CO	OIL PEAK	
	d at Time: utside Air:	Mo/H OADB/WB/HF	r: 9 / 15 R: 86 / 77 / 1	24	Mo/Hr: OADB:			Mo/Hr: He OADB: 38	eating Design 8	
	Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible	Percent Of Total	t control of the cont	Space Peak Space Sens	Coil Peak Tot Sens	
	Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	i i	Btu/h	Btu/h	(%)
Envelope Loads							Envelope Loads			
Skylite Solar	0	0	0	0 :	0	0	,	0	0	0.00
Skylite Cond	0	0	0	0	0	0	, -	0	0	0.00
Roof Cond	0	472	472	15	0	0		0	-167	9.86
Glass Solar	598	0	598	19	952	44		0	0	0.00
Glass/Door Cond	104	0	104	3 ;	2	0		-295	-295	17.46
Wall Cond	512	247	759	24 ;	660	31		-145	-212	12.57
Partition/Door	0		0	0 :	0	0		0	0	0.00
Floor	0		0	0	0.00	0		-88	-88	5.21
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00
Infiltration	796		796	26	7	0		-531	-531	31.47
Sub Total ==>	2,009	719	2,728	87	1,621	76	Sub Total ==>	-1,059	-1,293	76.56
Internal Loads				:			Internal Loads			
Lights	362	90	452	14	362	17	Lights	0	0	0.00
People	0	0	0	0 :	0	0		0	0	0.00
Misc	0	0	0	0:	0	0		0	0	0.00
Sub Total ==>	362	90	452	14	362	17	Sub Total ==>	0	0	0.00
Ceiling Load	196	-196	0	0 :	160	7	Ceiling Load	-124	0	0.00
Ventilation Load	0	0	0	0	0	0	Ventilation Load	0	0	0.00
Adj Air Trans Heat	0		0	0	0	0	Adj Air Trans Heat	0	0	0
Dehumid. Ov Sizing	-		0	0	-		Ov/Undr Sizing	0	0	0.00
Ov/Undr Sizing	0		0	0	0	0	Exhaust Heat	•	39	-2.33
Exhaust Heat	· ·	-62	-62	-2	· ·	· ·	OA Preheat Diff.		0	0.00
Sup. Fan Heat			0	0			RA Preheat Diff.		0	0.00
Ret. Fan Heat		0	0	0			Additional Reheat		-441	26.09
Duct Heat Pkup		Ö	Ö	0			System Plenum Heat		6	-0.33
Underfir Sup Ht Pku	a		0	0:			Underfir Sup Ht Pkup		0	0.00
Supply Air Leakage	r	0	0	0			Supply Air Leakage		0	0.00
Grand Total ==>	2,567	551	3,118	100.00	2,143	100.00	Grand Total ==>	-1,184	-1,689	100.00

TEMP	TEMPERATURES												
	Cooling	Heating											
SADB	51.6	113.1											
Ra Plenum	78.7	67.6											
Return	78.7	67.6											
Ret/OA	78.7	67.6											
Fn MtrTD	0.0	0.0											
Fn BldTD	0.0	0.0											
Fn Frict	0.0	0.0											

AIRF	LOWS													
	Cooling Heating													
Diffuser	82	25												
Terminal Main Fan	82 82	25 25												
Sec Fan	0	0												
Nom Vent	0	0												
AHU Vent	0	0												
Infil	15	15												
MinStop/Rh	25	25												
Return	97	40												
Exhaust	15	15												
Rm Exh	0	0												
Auxiliary	0	0												
Leakage Dwn	0	0												
Leakage Ups	0	0												

ENG	ENGINEERING CKS												
	Cooling	Heating											
% OA	0.0	0.0											
cfm/ft²	0.50	0.15											
cfm/ton	315.86												
ft ² /ton	637.11												
Btu/hr·ft²	18.84	-10.20											
No. People	0.0	0.0/1000 ft ²											

	COOLING COIL SELECTION											
	Total (ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	E r °F		/WB/HR gr/lb	Lea °F	ve DB	/WB/HR gr/lb		
Main Clg Aux Clg	0.3 0.0	3.1 0.0	2.5 0.0	75 0	78.7 0.0	63.9 0.0	65.0 0.0	51.6 0.0	49.4 0.0	48.8 0.0		
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		
Total	0.3	3.1										

	AREAS			
G	Fross Total	Glas		
		ft²	(%)	
Floor	166			r
Part	0			1
Int Door	0			F
ExFlr	6			F
Roof	179	0	0	H
Wall	66	16	25	
Ext Door	0	0	0	7

HE	ATING COI	L SELECTI	ON	
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-1.7	25	51.6	113.1
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Reheat	-0.5	25	51.6	70.0
Humidif Opt Vent	0.0 0.0	0	0.0	0.0 0.0
Total	-1.7			

Project Name: HealthFirst Medico
Dataset Name: 21184.TRC

ROOM BY ROOM

By RLF

Room Description: 118 S TLT

Zone Description: Zone - 1-1-1

System Description: AHU **AIRFLOW INFORMATION**

Neutral, Average Const.

0.60 air changes/hr

Heating

0.00 cfm

None

GENERAL INFORMATION

Floor Area: 44 ft² FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

Infil Schedule: Available (100%) Vav Airflow:

Vav Sched: Available (100%)

Cooling

Infil Value: 0.60 air changes/hr

Infil Type: Neutral, Average Const.

Vent Type: None

Vent Value: 0.00 cfm

Vent Schedule: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

								Glass			— Aaj — Temp/	Sen/	Rm/		Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft².°F	Type / Alpha Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl		Heat	Perm	
Roof - 1	29 ft²	0	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
Roof - 2	99 ft²	270	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
NORTH	104 ft ²	0	0 ASHRAE 90.1 MASS	0.1374	0.90										
WEST	83 ft²	270	0 ASHRAE 90.1 MASS	0.1374	0.90										
Floor - 1														16	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 119 CONF/CONSULT

Zone Description: Zone - 1-1-2

System Description: AHU

GENERAL INFORMATION

Floor Area: 102 ft² Flr-Flr Height: 12.0 ft
Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 4 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

 Cooling
 Heating

 Vent Type:
 None

 Vent Value:
 0.00 cfm

 0.00 cfm
 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

								Glass			— Aaj — Temp/	Sen/ Rm/		Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft².°F	Type / Alpha Energy Typ	Area e ft²	Shade Coef	U Value Btu/h·ft².°F		Internal Shading	Grnd Refl	Cool Heat Tmp Tmp	Perm L	Loss
Roof - 1	16 ft²	0	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None	·			
Roof - 2	94 ft ²	270	90 R-30 Roof	0.0314	0.90	0			Overhang - None	None				
WEST	108 ft²	270	0 ASHRAE 90.1 MASS	0.1374	0.90									
Opening - 1			Window		90.1-2013 W	/indow 16	0.29	0.57	Overhang -	None	0.00			
Floor - 1													9 0) 50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 120 PROVIDER OFF

Zone Description: Zone - 1-1-2 GENERAL INFORMATION

AIRFLOW INFORMATION

Floor Area:	113 ft ²	Flr-Flr Height: 12.0 ft	
Plenum Height	3 N ft	Height Above Flr:	

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None Room Type:Conditioned **PEOPLE**

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%) Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

					_			(Glass			Temp/	Sen/	Rm/	Ret/	Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl			Perm	
Roof - 1	122 ft²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None	·				
WEST	108 ft²	270	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window		9	0.1-2013 Window	16	0.29	0.57	Overhang -	None	0.00				
Floor - 1															9	0.50

Room Description: 111 TEAM STATION

System Description: AHU

System Description: AHU

GENERAL INFORMATION

FIr-FIr Height: 12.0 ft Floor Area: 150 ft2 Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Cla Tstat: None Htg Tstat: None

Misc Load 1

Thermostat Location:Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned Zone Description: Zone - 1-1-3

PEOPLE People Type: General Office Space

of People: 4 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

None

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling **Heating** Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%) Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

Adj Pct Pct Pct Rad Glass Rm/ Ret/ Frc/ Temp/ Sen/ U Value Const Type / Area Shade U Value External Area/ Type / Internal Grnd Cool Heat Perm Loss Btu/h·ft².°F Alpha Energy Type Btu/h·ft2.°F Description Amount Tilt Schedule ft2 Coef Shading Shading Refl Tmp Tmp Len Coef Roof - 1 67 R-30 Roof 0.0314 0.90 0 163 ft² 0 Overhang - None None

Project Name: HealthFirst Medico

1.00 W/sq ft

H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC Dataset Name:

Cooling Only (Design)

TRACE® 700 v6.3.4 calculated at 05:19 PM on 04/11/2022 Alternative - 1 Entered Values - Rooms Page 4 of 25

100 100

0 60.00

ROOM BY ROOM

By RLF

Room Description: 125 TEAM STATION

Zone Description: Zone - 1-1-3

System Description: AHU

	GENERALI	NECKINATION	

OFNEDAL INFORMATION Floor Area: 198 ft2 Flr-Flr Height: 12.0 ft Plenum Height: 3.0 ft Height Above FIr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Room Multiplier: 1 Humidistat Location:Room

CO2 Sensor Location: None Room Type:Conditioned **PEOPLE**

People Type: General Office Space

of People: 6 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

								Glass			Temp/	Sen/	Rm/	Ret/	Frc/
	Area/		Const Type /	U Value	Type /	Area	Shade	U Value	External	Internal	Grnd	Cool	Heat	Perm	Loss
Description	Amount	Dir	Tilt Schedule	Btu/h·ft².°F	Alpha Energy T	ype ft²	Coef	Btu/h·ft².°F	Shading	Shading	Refl	Tmp	Tmp	Len	Coef
Roof - 1	99 ft²	270	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
Roof - 2	116 ft ²	0	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)		None							100	100	0 60	0.00

Room Description: 126 B TLT

Zone Description: Zone - 1-1-3

System Description: AHU

Pct Pct Pct Rad

GENERAL INFORMATION Floor Area: 198 ft2 FIr-FIr Height: 12.0 ft

Height Above Flr: Plenum Height: 3.0 ft

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1 Room Multiplier: 1 Humidistat Location:Room

CO2 Sensor Location: None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Adi

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%) Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

Adj Pct Pct Pct Rad Glass Ret/ Temp/ Sen/ Rm/ Frc/ U Value Shade U Value Perm Loss Area/ Const Type / Type / Area External Internal Grnd Cool Heat Btu/h·ft².°F Alpha Energy Type ft² Btu/h·ft2.°F Shading Description Amount Dir Tilt Schedule Coef Shading Refl Tmp Tmp Len Coef Roof - 1 137 ft² 67 R-30 Roof 0.0314 0.90 Overhang - None None

Project Name: HealthFirst Medico

H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC Dataset Name:

ROOM BY ROOM

By RLF

Room Description: 129 CORR CENTRAL

GENERAL INFORMATION Floor Area: 125 ft2 Flr-Flr Height: 12.0 ft

Plenum Height: 3.0 ft Height Above FIr: Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Room Multiplier: 1 Humidistat Location:Room

CO2 Sensor Location: None Room Type:Conditioned Zone Description: Zone - 1-1-3

PEOPLE People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

System Description: AHU

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

									Adj Po	ct Pct	Pct	Rad
						Glass		1	emp/ Se	n/ Rm/	Ret/	Frc/
	Area/	Const Type /	U Value Typ	oe / Area	Shade	U Value E	External Inte	ernal	Grnd Co	ol Heat	Perm	Loss
Description	Amount I	Dir Tilt Schedule	Btu/h·ft²-°F Alpha End	ergy Type ft²	Coef	Btu/h·ft².°F	Shading Sha	iding	Refl Tn	np Tmp	Len	Coef
Roof - 1	129 ft²	0 67 R-30 Roof	0.0314 0.90	0		Overh	nang - None Noi	ne				
Roof - 2	6 ft ² 1	180 67 R-30 Roof	0.0314 0.90	0		Overh	nang - None Noi	ne				

Room Description: 130 CORR

GENERAL INFORMATION FIr-FIr Height: 12.0 ft

Floor Area: 99 ft2 Plenum Height: 3.0 ft Height Above FIr:

Slab Cnstr Type: 4* LW Concrete Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Floor - 1

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None

Room Type:Conditioned

Zone Description: Zone - 1-1-3

PEOPLE People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

System Description: AHU

15 0.50

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%) Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

			Glass			¬ Temp/	Sen/	Ret/	Frc/
Description	Area/ Const Type / Amount Dir Tilt Schedule	U Value Type / Btu/h·ft²-°F Alpha Energy Type	Area Shade U Valu ft² Coef Btu/h·ft²·		Internal Shading	Grnd Refl		Perm	
Roof - 1	92 ft ² 0 67 R-30 Roof	0.0314 0.90	0	Overhang - None	None				
Roof - 2	15 ft ² 180 67 R-30 Roof	0.0314 0.90	0	Overhang - None	None				

Project Name: HealthFirst Medico

H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC Dataset Name:

Adi

Pct Pct Pct Rad

ROOM BY ROOM

By RLF

Room Description: 131 CORR

Floor Area: 224 ft²

Design Htg DB / Drift Point:

Design Relative Humidity:

Thermostat Location: Room

Humidistat Location:Room

CO2 Sensor Location: None

Moisture Capacitance:

Slab Cnstr Type: 4* LW Concrete

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F

Room Type:Conditioned

Plenum Height: 3.0 ft

Is There Carpet?: YES

Clg Tstat: None

Htg Tstat: None

Zone Description: Zone - 1-1-3 System Description: AHU **PEOPLE AIRFLOW INFORMATION** FIr-FIr Height: 12.0 ft People Type: General Office Space Cooling Heating Height Above FIr: # of People: 0 People Vent Type: None None People Sensible: 250 Btu/h Vent Value: 0.00 cfm 0.00 cfm Room Mass: Time delay based on actual mass People Latent: 200 Btu/h Vent Schedule: Available (100%) People Schedule: Cooling Only (Design) Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%) Workstation: 0.0 workstation/person Vav Airflow: Vav Sched: Available (100%) LIGHTS Supply: To be calculated To be calculated Lighting Type: Recessed fluorescent, not vented, 80% load Aux Supply: To be calculated To be calculated to space Room Exhaust: Fixture Type: RECFL-NV Rm Exh Sched: Available (100%) Floor Multiplier: 1 % Load to RA: 20 % Room Multiplier: 1 Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft Ballast Factor: 1.0

					Adj	Pct Po	t Pct	Rad
			Glass		¬ Temp/	Sen/ Rr	n/ Ret/	Frc/
	Area/ Const Type /	U Value Type /	Area Shade U Value External	Internal	Grnd	Cool He	at Perm	ı Loss
Description	Amount Dir Tilt Schedule	Btu/h ft².°F Alpha Energy Type	ft² Coef Btu/h·ft²·°F Shading	Shading	Refl	Tmp Tn	p Len	Coef
Roof - 1	243 ft ² 0 67 R-30 Roof	0.0314 0.90	0 Overhang - None	None				

Room Description: 132 CORR NORTH

GENERAL INFORMATION

70.0 °F / 64.0 °F

Medium

Zone Description: Zone - 1-1-3

System Description: AHU

Pct Pct

Pct Rad

GENERAL INFORMATION Floor Area: 113 ft2 FIr-FIr Height: 12.0 ft Height Above FIr: Plenum Height: 3.0 ft Slab Cnstr Type: 4* LW Concrete Room Mass: Time delay based on actual mass Ceiling R-Value: 1.786 hr·ft²-°F/Btu Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

HealthFirst Medico

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Cla Tstat: None Htg Tstat: None

Project Name:

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None Room Type:Conditioned

PEOPLE People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Heating

0.00 cfm

None

Vent Schedule: Available (100%) Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%) Vav Airflow: Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated Room Exhaust:

Rm Exh Sched: Available (100%)

Cooling

Vent Type: None

Vent Value: 0.00 cfm

								Glass			_ Temp/	Sen/ Rm/	Ret/ Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft².°F	Type / Alpha Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl		Perm Loss
Roof - 1	25 ft²	0	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None			
Roof - 3	98 ft²	270	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None			
Floor - 1													6 0.50

ROOM BY ROOM

By RLF

Room Description: 121 EXAM ROOM 10

Zone Description: Zone - 1-1-4

System Description: AHU

GENERAL INFORMATION

Floor Area: 116 ft² Flr-Flr Height: 12.0 ft
Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

CoolingHeatingVent Type:NoneNoneVent Value:0.00 cfm0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

									Glass			Aaj Temp/	Sen/	Pct Rm/	Pct Ret/	Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl		Heat	Perm	
Roof - 1	126 ft²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
WEST	135 ft²	270	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)			None							100	100	0 6	00.06
Floor - 1															11	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 122 EXAM ROOM 9

Zone Description: Zone - 1-1-4

System Description: AHU

|--|

Floor Area: 116 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

									Glass			Adj — Temp/	Pct Sen/	Pct Rm/		Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alph	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft².°F	External Shading	Internal Shading	Grnd Refl		Heat	Perm	
Roof - 1	126 ft ²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None	·				
WEST	123 ft ²	270	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)			None							100	100	0 (60.00
Floor - 1															10	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 123 EXAM ROOM 8

Zone Description: Zone - 1-1-4

System Description: AHU

GENERAL INFORMATION

Floor Area: 116 ft² Flr-Flr Height: 12.0 ft
Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)
Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

CoolingHeatingVent Type:NoneNoneVent Value:0.00 cfm0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

								(Glass			— Temp/	Sen/			Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl	Cool Tmp	Heat	Perm	
Roof - 1	126 ft²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
WEST	122 ft²	270	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	16	0.29	0.57	Overhang -	None	0.00				
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)			None							100	100	0	60.00
Floor - 1															10	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 124 MECH

Zone Description: Zone - 1-1-4

System Description: AHU

GENERAL INFORMATION

Floor Area: 41 ft² FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Design Relative Humidity:

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.000 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

									Glass			Adj — Temp/	Pct Sen/	Pct Rm/		Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef		External Shading	Internal Shading	Grnd Refl		l Heat	Perm	
Roof - 1	17 ft²	180	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
Roof - 2	117 ft²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
SOUTH	108 ft²	180	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	16	0.29	0.57	Overhang -	None	0.00				
Floor - 1															q	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 100 LOBBY

Zone Description: Zone - 1-2-1

System Description: AHU **AIRFLOW INFORMATION** Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm Vent Schedule: Available (100%) Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%) Vav Sched: Available (100%) To be calculated Supply: To be calculated Aux Supply: To be calculated To be calculated Rm Exh Sched: Available (100%)

Adi

Pct

System Description: AHU

Pct

Neutral, Average Const.

0.60 air changes/hr

Pct Rad

GENERAL INFORMATION

Floor Area: 420 ft² FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above FIr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Design Relative Humidity:

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Room Multiplier: 1 Humidistat Location:Room

CO2 Sensor Location:None

Room Type:Conditioned

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

PEOPLE

to space Fixture Type: RECFL-NV

Workstation: 0.0 workstation/person

People Type: General Office Space

People Schedule: Cooling Only (Design)

of People: 12 People

People Sensible: 250 Btu/h

People Latent: 200 Btu/h

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

								(Glass			¬ Temp/	Sen/	Rm/	Ret/	Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl	Cool Tmp	Heat Tmp	Perm I	Loss Coef
Roof - 1	455 ft²	180	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
SOUTH	492 ft²	180	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Misc Load 1 Floor - 1	0.50 W/sq ft		Cooling Only (Design)			None							100	100	0 60 41 (

Room Description: 101 W TLT

GENERAL INFORMATION

Floor Area: 47 ft² FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above FIr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1 Humidistat Location: Room Room Multiplier: 1

CO2 Sensor Location:None Room Type:Conditioned Zone Description: Zone - 1-2-1 **PEOPLE**

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Infil Value: 0.60 air changes/hr

Infil Schedule: Available (100%) Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Vav Airflow:

Room Exhaust:

Rm Exh Sched: Available (100%)

Pct Adj Pct Pct Rad Glass Temp/ Sen/ Rm/ Ret/ Frc/ Const Type / U Value Type / Area Shade U Value External Internal Grnd Heat Perm Loss Area/ Cool Description Tilt Schedule Btu/h·ft².°F Alpha Energy Type Btu/h·ft2.°F Shading Refl Amount Dir Coef Shading Tmp Tmp Len Coef Roof - 1 180 0.0314 0.90 0 Overhang - None None 51 ft² 67 R-30 Roof

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 102 M TLT

Clg Tstat: None

Htg Tstat: None

Zone Description: Zone - 1-2-1 System Description: AHU **GENERAL INFORMATION PEOPLE AIRFLOW INFORMATION** Floor Area: 47 ft2 FIr-FIr Height: 12.0 ft People Type: General Office Space Cooling Heating Plenum Height: 3.0 ft Height Above FIr: # of People: 0 People Vent Type: None None People Sensible: 250 Btu/h Slab Cnstr Type: 4* LW Concrete Vent Value: 0.00 cfm 0.00 cfm Room Mass: Time delay based on actual mass People Latent: 200 Btu/h Vent Schedule: Available (100%) Ceiling R-Value: 1.786 hr·ft²-°F/Btu Infil Type: Neutral, Average Const. People Schedule: Cooling Only (Design) Neutral, Average Const. Is There Carpet?: YES Infil Value: 0.60 air changes/hr 0.60 air changes/hr Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Infil Schedule: Available (100%) Workstation: 0.0 workstation/person Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Vav Airflow: Design Relative Humidity: Vav Sched: Available (100%) LIGHTS Moisture Capacitance: Medium Supply: To be calculated To be calculated Lighting Type: Recessed fluorescent, not vented, 80% load Aux Supply: To be calculated To be calculated to space Room Exhaust: Fixture Type: RECFL-NV Rm Exh Sched: Available (100%) Thermostat Location: Room Floor Multiplier: 1 % Load to RA: 20 % Room Multiplier: 1 Lighting Schedule: Cooling Only (Design) Humidistat Location:Room Lighting Amount: 0.800 W/sq ft CO2 Sensor Location: None Ballast Factor: 1.0 Room Type:Conditioned

				Glass			Adj	PCI PCI	
	Area/	Const Type /	U Value Type /	Area Shade U Va	lue External	Internal	Temp/ Grnd	Sen/ Rm/ Cool Heat	
Description	Amount D	, ·	Btu/h·ft²·°F Alpha Energy Type	ft ² Coef Btu/h·f		Shading	Refl	Tmp Tmp	
Roof - 1	51 ft² 1	80 67 R-30 Roof	0.0314 0.90	0	Overhang - None	None			-

Room Description: 113 ELEC

Zone Description: Zone - 1-2-2

System Description: AHU

GENERAL INFORMATION Floor Area: 55 ft2 FIr-FIr Height: 12.0 ft Height Above FIr: Plenum Height: 3.0 ft Slab Cnstr Type: 4* LW Concrete Room Mass: Time delay based on actual mass Ceiling R-Value: 1.786 hr-ft2-°F/Btu Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Design Relative Humidity: 50 %

Moisture Capacitance: Medium Cla Tstat: None

Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned **PEOPLE**

People Type: General Office Space # of People: 0 People People Sensible: 250 Btu/h

People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

None

to space Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

Aux Supply: To be calculated Room Exhaust:

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%) Vav Airflow:

AIRFLOW INFORMATION

Heating

0.00 cfm

None

Vav Sched: Available (100%) Supply: To be calculated To be calculated To be calculated

Rm Exh Sched: Available (100%)

Cooling

Vent Type: None

Vent Value: 0.00 cfm

Vent Schedule: Available (100%)

Rad Adi Pct Pct Pct Glass Temp/ Rm/ Ret/ Frc/ Sen/ Area/ Const Type / U Value Type / Area Shade U Value External Internal Grnd Cool Heat Perm Loss Btu/h·ft².°F Alpha Energy Type Btu/h·ft2.°F Tmp Description Amount Dir Tilt Schedule ft² Coef Shading Shading Refl Tmp Len Coef Roof - 1 60 ft² 67 R-30 Roof 0.0314 0.90 0 Overhang - None None 0

NORTH 65 ft² 0 ASHRAE 90.1 MASS 0 1374 0.90 Cooling Only (Design) Misc Load 1 2.00 W/sq ft

Floor - 1

Project Name: HealthFirst Medico

Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC 100 100 0 60.00 5 0.50

TRACE® 700 v6.3.4 calculated at 05:19 PM on 04/11/2022 Alternative - 1 Entered Values - Rooms Page 13 of 25

ROOM BY ROOM

By RLF

Room Description: 114 EVS

Zone Description: Zone - 1-2-2

People Type: General Office Space

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

to space

of People: 0 People

People Sensible: 250 Btu/h

People Latent: 200 Btu/h

PEOPLE

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

System Description: AHU **AIRFLOW INFORMATION** Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm Vent Schedule: Available (100%) Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%) Vav Airflow: Vav Sched: Available (100%) Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated Rm Exh Sched: Available (100%)

GENERAL INFORMATION Floor Area: 57 ft² FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr: Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Humidistat Location:Room

CO2 Sensor Location: None Room Type:Conditioned

Floor Multiplier: 1 Room Multiplier: 1

Room Exhaust:

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

griding / unlount.	0.000
Ballast Factor:	1.0

									Glass			Adj _ Temp/		Pct Rm/	Pct Ret/	Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl	Cool		Perm	
Roof - 1	62 ft²	0	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
NORTH	79 ft²	0	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Floor - 1															7	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 115 SOIL

Zone Description: Zone - 1-2-2

System Description: AHU

	GEN	ERAL	INFOR	MAHON
--	-----	------	-------	-------

Floor Area: 56 ft² Flr-Flr Height: 12.0 ft
Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

55 ft²

0 0 ASHRAE 90.1 MASS

CO2 Sensor Location: None

Room Type:Conditioned

PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

0.90

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

0.1374

AIRFLOW INFORMATION

CoolingHeatingVent Type:NoneNoneNoneVent Value:0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

					Adj	Pct Pct F	Pct Rad
			Glass		Temp/	Sen/ Rm/ R	Ret/ Frc/
	Area/ Const Type /	U Value Type /	Area Shade U Value External	Internal	Grnd	Cool Heat Pe	erm Loss
Description	Amount Dir Tilt Schedule	Btu/h·ft²·°F Alpha Energy Type	ft² Coef Btu/h·ft²·°F Shading	Shading	Refl	Tmp Tmp L	en Coef
Roof - 1	61 ft ² 0 67 R-30 Roof	0.0314 0.90	0 Overhang - None	None	·		

NORTH Floor - 1

5 0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 116 MANAGER OFF

Zone Description: Zone - 1-2-2

System Description: AHU

GENERAL INFORMATION

Floor Area: 102 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned

Floor Multiplier: 1

PEOPLE

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

People Type: General Office Space

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

									Glass			Adj — Temp/	Pct Sen/	Pct Rm/	Pct Ret/	Rad Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl				Loss Coef
Roof - 1	111 ft²	0	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
NORTH	116 ft ²	0	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Floor - 1															10	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 109 PROVIDER OFF Zone Description: Zone - 1-2-3 System Description: AHU **GENERAL INFORMATION PEOPLE AIRFLOW INFORMATION** Floor Area: 117 ft2 FIr-FIr Height: 12.0 ft People Type: General Office Space Cooling Heating Plenum Height: 3.0 ft Height Above FIr: # of People: 2 People Vent Type: None None People Sensible: 250 Btu/h Slab Cnstr Type: 4* LW Concrete Vent Value: 0.00 cfm 0.00 cfm Room Mass: Time delay based on actual mass People Latent: 200 Btu/h Vent Schedule: Available (100%) Ceiling R-Value: 1.786 hr·ft²-°F/Btu Infil Type: Neutral, Average Const. People Schedule: Cooling Only (Design) Neutral, Average Const. Is There Carpet?: YES Infil Value: 0.60 air changes/hr 0.60 air changes/hr Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Infil Schedule: Available (100%) Workstation: 0.0 workstation/person Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Vav Airflow: Design Relative Humidity: Vav Sched: Available (100%) LIGHTS To be calculated Moisture Capacitance: Medium Supply: To be calculated Lighting Type: Recessed fluorescent, not vented, 80% load Clg Tstat: None Aux Supply: To be calculated To be calculated to space Htg Tstat: None Room Exhaust: Fixture Type: RECFL-NV Rm Exh Sched: Available (100%) Thermostat Location: Room Floor Multiplier: 1 % Load to RA: 20 % Room Multiplier: 1 Lighting Schedule: Cooling Only (Design) Humidistat Location:Room Lighting Amount: 0.800 W/sq ft CO2 Sensor Location:None Ballast Factor: 1.0 Room Type:Conditioned

									Glass			¬ Temp/	Sen/	Rm/	Ret/ Fr	.c/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl	Cool Tmp		Perm Lo	SS
Roof - 1	127 ft²	0	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
NORTH	154 ft²	0	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	33	0.29	0.57	Overhang -	None	0.00				
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)			None							100	100	0 60.0)0
Floor - 1															13 0.5	50

Room Description: 112 POC

Zone Description: Zone - 1-2-3 **GENERAL INFORMATION**

Floor Area: 20 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1 Humidistat Location: Room Room Multiplier: 1

CO2 Sensor Location:None Room Type:Conditioned **PEOPLE**

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

Pct

System Description: AHU

Pct Rad

Adj

AIRFLOW INFORMATION Heating None 0.00 cfm

Vent Value: 0.00 cfm Vent Schedule: Available (100%)

Vent Type: None

Cooling

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow: Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Close

Rm Exh Sched: Available (100%)

Pct Adj Pct Pct Rad Glass Temp/ Sen/ Rm/ Ret/ Frc/ Const Type / U Value Type / Area Shade U Value External Internal Grnd Heat Perm Loss Area/ Cool Description Tilt Schedule Btu/h·ft².°F Alpha Energy Type Btu/h·ft2.°F Shading Refl Amount Dir Coef Shading Tmp Tmp Len Coef Roof - 1 22 ft² 0.0314 0.90 0 Overhang - None None 0 67 R-30 Roof

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 129 CORR NORTH

Zone Description: Zone - 1-2-3

System Description: AHU

Neutral, Average Const.

0.60 air changes/hr

GENERAL INFORMATION

Floor Area: 77 ft² Flr-Flr Height: 12.0 ft

Plenum Height: 3.0 ft Height Above Flr: Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²·°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %
Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None Room Type:Conditioned PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)
Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION
Heating

 Vent Type:
 Cooling None
 Heating None

 Vent Value:
 0.00 cfm
 0.00 cfm

Vent Schedule: Available (100%)
Infil Type: Neutral, Average Const.
Infil Value: 0.60 air changes/hr

Infil Value: 0.60 air changes/hr Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

							Glass			Aaj		ct PC	
							Giass			_ Temp/	Sen/ F	.m/ Re	et/ Frc/
	Area/	Const Type /	U Value	Type /	Area	Shade	U Value	External	Internal	Grnd	Cool H	eat Per	m Loss
Description	Amount Dir	r Tilt Schedule	Btu/h·ft²·°F	Alpha Energy Type	ft²	Coef	Btu/h·ft²·°F	Shading	Shading	Refl	Tmp T	mp Le	n Coef
Roof - 1	83 ft² (0 67 R-30 Roof	0.0314	0.90	0			Overhang - None	None				
NORTH	110 ft² (0 0 ASHRAE 90.1 MASS	0.1374	0.90									
Opening - 1		Door		90.1-13 Min Swinging	g 21	0.00	0.70	Overhang - None	None	0.00			

Room Description: 105 EXAM ROOM 2

Zone Description: Zone - 1-2-4

System Description: AHU

15 0.50

Pct Rad

GENERAL INFORMATION

Floor Area: 117 ft² Flr-Flr Height: 12.0 ft
Plenum Height: 3.0 ft Height Above Flr:

Plenum Height: 3.0 ft Height Above Slab Constr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Floor - 1

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F
Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 %

Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location:Room Floor Multiplier: 1
Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location:None Room Type:Conditioned PEOPLE

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)
Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

 Cooling
 Heating

 Vent Type:
 None
 None

 Vent Value:
 0.00 cfm
 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Sched: Ava

Vav Sched: Available (100%) Supply: To be calculated

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

		<u></u>	Glass			_ Temp/		m/ Ret/	Frc/
	Area/ Const Type /	U Value Type /	Area Shade U Valu	e External	Internal	Grnd	Cool H		1 Loss
Description	Amount Dir Tilt Schedule	Btu/h·ft².°F Alpha Energy Type	ft² Coef Btu/h·ft²·	°F Shading	Shading	Refl	Tmp T	mp Len	Coef
Roof - 1	127 ft ² 180 67 R-30 Roof	0.0314 0.90	0	Overhang - None	None	'			

Misc Load 1 1.00 W/sq ft Cooling Only (Design) None 100 100 0 60.00

Project Name: HealthFirst Medico

Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC

Pct Pct

ROOM BY ROOM

By RLF

Room Description: 106 EXAM ROOM 3

Design Relative Humidity:

Zone Description: Zone - 1-2-4

System Description: AHU **GENERAL INFORMATION PEOPLE AIRFLOW INFORMATION** Floor Area: 117 ft2 People Type: General Office Space Cooling Flr-Flr Height: 12.0 ft Heating Plenum Height: 3.0 ft Height Above FIr: # of People: 2 People Vent Type: None None Slab Cnstr Type: 4* LW Concrete People Sensible: 250 Btu/h Vent Value: 0.00 cfm 0.00 cfm Room Mass: Time delay based on actual mass People Latent: 200 Btu/h Vent Schedule: Available (100%) Ceiling R-Value: 1.786 hr·ft²-°F/Btu Infil Type: Neutral, Average Const. People Schedule: Cooling Only (Design) Neutral, Average Const. Is There Carpet?: YES Infil Value: 0.60 air changes/hr 0.60 air changes/hr Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Infil Schedule: Available (100%) Workstation: 0.0 workstation/person Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Vav Airflow:

LIGHTS Moisture Capacitance: Medium Lighting Type: Recessed fluorescent, not vented, 80% load Clg Tstat: None to space Htg Tstat: None Fixture Type: RECFL-NV Thermostat Location: Room Floor Multiplier: 1 % Load to RA: 20 %

Room Multiplier: 1 Lighting Schedule: Cooling Only (Design) Humidistat Location:Room Lighting Amount: 0.800 W/sq ft

CO2 Sensor Location: None Ballast Factor: 1.0 Room Type:Conditioned

Pct Pct Adi Pct Rad Glass Temp/ Sen/ Rm/ Ret/ Frc/

Room Exhaust:

Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Type / Alpha Energy Type		Shade Coef	U Value Btu/h·ft².°F	External Shading	Internal Shading	Grnd Refl	Cool Tmp	Heat Tmp	Perm Loss Len Coef
Roof - 1	89 ft²	180	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None				
Roof - 2	38 ft²	0	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None				
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)		None							100	100	0 60.00

Room Description: 107 EXAMS ROOM 4

GENERAL INFORMATION

Zone Description: Zone - 1-2-4

System Description: AHU PEOPLE **AIRFLOW INFORMATION**

Vav Sched: Available (100%)

Aux Supply: To be calculated

Rm Exh Sched: Available (100%)

Supply: To be calculated

Floor Area: 117 ft² FIr-FIr Height: 12.0 ft People Type: General Office Space Cooling Heating # of People: 2 People Plenum Height: 3.0 ft Height Above Flr: Vent Type: None None Slab Cnstr Type: 4* LW Concrete People Sensible: 250 Btu/h Vent Value: 0.00 cfm 0.00 cfm

Room Mass: Time delay based on actual mass People Latent: 200 Btu/h Vent Schedule: Available (100%)

Ceiling R-Value: 1.786 hr-ft2-°F/Btu People Schedule: Cooling Only (Design) Infil Type: Neutral, Average Const. Neutral, Average Const. Is There Carpet?: YES Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%)

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Workstation: 0.0 workstation/person Design Htg DB / Drift Point: 70.0 °F / 64.0 °F Vav Airflow: Design Relative Humidity: 50 % Vav Sched: Available (100%) LIGHTS

Moisture Capacitance: Medium Supply: To be calculated To be calculated Lighting Type: Recessed fluorescent, not vented, 80% load Clg Tstat: None Aux Supply: To be calculated To be calculated to space

Htg Tstat: None Room Exhaust: Fixture Type: RECFL-NV Rm Exh Sched: Available (100%) Thermostat Location:Room Floor Multiplier: 1 % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Humidistat Location:Room Room Multiplier: 1

Lighting Amount: 0.800 W/sq ft CO2 Sensor Location: None

Room Type:Conditioned Ballast Factor: 1.0

Glass Frc/ Ret/ Temp/ Sen/ Rm/ U Value Shade U Value Area/ Const Type / Type / Area External Internal Grnd Cool Heat Perm Loss Tilt Schedule Btu/h·ft².°F Alpha Energy Type ft² Btu/h·ft2.°F Shading Description Amount Dir Coef Shading Refl Tmp Tmp Len Coef Roof - 1 127 ft² 67 R-30 Roof 0.0314 0.90 Overhang - None None Misc Load 1 1.00 W/sa ft Cooling Only (Design) 100 100 0 60.00 None

Project Name: HealthFirst Medico

Dataset Name: H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC Adj

Pct

Pct

Pct

Rad

To be calculated

To be calculated

ROOM BY ROOM

By RLF

Room Description: 108 EXAM ROOM 5

Zone Description: Zone - 1-2-4

GENERAL INFORMATION PEOPLE

Plenum Height: 3.0 ft Height Above FIr: Slab Cnstr Type: 4* LW Concrete

FIr-FIr Height: 12.0 ft

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Floor Area: 117 ft²

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

System Description: AHU

System Description: AHU

Det

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

			Glass			Adj - Temp/	Sen/ Rm/	Ret/ Frc/
	Area/ Const Type /	U Value Type /	Area Shade U Value	External	Internal	Grnd		Perm Loss
Description	Amount Dir Tilt Schedule	Btu/h·ft².°F Alpha Energy Type	ft² Coef Btu/h·ft².°F	Shading	Shading	Refl	Tmp Tmp	Len Coef
Roof - 1	127 ft ² 0 67 R-30 Roof	0.0314 0.90	0 0	Overhang - None	None			<u> </u>

Misc Load 1 1.00 W/sa ft Cooling Only (Design) None 100 100 0 60.00

Room Description: 103 RECEPTION/SCHEDULING

GENERAL INFORMATION

Floor Area: 325 ft² FIr-FIr Height: 12.0 ft

Plenum Height: 3.0 ft Height Above FIr: Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft²-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Cla Tstat: None Htg Tstat: None

Thermostat Location:Room Humidistat Location:Room

CO2 Sensor Location: None

Floor Multiplier: 1 Room Multiplier: 1

Room Type:Conditioned

Zone Description: Zone - 1-2-5

PEOPLE People Type: General Office Space

of People: 4 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION Cooling Heating

Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

									Glass			. Temp/	Sen/	Rm/		Frc/
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft²·°F	Alpha	Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft².°F	External Shading	Internal Shading	Grnd Refl		Heat Tmp	Perm	
Roof - 1	299 ft²	180	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
Roof - 2	53 ft ²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
Misc Load 1	1.00 W/sq ft		Cooling Only (Design)			None							100	100	0 6	00.06

Project Name: HealthFirst Medico

H:\21184\ME\CALCULATIONS\LOAD CALCULATIONS\TRACE\21184.TRC Dataset Name:

ROOM BY ROOM

By RLF

Room Description: 110 EXAM ROOM 6

Zone Description: Zone - 1-2-5

System Description: AHU

GENERAL INFORMATION Floor Area: 116 ft2 FIr-FIr Height: 12.0 ft

Plenum Height: 3.0 ft Height Above FIr: Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Ceiling R-Value: 1.786 hr·ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned **PEOPLE**

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

					¬ Temp/	Sen/	Rm/	Ret/ I	Frc/			
	Area/	Const Type /	U Value Typ	e / Area	Shade U Value	External	Internal	Grnd	Cool	Heat	Perm L	_oss
Description	Amount	Dir Tilt Schedule	Btu/h·ft²·°F Alpha Ene	ergy Type ft²	Coef Btu/h·ft²·°F	Shading	Shading	Refl	Tmp	Tmp	Len C	Coef
Roof - 1	50 ft ²	0 67 R-30 Roof	0.0314 0.90	0		Overhang - None	None					
Roof - 2	76 ft²	180 67 R-30 Roof	0.0314 0.90	0		Overhang - None	None					
Misc Load 1	1.00 W/sq ft	Cooling Only (Design)	Non	е					100	100	0 60	0.00

Room Description: 127 CLEAN STORAGE

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F

Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Room Type:Conditioned

Floor Area: 92 ft2

Slab Cnstr Type: 4* LW Concrete

Design Relative Humidity:

Thermostat Location: Room

Humidistat Location:Room

CO2 Sensor Location: None

Moisture Capacitance:

Ceiling R-Value: 1.786 hr-ft2-°F/Btu

Plenum Height: 3.0 ft

Is There Carpet?: YES

Clg Tstat: None

Htg Tstat: None

GENERAL INFORMATION

50 %

Medium

Room Mass: Time delay based on actual mass

FIr-FIr Height: 12.0 ft

Floor Multiplier: 1

Room Multiplier: 1

Height Above FIr:

Zone Description: Zone - 1-2-5 PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design) Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

System Description: AHU

Pct Pct

Pct Rad

AIRFLOW INFORMATION Heating None 0.00 cfm

Vent Schedule: Available (100%)

Vent Type: None

Vent Value: 0.00 cfm

Cooling

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow: Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

			Glass		Adj Pct Pct Pct Rad Temp/ Sen/ Rm/ Ret/ Frc/
Description	Area/ Const Type / Amount Dir Tilt Schedule	U Value Type / Btu/h·ft²-°F Alpha Energy Type	Area Shade U Value External ft² Coef Btu/h·ft².°F Shading	Internal Shading	Grnd Cool Heat Perm Loss Refl Tmp Tmp Len Coef
Roof - 1	100 ft ² 270 67 R-30 Roof	0.0314 0.90	0 Overhang - None	None	

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 128 COMM

Zone Description: Zone - 1-2-5

System Description: AHU

GENERAL INFORMATION

Floor Area: 90 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Humidistat Location:Room

CO2 Sensor Location: None Room Type:Conditioned

Floor Multiplier: 1

Room Multiplier: 1

PEOPLE

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

								Glass			Adj T/	Pct C/	Pct		Rad
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft².°F	Type / Alpha Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft².°F	External Shading	Internal Shading	Temp/ Grnd Refl	Sen/ Cool Tmp	Rm/ Heat Tmp	Ret/ Perm Len	
Roof - 1	62 ft²	0	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None	·				
Roof - 2	68 ft²	180	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
Roof - 3	9 ft²	270	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
Misc Load 1	12,000 Btuh		Cooling Only (Design)		None							100	100	0 6	00.06

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 132 CORR SOUTH

Zone Description: Zone - 1-2-5

System Description: AHU

INFORMATION

Floor Area: 166 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned **PEOPLE**

People Type: General Office Space

of People: 0 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space

Fixture Type: RECFL-NV % Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

				Glass					Temp/	Sen		Ret/	Frc/			
Description	Area/ Amount	Dir	Const Type / Tilt Schedule	U Value Btu/h·ft².°F		Type / Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl		ol Heat	Perm	Loss
Roof - 2	70 ft²	180	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None	· ·				
Roof - 3	109 ft²	270	67 R-30 Roof	0.0314	0.90		0			Overhang - None	None					
SOUTH	66 ft²	180	0 ASHRAE 90.1 MASS	0.1374	0.90											
Opening - 1			Window			90.1-2013 Window	16	0.29	0.57	Overhang -	None	0.00				
Floor - 1															6	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 104 EXAM ROOM 1

Zone Description: Zone - 1-2-6 **GENERAL INFORMATION**

PEOPLE

System Description: AHU

Floor Area: 117 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None

Room Type:Conditioned

People Type: General Office Space

of People: 2 People People Sensible: 250 Btu/h People Latent: 200 Btu/h

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

to space Fixture Type: RECFL-NV

% Load to RA: 20 % Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

	Glass									Aaj Temp/	Sen/	Pct Rm/	Pct Ret/	Rad Frc/
Description	Area/ Amount D	Const Type / Dir Tilt Schedule	U Value Btu/h·ft².°F	Type / Alpha Energy Type	Area ft²	Shade Coef	U Value Btu/h·ft²·°F	External Shading	Internal Shading	Grnd Refl	Cool Tmp	Heat	Perm	
Roof - 1	127 ft² 18	80 67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
SOUTH	154 ft²	0 0 ASHRAE 90.1 MASS	0.1374	0.90										
Opening - 1		Door		90.1-13 Min Swinging	42	0.00	0.70	Overhang - None	None	0.00				
Misc Load 1	1.00 W/sq ft	Cooling Only (Design)		None							100	100	0 6	00.06
Floor - 1													13	0.50

Project Name: HealthFirst Medico

ROOM BY ROOM

By RLF

Room Description: 129 CORR SOUTH

Zone Description: Zone - 1-2-6

System Description: AHU

GENERAL INFORMATION

Floor Area: 155 ft2 FIr-FIr Height: 12.0 ft Plenum Height: 3.0 ft Height Above Flr:

Slab Cnstr Type: 4* LW Concrete

Room Mass: Time delay based on actual mass

Cpiling R-Value: 1.786 hr-ft2-°F/Btu

Is There Carpet?: YES

Design Clg DB / Drift Point: 75.0 °F / 81.0 °F Design Htg DB / Drift Point: 70.0 °F / 64.0 °F

Design Relative Humidity: 50 % Moisture Capacitance: Medium

Clg Tstat: None Htg Tstat: None

Floor - 1

Thermostat Location: Room Floor Multiplier: 1 Humidistat Location:Room Room Multiplier: 1

CO2 Sensor Location: None Room Type:Conditioned

People Schedule: Cooling Only (Design)

Workstation: 0.0 workstation/person

People Type: General Office Space

of People: 0 People

People Sensible: 250 Btu/h

People Latent: 200 Btu/h

LIGHTS

Lighting Type: Recessed fluorescent, not vented, 80% load

PEOPLE

to space Fixture Type: RECFL-NV

% Load to RA: 20 %

Lighting Schedule: Cooling Only (Design)

Lighting Amount: 0.800 W/sq ft

Ballast Factor: 1.0

AIRFLOW INFORMATION

Cooling Heating Vent Type: None None Vent Value: 0.00 cfm 0.00 cfm

Vent Schedule: Available (100%)

Infil Type: Neutral, Average Const. Neutral, Average Const. Infil Value: 0.60 air changes/hr 0.60 air changes/hr

Infil Schedule: Available (100%)

Vav Airflow:

Vav Sched: Available (100%)

Supply: To be calculated To be calculated Aux Supply: To be calculated To be calculated

Room Exhaust:

Rm Exh Sched: Available (100%)

											Adj	Pct	Pct	Pct	Rad
								Glass			¬ Temp/	Sen/	Rm/	Ret/	Frc/
	Area/		Const Type /	U Value	Type /	Area	Shade	U Value	External	Internal	Grnd	Cool	Heat	Perm	Loss
Description	Amount	Dir	Tilt Schedule	Btu/h·ft².°F	Alpha Energy Type	ft²	Coef	Btu/h·ft².°F	Shading	Shading	Refl	Tmp	Tmp	Len	Coef
Roof - 2	168 ft²	180	67 R-30 Roof	0.0314	0.90	0			Overhang - None	None					
SOUTH	66 ft²	180	0 ASHRAE 90.1 MASS	0.1374	0.90										

15 0.50

Project Name: HealthFirst Medico